

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT				
APPLICATION FOR PERMIT TO DRILL						1. WELL NAME and NUMBER Powvitch 2-24-3-2WH				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT WILDCAT				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR NEWFIELD PRODUCTION COMPANY						7. OPERATOR PHONE 435 646-4825				
8. ADDRESS OF OPERATOR Rt 3 Box 3630 , Myton, UT, 84052						9. OPERATOR E-MAIL mcrozier@newfield.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) 14-20-H62-6176			11. MINERAL OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input checked="" type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input type="checkbox"/> INDIAN <input checked="" type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee')						14. SURFACE OWNER PHONE (if box 12 = 'fee')				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN') Heirs of Annie Powvitch - UTE			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input type="checkbox"/> HORIZONTAL <input checked="" type="checkbox"/>				
20. LOCATION OF WELL		FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN		
LOCATION AT SURFACE		75 FNL 2332 FEL		NWNE	24	3.0 S	2.0 W	U		
Top of Uppermost Producing Zone		75 FNL 2332 FEL		NWNE	24	3.0 S	2.0 W	U		
At Total Depth		660 FSL 1980 FEL		SWSE	24	3.0 S	2.0 W	U		
21. COUNTY DUCESNE			22. DISTANCE TO NEAREST LEASE LINE (Feet) 75			23. NUMBER OF ACRES IN DRILLING UNIT 40				
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 0			26. PROPOSED DEPTH MD: 12726 TVD: 8249				
27. ELEVATION - GROUND LEVEL 5109			28. BOND NUMBER RLB0010462			29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 437478				
Hole, Casing, and Cement Information										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
COND	17.5	14	0 - 60	37.0	H-40 ST&C	0.0	Class G	35	1.17	15.8
SURF	12.25	9.625	0 - 2500	36.0	J-55 LT&C	8.3	Type III	216	3.33	11.0
							Type III	95	1.9	13.0
I1	8.75	7	0 - 8751	26.0	P-110 Other	11.5	35/65 Poz	241	2.59	11.5
							50/50 Poz	282	1.62	13.0
PROD	6.125	4.5	7831 - 12726	13.5	P-110 Other	11.5	No Used	0	0.0	0.0
ATTACHMENTS										
VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Don Hamilton				TITLE Permitting Agent			PHONE 435 719-2018			
SIGNATURE				DATE 12/21/2012			EMAIL starpoint@etv.net			
API NUMBER ASSIGNED 43013519420000				APPROVAL Permit Manager						

Newfield Production Company**2-24-3-2WH****Surface Hole Location: 75' FNL, 2332' FEL, Section 24, T3S, R2W****Bottom Hole Location: 660' FSL, 1980' FEL, Section 24, T3S, R2W****Duchesne County, UT****Drilling Program****1. Formation Tops**

Uinta	surface
Green River	3,312'
Garden Gulch member	6,105'
Uteland Butte	8,352'
Lateral TD	8,249' TVD / 12,726' MD

2. Depth to Oil, Gas, Water, or Minerals

Base of moderately saline	1,259'	(water)
Green River	6,105' - 8,249'	(oil)

3. Pressure Control

<u>Section</u>	<u>BOP Description</u>
----------------	------------------------

Surface	12-1/4" diverter
---------	------------------

Interm/Prod	The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc for a 5M system.
-------------	---

A 5M BOP system will consist of 2 ram preventers (double or two singles) and an annular preventer (see attached diagram). A choke manifold rated to at least 5,000 psi will be used.

4. Casing

Description	Interval		Weight (ppf)	Grade	Coupl	Pore Press @ Shoe	MW @ Shoe	Frac Grad @ Shoe	Safety Factors		
	Top	Bottom (TVD/MD)							Burst	Collapse	Tension
Conductor 14	0'	60'	37	H-40	Weld	--	--	--	--	--	--
Surface 9 5/8	0'	2,500'	36	J-55	LTC	8.33	8.33	12	3,520	2,020	453,000
Intermediate 7	0'	8,384' 8,751'	26	P-110	BTC	11	11.5	15	2.51	2.54	5.03
Production 4 1/2	7,831'	8,249' 12,726'	13.5	P-110	BTC	11	11.5	--	9,960	6,210	830,000
									2.52	1.49	3.65
									12,410	10,670	422,000
									3.19	2.60	6.39

Assumptions:

Surface casing MASP = (frac gradient + 1.0 ppg) - (gas gradient)

Intermediate casing MASP = (reservoir pressure) - (gas gradient)

Production casing MASP = (reservoir pressure) - (gas gradient)

All collapse calculations assume fully evacuated casing with a gas gradient

All tension calculations assume air weight of casing

Gas gradient = 0.1 psi/ft

All casing shall be new.

All casing strings shall have a minimum of 1 centralizer on each of the bottom 3 joints.

5. Cement

Job	Hole Size	Fill	Slurry Description	ft ³	OH excess	Weight (ppg)	Yield (ft ³ /sk)
				sacks			
Conductor	17 1/2	60'	Class G w/ 2% KCl + 0.25 lbs/sk Cello Flake	41	15%	15.8	1.17
				35			
Surface Lead	12 1/4	2,000'	Type III + .125 lbs/sk Cello Flakes	720	15%	11.0	3.33
				216			
Surface Tail	12 1/4	500'	Type III + .125 lbs/sk Cello Flakes	180	15%	13.0	1.9
				95			
Intermediate Lead	8 3/4	3,605'	Premium - 65% Class G / 35% Poz + 10% Bentonite	623	15%	11.5	2.59
				241			
Intermediate Tail	8 3/4	2,646'	50/50 Poz/Class G + 1% bentonite	457	15%	13.0	1.62
				282			
Production	6 1/8	--	Liner will not be cemented. It will be isolated with a liner top packer.	--	--	--	--
				--			

The surface casing will be cemented to surface. In the event that cement does not reach surface during the primary cement job, a remedial job will be performed.

Actual cement volumes for the intermediate casing string will be calculated from an open hole caliper log, plus 15% excess.

The cement slurries will be adjusted for hole conditions and blend test results.

The production liner will be left uncemented. Individual frac stages will be isolated with open hole packers. A liner top hanger and packer will be installed 50' above KOP.

6. Type and Characteristics of Proposed Circulating Medium

<u>Interval</u>	<u>Description</u>
Surface - 2,500'	An air and/or fresh water system will be utilized. If an air rig is used, the blooie line discharge may be less than 100' from the wellbore in order to minimize location size. The blooie line is not equipped with an automatic igniter. The air compressor may be located less than 100' from the well bore due to the low possibility of combustion with the air/dust mixture. Water will be on location to be used as kill fluid, if necessary.
2,500' - TD	A water based mud system will be utilized. Hole stability may be improved with additions of KCl or a similar inhibitive substance. In order to control formation pressure the system will be weighted with additions of bentonite, and

if conditions warrant, with barite.

Anticipated maximum mud weight is 11.5 ppg.

7. Logging, Coring, and Testing

Logging: A dual induction, gamma ray, and caliper log will be run in the intermediate section from the top of the curve to the base of the surface casing. A compensated neutron/formation density log will be run in the intermediate section from the top of the curve to the top of the Garden Gulch formation. A cement bond log will be run from the top of the curve to the cement top behind the intermediate casing.

Cores: As deemed necessary.

DST: There are no DST's planned for this well.

8. Anticipated Abnormal Pressure or Temperature

Maximum anticipated bottomhole pressure will be approximately equal to total depth (feet) multiplied by a 0.57 psi/ft gradient.

$$8,249' \times 0.57 \text{ psi/ft} = 4718 \text{ psi}$$

No abnormal temperature is expected. No H₂S is expected.

9. Other Aspects

An 8-3/4" vertical hole will be drilled to a kick off point of 7,881' .

Directional tools will then be used to build to 92.10 degrees inclination.

The 7" intermediate casing string will be set once the well is landed horizontally in the target zone.

The lateral will be drilled to the bottomhole location shown on the plat.


A liner with a system of open hole packers will be used to provide multi-stage frac isolation in the lateral. The top of the liner will be place 50' above KOP and will be isolated with a liner top packer.

Newfield requests the following variances from Onshore Order #2:


- Variance from Onshoer Order #2, III.E.1

Refer to Newfield Production Company Standard Operating Practices "Ute Tribal Green River Development Program" paragraph 9.0

Typical 5M BOP stack configuration



Typical 5M choke manifold configuration



T3S, R2W, U.S.B.&M.

NEWFIELD EXPLORATION COMPANY


Well location, POWVITCH #2-24-3-2WH, located as shown in the NW 1/4 NE 1/4 of Section 24, T3S, R2W, U.S.B.&M., Duchesne County, Utah.

BASIS OF ELEVATION

SPOT ELEVATION LOCATED AT THE SOUTHEAST CORNER OF SECTION 20, T3S, R2W, U.S.B.&M. TAKEN FROM THE MYTON, QUADRANGLE, UTAH, DUCHESNE COUNTY, 7.5 MINUTE QUAD (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5148 FEET.

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

ROBERT L. KAY
REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

REVISED: 04-03-12


UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 02-10-12	DATE DRAWN: 02-15-12
PARTY J.C. G.O. J.J.	REFERENCES G.L.O. PLAT	
WEATHER COOL	FILE NEWFIELD EXPLORATION COMPANY	

LEGEND:

- └─┘ = 90° SYMBOL
● = PROPOSED WELL HEAD.
▲ = SECTION CORNERS LOCATED.

NAD 83 (TARGET BOTTOM HOLE)	NAD 83 (SURFACE LOCATION)
LATITUDE = 40°12'08.30" (40.202306)	LATITUDE = 40°12'53.38" (40.214828)
LONGITUDE = 110°03'18.95" (110.055264)	LONGITUDE = 110°03'24.21" (110.056725)
NAD 27 (TARGET BOTTOM HOLE)	NAD 27 (SURFACE LOCATION)
LATITUDE = 40°12'08.44" (40.202344)	LATITUDE = 40°12'53.53" (40.214869)
LONGITUDE = 110°03'16.41" (110.054558)	LONGITUDE = 110°03'21.67" (110.056019)



RECEIVED: December 21, 2012

 PROPOSED LOCATION

Utah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

POWVITCH #2-24-3-2WH
SECTION 24, T3S, R2W, U.S.B.&M.
75' FNL 2332' FEL


ACCESS ROAD MAP

02 14 12
MONTH DAY YEAR

SCALE: 1:100,000	DRAWN BY: B.D.H.	REV: 04-05-12 C.I.
------------------	------------------	--------------------

A
TOPO





LEGEND:

- EXISTING ROAD
- - - PROPOSED ACCESS ROAD
- * * * * * EXISTING FENCE
- - - - - EXISTING POWER LINE
- - - - - EXISTING FIBER OPTIC LINE



Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



NEWFIELD EXPLORATION COMPANY


POWVITCH #2-24-3-2WH
SECTION 24, T3S, R2W, U.S.B.&M.
75' FNL 2332' FEL

ACCESS ROAD
MAP

02 14 12
 MONTH DAY YEAR

B
TOPO

SCALE: 1" = 2000' DRAWN BY: B.D.H. REV: 04-05-12 C.I.

**LEGEND:**

- ⊗ DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED



Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813

**NEWFIELD EXPLORATION COMPANY**


POWVITCH #2-24-3-2WH
SECTION 24, T3S, R2W, U.S.B.&M.
75' FNL 2332' FEL

**TOPOGRAPHIC
MAP**

02 14 12
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: B.D.H. REV: 04-05-12 C.I.





APPROXIMATE TOTAL PIPELINE DISTANCE = 1,870' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- - - - - PROPOSED PIPELINE
- - - - - PROPOSED PIPELINE (SERVICING OTHER WELLS)



Utah Engineering & Land Surveying
 85 South 200 East Vernal, Utah 84078
 (435) 789-1017 * FAX (435) 789-1813



NEWFIELD EXPLORATION COMPANY

POWVITCH #2-24-3-2WH
SECTION 24, T3S, R2W, U.S.B.&M.
75' FNL 2332' FEL

TOPOGRAPHIC
MAP

02 14 12
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: B.D.H. REV: 09-26-12 C.I.

D
TOPO


Powvitch 2-24-3-2WH

SHL 75' FNL & 2332' FEL

Top of Producing Interval 660' FNL & 1980' FEL

BHL 660' FSL & 1980' FEL

Township 3 South, Range 2 West, Section 24: W½E½



Newfield Exploration Company

Duchesne County, UT

Sec. 24-T3S-R2W

2-24-3-2WH

Plan A Rev 0 Permit

Plan: Plan A Rev 0 Proposal - Permit Only

Sperry Drilling Services

Proposal Report

30 November, 2012

Well Coordinates: 2,209,874.11 N, 622,844.65 E (40° 12' 53.38" N, 110° 03' 24.21" W)

Ground Level: 5,109.00 ft

Local Coordinate Origin:

Centered on Well 2-24-3-2WH

Viewing Datum:

RKB 18' @ 5127.0ft (Original Well Elev)

TVDs to System:

N

North Reference:

True

Unit System:

Class Units

Geodetic Scale Factor Applied

Version: 5000.1 Build: 61

HALLIBURTON

RECEIVED: December 21, 2012

Project: Duchesne County, UT

Site: Sec. 24-T3S-R2W

Well: 2-24-3-2WH

Wellbore: Plan A Rev 0 Permit

Design: Plan A Rev 0 Proposal - Permit Only

Newfield Exploration Company

HALLIBURTON




Sperry Drilling

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	VSec	Target
1	0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.0	
2	3000.0	0.00	0.00	3000.0	0.0	0.0	0.00	0.00	0.0	
3	3466.7	7.00	93.00	3465.5	-1.5	28.4	1.50	93.00	4.0	
4	5699.7	7.00	93.00	5681.9	-15.7	300.2	0.00	0.00	42.4	
5	6166.3	0.00	0.00	6147.4	-17.2	328.6	1.50	180.00	46.4	
6	7881.4	0.00	0.00	7862.4	-17.2	328.6	0.00	0.00	46.4	
7	8691.4	89.10	179.00	8383.2	-529.8	337.6	11.00	179.00	557.8	
8	8751.4	89.10	179.00	8384.1	-589.8	338.6	0.00	0.00	617.6	
9	8901.4	89.10	179.00	8386.5	-739.8	341.3	0.00	0.00	767.2	
10	9001.4	92.10	179.00	8385.5	-839.7	343.0	3.00	0.00	867.0	
11	12726.5	92.10	179.00	8249.0	-4561.8	408.1	0.00	0.00	4580.0	2-24-3-2WH_BHL Tgt

WELLBORE TARGET DETAILS (MAP CO-ORDINATES AND LAT/LONG)

Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Shape
2-24-3-2WH_Section Lines	0.0	0.0	0.0	2209874.12	622844.65	40° 12' 53.380 N	110° 3' 24.210 W	Polygon
2-24-3-2WH_Setback Lines	0.0	0.0	0.0	2209874.12	622844.65	40° 12' 53.380 N	110° 3' 24.210 W	Polygon
2-24-3-2WH_SHL Tgt	0.0	0.0	0.0	2209874.12	622844.65	40° 12' 53.380 N	110° 3' 24.210 W	Point
2-24-3-2WH_BHL Tgt	8249.0	-4561.8	408.1	2208485.97	622991.46	40° 12' 8.300 N	110° 3' 18.950 W	Point



WELL DETAILS: 2-24-3-2WH

Ground Level: 5109.0			
Northing	Easting	Latitude	Longitude
2209874.11	622844.65	40° 12' 53.380 N	110° 3' 24.210 W

Plan A Rev 0 Proposal - (2-24-3-2WH)

Created By: Ryan Sprague Date: 11/30/2012

Checked: _____ Date: _____

RECEIVED: December 21, 2012

HALLIBURTON

Duchesne County, UT

Plan Report for 2-24-3-2WH - Plan A Rev 0 Proposal - Permit Only

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	Toolface Azimuth (°)
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2-24-3-2WH_Section Lines - 2-24-3-2WH_Setback Lines - 2-24-3-2WH_SHL Tgt										
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,100.0	0.00	0.00	1,100.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,200.0	0.00	0.00	1,200.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,300.0	0.00	0.00	1,300.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,400.0	0.00	0.00	1,400.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,500.0	0.00	0.00	1,500.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,600.0	0.00	0.00	1,600.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,700.0	0.00	0.00	1,700.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,800.0	0.00	0.00	1,800.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
1,900.0	0.00	0.00	1,900.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,000.0	0.00	0.00	2,000.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,100.0	0.00	0.00	2,100.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,200.0	0.00	0.00	2,200.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,300.0	0.00	0.00	2,300.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,400.0	0.00	0.00	2,400.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,500.0	0.00	0.00	2,500.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,600.0	0.00	0.00	2,600.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,700.0	0.00	0.00	2,700.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,800.0	0.00	0.00	2,800.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
2,900.0	0.00	0.00	2,900.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
3,000.0	0.00	0.00	3,000.0	0.0	0.0	0.0	0.00	0.00	0.00	0.00
3,100.0	1.50	93.00	3,100.0	-0.1	1.3	0.2	1.50	1.50	0.00	93.00
3,200.0	3.00	93.00	3,199.9	-0.3	5.2	0.7	1.50	1.50	0.00	0.00
3,300.0	4.50	93.00	3,299.7	-0.6	11.8	1.7	1.50	1.50	0.00	0.00
3,400.0	6.00	93.00	3,399.3	-1.1	20.9	3.0	1.50	1.50	0.00	0.00
3,466.7	7.00	93.00	3,465.5	-1.5	28.4	4.0	1.50	1.50	0.00	0.00
3,500.0	7.00	93.00	3,498.6	-1.7	32.5	4.6	0.00	0.00	0.00	0.00
3,600.0	7.00	93.00	3,597.8	-2.3	44.7	6.3	0.00	0.00	0.00	0.00
3,700.0	7.00	93.00	3,697.1	-3.0	56.8	8.0	0.00	0.00	0.00	0.00
3,800.0	7.00	93.00	3,796.4	-3.6	69.0	9.8	0.00	0.00	0.00	0.00
3,900.0	7.00	93.00	3,895.6	-4.3	81.2	11.5	0.00	0.00	0.00	0.00
4,000.0	7.00	93.00	3,994.9	-4.9	93.3	13.2	0.00	0.00	0.00	0.00
4,100.0	7.00	93.00	4,094.1	-5.5	105.5	14.9	0.00	0.00	0.00	0.00
4,200.0	7.00	93.00	4,193.4	-6.2	117.7	16.6	0.00	0.00	0.00	0.00
4,300.0	7.00	93.00	4,292.6	-6.8	129.9	18.3	0.00	0.00	0.00	0.00
4,400.0	7.00	93.00	4,391.9	-7.4	142.0	20.1	0.00	0.00	0.00	0.00
4,500.0	7.00	93.00	4,491.1	-8.1	154.2	21.8	0.00	0.00	0.00	0.00
4,600.0	7.00	93.00	4,590.4	-8.7	166.4	23.5	0.00	0.00	0.00	0.00
4,700.0	7.00	93.00	4,689.6	-9.4	178.5	25.2	0.00	0.00	0.00	0.00
4,800.0	7.00	93.00	4,788.9	-10.0	190.7	26.9	0.00	0.00	0.00	0.00
4,900.0	7.00	93.00	4,888.2	-10.6	202.9	28.7	0.00	0.00	0.00	0.00
5,000.0	7.00	93.00	4,987.4	-11.3	215.0	30.4	0.00	0.00	0.00	0.00
5,100.0	7.00	93.00	5,086.7	-11.9	227.2	32.1	0.00	0.00	0.00	0.00
5,200.0	7.00	93.00	5,185.9	-12.5	239.4	33.8	0.00	0.00	0.00	0.00
5,300.0	7.00	93.00	5,285.2	-13.2	251.6	35.5	0.00	0.00	0.00	0.00
5,400.0	7.00	93.00	5,384.4	-13.8	263.7	37.3	0.00	0.00	0.00	0.00
5,500.0	7.00	93.00	5,483.7	-14.5	275.9	39.0	0.00	0.00	0.00	0.00

HALLIBURTON**Plan Report for 2-24-3-2WH - Plan A Rev 0 Proposal - Permit Only**

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	Toolface Azimuth (°)
5,600.0	7.00	93.00	5,582.9	-15.1	288.1	40.7	0.00	0.00	0.00	0.00
5,699.7	7.00	93.00	5,681.9	-15.7	300.2	42.4	0.00	0.00	0.00	0.00
5,800.0	5.49	93.00	5,781.6	-16.3	311.1	44.0	1.50	-1.50	0.00	180.00
5,900.0	3.99	93.00	5,881.3	-16.7	319.4	45.1	1.50	-1.50	0.00	180.00
6,000.0	2.49	93.00	5,981.1	-17.0	325.0	45.9	1.50	-1.50	0.00	180.00
6,100.0	0.99	93.00	6,081.0	-17.2	328.1	46.4	1.50	-1.50	0.00	180.00
6,166.3	0.00	0.00	6,147.4	-17.2	328.6	46.4	1.50	-1.50	0.00	-180.00
6,200.0	0.00	0.00	6,181.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
6,300.0	0.00	0.00	6,281.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
6,400.0	0.00	0.00	6,381.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
6,500.0	0.00	0.00	6,481.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
6,600.0	0.00	0.00	6,581.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
6,700.0	0.00	0.00	6,681.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
6,800.0	0.00	0.00	6,781.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
6,900.0	0.00	0.00	6,881.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
7,000.0	0.00	0.00	6,981.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
7,100.0	0.00	0.00	7,081.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
7,200.0	0.00	0.00	7,181.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
7,300.0	0.00	0.00	7,281.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
7,400.0	0.00	0.00	7,381.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
7,500.0	0.00	0.00	7,481.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
7,600.0	0.00	0.00	7,581.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
7,700.0	0.00	0.00	7,681.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
7,800.0	0.00	0.00	7,781.0	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
7,881.4	0.00	0.00	7,862.4	-17.2	328.6	46.4	0.00	0.00	0.00	0.00
Kickoff @ 7881.4MD, 7862.4TVD										
7,900.0	2.05	179.00	7,881.0	-17.6	328.6	46.8	11.02	11.02	0.00	179.00
7,950.0	7.55	179.00	7,930.8	-21.7	328.7	50.9	11.00	11.00	0.00	0.00
8,000.0	13.05	179.00	7,980.0	-30.7	328.9	59.9	11.00	11.00	0.00	0.00
8,050.0	18.55	179.00	8,028.1	-44.3	329.1	73.4	11.00	11.00	0.00	0.00
8,100.0	24.05	179.00	8,074.7	-62.4	329.4	91.5	11.00	11.00	0.00	0.00
8,150.0	29.55	179.00	8,119.3	-85.0	329.8	114.0	11.00	11.00	0.00	0.00
8,200.0	35.05	179.00	8,161.5	-111.7	330.3	140.7	11.00	11.00	0.00	0.00
8,250.0	40.55	179.00	8,201.0	-142.3	330.8	171.2	11.00	11.00	0.00	0.00
8,300.0	46.05	179.00	8,237.4	-176.6	331.4	205.4	11.00	11.00	0.00	0.00
8,350.0	51.55	179.00	8,270.3	-214.2	332.1	242.9	11.00	11.00	0.00	0.00
8,400.0	57.05	179.00	8,299.5	-254.8	332.8	283.4	11.00	11.00	0.00	0.00
8,450.0	62.55	179.00	8,324.6	-297.9	333.5	326.5	11.00	11.00	0.00	0.00
8,500.0	68.05	179.00	8,345.5	-343.3	334.3	371.8	11.00	11.00	0.00	0.00
8,550.0	73.55	179.00	8,361.9	-390.5	335.2	418.8	11.00	11.00	0.00	0.00
8,600.0	79.05	179.00	8,373.8	-439.1	336.0	467.3	11.00	11.00	0.00	0.00
8,650.0	84.55	179.00	8,380.9	-488.6	336.9	516.6	11.00	11.00	0.00	0.00
8,691.4	89.10	179.00	8,383.2	-529.9	337.6	557.8	10.99	10.99	0.00	0.00
End Build @ 8691.4MD, 8383.2TVD										
8,700.0	89.10	179.00	8,383.3	-538.5	337.7	566.4	0.00	0.00	0.00	0.00
8,751.4	89.10	179.00	8,384.1	-589.9	338.6	617.7	0.00	0.00	0.00	0.00
7" Casing Pt. @ 8751.4MD, 8384.1TVD										
8,800.0	89.10	179.00	8,384.9	-638.4	339.5	666.2	0.00	0.00	0.00	0.00
8,901.4	89.10	179.00	8,386.5	-739.8	341.3	767.2	0.00	0.00	0.00	0.00
9,001.4	92.10	179.00	8,385.5	-839.7	343.0	867.0	3.00	3.00	0.00	0.00
9,100.0	92.10	179.00	8,381.8	-938.3	344.7	965.3	0.00	0.00	0.00	0.00
9,200.0	92.10	179.00	8,378.2	-1,038.2	346.5	1,065.0	0.00	0.00	0.00	0.00
9,300.0	92.10	179.00	8,374.5	-1,138.1	348.2	1,164.6	0.00	0.00	0.00	0.00
9,400.0	92.10	179.00	8,370.9	-1,238.1	350.0	1,264.3	0.00	0.00	0.00	0.00
9,500.0	92.10	179.00	8,367.2	-1,338.0	351.7	1,364.0	0.00	0.00	0.00	0.00
9,600.0	92.10	179.00	8,363.5	-1,437.9	353.5	1,463.7	0.00	0.00	0.00	0.00
9,700.0	92.10	179.00	8,359.9	-1,537.8	355.2	1,563.3	0.00	0.00	0.00	0.00
9,800.0	92.10	179.00	8,356.2	-1,637.7	357.0	1,663.0	0.00	0.00	0.00	0.00
9,900.0	92.10	179.00	8,352.5	-1,737.6	358.7	1,762.7	0.00	0.00	0.00	0.00

HALLIBURTON

Duchesne County, UT

Plan Report for 2-24-3-2WH - Plan A Rev 0 Proposal - Permit Only

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	Toolface Azimuth (°)
10,000.0	92.10	179.00	8,348.9	-1,837.6	360.5	1,862.4	0.00	0.00	0.00	0.00
10,100.0	92.10	179.00	8,345.2	-1,937.5	362.2	1,962.0	0.00	0.00	0.00	0.00
10,200.0	92.10	179.00	8,341.5	-2,037.4	364.0	2,061.7	0.00	0.00	0.00	0.00
10,300.0	92.10	179.00	8,337.9	-2,137.3	365.7	2,161.4	0.00	0.00	0.00	0.00
10,400.0	92.10	179.00	8,334.2	-2,237.2	367.5	2,261.1	0.00	0.00	0.00	0.00
10,500.0	92.10	179.00	8,330.5	-2,337.1	369.2	2,360.7	0.00	0.00	0.00	0.00
10,600.0	92.10	179.00	8,326.9	-2,437.1	371.0	2,460.4	0.00	0.00	0.00	0.00
10,700.0	92.10	179.00	8,323.2	-2,537.0	372.7	2,560.1	0.00	0.00	0.00	0.00
10,800.0	92.10	179.00	8,319.5	-2,636.9	374.5	2,659.8	0.00	0.00	0.00	0.00
10,900.0	92.10	179.00	8,315.9	-2,736.8	376.2	2,759.4	0.00	0.00	0.00	0.00
11,000.0	92.10	179.00	8,312.2	-2,836.7	378.0	2,859.1	0.00	0.00	0.00	0.00
11,100.0	92.10	179.00	8,308.6	-2,936.7	379.7	2,958.8	0.00	0.00	0.00	0.00
11,200.0	92.10	179.00	8,304.9	-3,036.6	381.5	3,058.5	0.00	0.00	0.00	0.00
11,300.0	92.10	179.00	8,301.2	-3,136.5	383.2	3,158.2	0.00	0.00	0.00	0.00
11,400.0	92.10	179.00	8,297.6	-3,236.4	384.9	3,257.8	0.00	0.00	0.00	0.00
11,500.0	92.10	179.00	8,293.9	-3,336.3	386.7	3,357.5	0.00	0.00	0.00	0.00
11,600.0	92.10	179.00	8,290.2	-3,436.2	388.4	3,457.2	0.00	0.00	0.00	0.00
11,700.0	92.10	179.00	8,286.6	-3,536.2	390.2	3,556.9	0.00	0.00	0.00	0.00
11,800.0	92.10	179.00	8,282.9	-3,636.1	391.9	3,656.5	0.00	0.00	0.00	0.00
11,900.0	92.10	179.00	8,279.2	-3,736.0	393.7	3,756.2	0.00	0.00	0.00	0.00
12,000.0	92.10	179.00	8,275.6	-3,835.9	395.4	3,855.9	0.00	0.00	0.00	0.00
12,100.0	92.10	179.00	8,271.9	-3,935.8	397.2	3,955.6	0.00	0.00	0.00	0.00
12,200.0	92.10	179.00	8,268.2	-4,035.7	398.9	4,055.2	0.00	0.00	0.00	0.00
12,300.0	92.10	179.00	8,264.6	-4,135.7	400.7	4,154.9	0.00	0.00	0.00	0.00
12,400.0	92.10	179.00	8,260.9	-4,235.6	402.4	4,254.6	0.00	0.00	0.00	0.00
12,500.0	92.10	179.00	8,257.3	-4,335.5	404.2	4,354.3	0.00	0.00	0.00	0.00
12,600.0	92.10	179.00	8,253.6	-4,435.4	405.9	4,453.9	0.00	0.00	0.00	0.00
12,700.0	92.10	179.00	8,249.9	-4,535.3	407.7	4,553.6	0.00	0.00	0.00	0.00
12,726.5	92.10	179.00	8,249.0	-4,561.8	408.1	4,580.0	0.00	0.00	0.00	0.00

TD at 12726.5 - 2-24-3-2WH_BHL Tgt

Plan Annotations

Measured Depth (ft)	Vertical Depth (ft)	Local Coordinates +N/-S (ft)	+E/-W (ft)	Comment
7,881.4	7,862.4	0.0	0.0	Kickoff @ 7881.4MD, 7862.4TVD
8,691.4	8,383.2	-1.5	28.4	End Build @ 8691.4MD, 8383.2TVD
8,751.4	8,384.1	-15.7	300.2	7"Casing Pt. @ 8751.4MD, 8384.1TVD
12,726.5	8,249.0	-17.2	328.6	TD at 12726.5

Vertical Section Information

Angle Type	Target	Azimuth (°)	Origin Type	Origin +N/-S (ft)	+E/-W (ft)	Start TVD (ft)
Target	2-24-3-2WH_BHL Tgt	174.89	Slot	0.0	0.0	0.0

Survey tool program

From (ft)	To (ft)	Survey/Plan	Survey Tool
0.0	12,726.5	Plan A Rev 0 Proposal - Permit Only	MWD

HALLIBURTON

Duchesne County, UT

Plan Report for 2-24-3-2WH - Plan A Rev 0 Proposal - Permit Only**Casing Details**

Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (in)	Hole Diameter (in)
8,750.2	8,384.1	7"	7.000	7.500

Targets associated with this wellbore

Target Name	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Shape
2-24-3-2WH_Section Lines	0.0	0.0	0.0	Polygon
2-24-3-2WH_BHL Tgt	8,249.0	-4,561.8	408.1	Point
2-24-3-2WH_Setback Lines	0.0	0.0	0.0	Polygon
2-24-3-2WH_SHL Tgt	0.0	0.0	0.0	Point

CONFIDENTIAL

North Reference Sheet for Sec. 24-T3S-R2W - 2-24-3-2WH - Plan A Rev 0 Permit

All data is in Feet unless otherwise stated. Directions and Coordinates are relative to True North Reference.

Vertical Depths are relative to RKB 18' @ 5127.0ft (Original Well Elev). Northing and Easting are relative to 2-24-3-2WH

Coordinate System is US State Plane 1983, Utah Central Zone using datum North American Datum 1983, ellipsoid GRS 1980

Projection method is Lambert Conformal Conic (2 parallel)

Central Meridian is -111.50°, Longitude Origin:0° 0' 0.000 E°, Latitude Origin:40° 39' 0.000 N°

False Easting: 500,000.00m, False Northing: 2,000,000.00m, Scale Reduction: 0.99992075


Grid Coordinates of Well: 2,209,874.11 m N, 622,844.65 m E

Geographical Coordinates of Well: 40° 12' 53.38" N, 110° 03' 24.21" W


Grid Convergence at Surface is: 0.92°

Based upon Minimum Curvature type calculations, at a Measured Depth of 12,726.50ft
the Bottom Hole Displacement is 4,580.03ft in the Direction of 174.89° (True).


Magnetic Convergence at surface is: -10.26° (29 November 2012, , BGGM2012)



Typical 5M BOP stack configuration



Typical 5M choke manifold configuration



NEWFIELD EXPLORATION COMPANY

LOCATION LAYOUT FOR

POWITCH #2-24-3-2WH

SECTION 24, T3S, R2W, U.S.B.&M.

75' FNL 2332' FEL


FIGURE #1

SCALE: 1" = 60'

DATE: 02-15-12

DRAWN BY: J.J.

REVISED: 04-03-12



Elev. Ungraded Ground At Loc. Stake = 5108.8'
 FINISHED GRADE ELEV. AT LOC. STAKE = 5107.1'

UINTAH ENGINEERING & LAND SURVEYING
 85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

RECEIVED: December 21, 2012

NEWFIELD EXPLORATION COMPANY

TYPICAL CROSS SECTIONS FOR

POWVITCH #2-24-3-2WH


SECTION 24, T3S, R2W, U.S.B.&M.

75' FNL 2332' FEL

FIGURE #2

X-Section
Scale
1" = 100'

DATE: 02-15-12
DRAWN BY: J.J.
REVISED: 04-03-12



NOTE:

Topsoil should not be
Stripped Below Finished
Grade on Substructure Area.

APPROXIMATE ACREAGES

WELL SITE DISTURBANCE = ± 4.591 ACRES
ACCESS ROAD DISTURBANCE = ± 0.701 ACRES
PIPELINE DISTURBANCE = ± 1.195 ACRES
TOTAL = ± 6.487 ACRES

* NOTE:
FILL QUANTITY INCLUDES
5% FOR COMPACTION

APPROXIMATE YARDAGES

(12") Topsoil Stripping = 4,740 Cu. Yds.
Remaining Location = 5,390 Cu. Yds.
TOTAL CUT = 10,130 CU.YDS.
FILL = 4,490 CU.YDS.

EXCESS MATERIAL = 5,640 Cu. Yds.
Topsoil & Pit Backfill = 5,640 Cu. Yds.
(1/2 Pit Vol.)
EXCESS UNBALANCE = 0 Cu. Yds.
(After Interim Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

RECEIVED: December 21, 2012

NEWFIELD EXPLORATION COMPANY

PRODUCTION FACILITY LAYOUT FOR

POWVITCH #2-24-3-2WH

SECTION 24, T3S, R2W, U.S.B.&M.

75' FNL 2332' FEL

FIGURE #4



SCALE: 1" = 60'

DATE: 02-15-12

DRAWN BY: J.J.

REVISED: 04-03-12

REVISED: 04-27-12



RECLAIMED AREA


APPROXIMATE ACREAGES

UN-RECLAIMED = ± 1.338 ACRES

UINTAH ENGINEERING & LAND SURVEYING



85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

RECEIVED: December 21, 2012



API Number: 4301351942
Well Name: Powvitch 2-24-3-2WH
Township T03.0S Range R02.0W Section 24
Meridian: UBM
Operator: NEWFIELD PRODUCTION COMPANY
 Map Prepared:
 Map Produced by Diana Mason

Units	Wells Query
STATUS	Status
ACTIVE	APD - Approved Permit
EXPLORATORY	DRL - Spudded (Drilling Commenced)
GAS STORAGE	GIW - Gas Injection
NF PP OIL	GS - Gas Storage
NF SECONDARY	LOC - New Location
PI OIL	OPS - Operation Suspended
PP GAS	PA - Plugged Abandoned
PP GEOTHERM	PGW - Producing Gas Well
PP OIL	POW - Producing Oil Well
SECONDARY	SGW - Shut-in Gas Well
TERMINATED	SOW - Shut-in Oil Well
Fields	TA - Temp. Abandoned
Unknown	TW - Test Well
ABANDONED	WDW - Water Disposal
ACTIVE	WW - Water Injection Well
COMBINED	WSW - Water Supply Well
INACTIVE	Bottom Hole Location - Oil/Gas/Dib
STORAGE	
TERMINATED	





January 7, 2013

State of Utah
Division of Oil, Gas & Mining
ATTN: Brad Hill
P O Box 145801
Salt Lake City, UT 84114

RE: **Powvitch 2-24-3-2WH**
Section 24, T3S, R2W
Duchesne County, Utah

Dear Brad,

Newfield Production Company ("Newfield") proposes to drill the Powvitch 2-24-3-2WH from a surface location of 75' FNL & 2,332' FEL of Section 24, T3S, R2W to a bottom hole location of 660' FSL & 1,980' FEL of Section 24, T3S, R2W. Newfield shall case and cement the Powvitch 2-24-3-2WH wellbore from the surface location to the point where the wellbore reaches the legal setback of 660' FNL of Section 24, T3S, R2W. The cased and cemented portion of the wellbore shall not be perforated nor produced. In the event a future recompletion into the cased and cemented portion of the wellbore is proposed, Newfield shall file the appropriate application with the State.

Newfield is the operator of the Lamb 14-13-3-2 located in the northern offset drilling and spacing unit (Section 13, T3S-R2W). Due to these circumstances, Newfield respectfully requests that DOGM administratively grant an exception location for the Powvitch 2-24-3-2WH.

If you have any questions or require further information, please do not hesitate to contact the undersigned at 303-383-4169 or by email at kharris@newfield.com. Your consideration of this matter is greatly appreciated.

Sincerely,

A handwritten signature in blue ink, appearing to read "Ken H.", written over a large, diagonal red "CONFIDENTIAL" watermark.

Kenneth M. Harris
Landman

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 12/21/2012

API NO. ASSIGNED: 43013519420000

WELL NAME: Powvitch 2-24-3-2WH

OPERATOR: NEWFIELD PRODUCTION COMPANY (N2695)

PHONE NUMBER: 435 719-2018

CONTACT: Don Hamilton

PROPOSED LOCATION: NWNE 24 030S 020W

Permit Tech Review: ☒

SURFACE: 0075 FNL 2332 FEL

Engineering Review: ☐

BOTTOM: 0660 FSL 1980 FEL

Geology Review: ☒

COUNTY: DUCHESNE

LATITUDE: 40.21491

LONGITUDE: -110.05682

UTM SURF EASTINGS: 580257.00

NORTHINGS: 4452037.00

FIELD NAME: WILDCAT

LEASE TYPE: 2 - Indian

LEASE NUMBER: 14-20-H62-6176

PROPOSED PRODUCING FORMATION(S): GREEN RIVER

SURFACE OWNER: 2 - Indian

COALBED METHANE: NO

RECEIVED AND/OR REVIEWED:

☒ PLAT☒ Bond: INDIAN - RLB0010462☐ Potash☐ Oil Shale 190-5☐ Oil Shale 190-3☐ Oil Shale 190-13☒ Water Permit: 437478☐ RDCC Review:☐ Fee Surface Agreement☐ Intent to Commingle

Commingle Approved

LOCATION AND SITING:

☐ R649-2-3.

Unit:

☐ R649-3-2. General☒ R649-3-3. Exception☒ Drilling Unit

Board Cause No: Cause 139-90

Effective Date: 5/9/2012

Siting: 4 Prod LGRRV-WSTC Wells

☐ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 1 - Exception Location - bhill
4 - Federal Approval - dmason
27 - Other - bhill

RECEIVED: January 16, 2013



GARY R. HERBERT
Governor

GREGORY S. BELL
Lieutenant Governor

State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: Powvitch 2-24-3-2WH

API Well Number: 43013519420000

Lease Number: 14-20-H62-6176

Surface Owner: INDIAN

Approval Date: 1/16/2013

Issued to:

NEWFIELD PRODUCTION COMPANY , Rt 3 Box 3630 , Myton, UT 84052

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 139-90. The expected producing formation or pool is the GREEN RIVER Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Exception Location:

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-21, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels at 801-538-5284

(please leave a voicemail message if not available)

OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website

at <http://oilgas.ogm.utah.gov>

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

Approved By:

A handwritten signature in black ink, appearing to read "John Rogers", written over a horizontal line.

For John Rogers
Associate Director, Oil & Gas

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED

DEC 28 2012

FORM APPROVED
OMB No. 1004-0136
Expires July 31, 2010

APPLICATION FOR PERMIT TO DRILL OR REENTER

BLM

CONFIDENTIAL

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. 1420H626176
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name UINTAH AND OURAY
2. Name of Operator NEWFIELD EXPLORATION COMPANY		7. If Unit or CA Agreement, Name and No.
3a. Address ROUTE 3 BOX 3630 MYTON, UT 84052		8. Lease Name and Well No. POWVITCH 2-24-3-2WH
3b. Phone No. (include area code) Ph: 435-719-2018 Fx: 435-719-2019		9. API Well No. 43-013-S1942
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NWNE 75FNL 2332FEL 40.214828 N Lat, 110.056725 W Lon At proposed prod. zone Lot 2 660FSL 1980FEL 40.202306 N Lat, 110.055264 W Lon		10. Field and Pool, or Exploratory NATURAL BUTTES
14. Distance in miles and direction from nearest town or post office* 1.7 MILES NORTHEAST OF MYTON, UTAH		11. Sec., T., R., M., or Blk. and Survey or Area Sec 24 T3S R2W Mer UBM
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 75	16. No. of Acres in Lease 120.00	12. County or Parish DUCHESNE
18. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 0	19. Proposed Depth 12726 MD 8249 TVD	13. State UT
21. Elevations (Show whether DF, KB, RT, GL, etc.) 5109 GL	22. Approximate date work will start 01/15/2103	17. Spacing Unit dedicated to this well 40.00
		20. BLM/BIA Bond No. on file RLB0010462
		23. Estimated duration 60 DAYS

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.
2. A Drilling Plan.
3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
5. Operator certification
6. Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature (Electronic Submission)	Name (Printed/Typed) DON S HAMILTON Ph: 435-719-2018	Date 12/21/2012
Title PERMITTING AGENT		
Approved by (Signature) 	Name (Printed/Typed) Jerry Kenczka	Date APR 11 2013
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

Electronic Submission #168621 verified by the BLM Well Information System
For NEWFIELD EXPLORATION COMPANY, sent to the Vernal
Committed to AFMSS for processing by ROBIN R. HANSEN on 01/04/2013 (13RRH3566AF)

RECEIVED

APR 16 2013

BUREAU OF OIL, GAS & MINING

NOTICE OF APPROVAL

** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED **



UNITED STATES DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: Newfield Production Company
Well No: Powvitch 2-24-3-2WH
API No: 43-013-51942

Location: NWNE, Sec. 24, T3S, R2W
Lease No: 14-20-H62-6176
Agreement:

OFFICE NUMBER: (435) 781-4400

OFFICE FAX NUMBER: (435) 781-3420

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

NOTIFICATION REQUIREMENTS

Location Construction (Notify Environmental Scientist)	-	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings to blm_ut_vn_opreport@blm.gov .
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

**SURFACE USE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

- All Applicant-Committed Environmental Protection Measures (ACEPMs) listed in Section 2.1.8 of Environmental Assessment No. U&O-FY13-Q1-021,
- All on ACEPMs page 5 of the *Final Biological Opinion for Newfield Exploration Company and Ute Energy, LLC's proposed Rocky Point Exploration and Development* (Rocky Point BO) dated March 20, 2012,
- All terms and conditions of the Rocky Point BO and
- Any and all additional terms or stipulations attached to BIA ROW Serial No. H62-2013-119 and BIA ROW Serial No. H62-2013-120.

**DOWNHOLE PROGRAM
CONDITIONS OF APPROVAL (COAs)**

SITE SPECIFIC DOWNHOLE COAs:

- Intermediate casing (size casing 7 inch) cement shall be brought up and into the surface.
- Surface casing cement shall be brought to surface.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**
- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB

or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.

- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in CD (compact disc) format to the Vernal BLM Field Office. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.


OPERATING REQUIREMENT REMINDERS:


- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at www.ONRR.gov.
- Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
 - Operator name, address, and telephone number.
 - Well name and number.
 - Well location (¼¼, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid,

and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-H62-6176			
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE			
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: 1001 17th Street, Suite 2000 , Denver, CO, 80202		8. WELL NAME and NUMBER: POWVITCH 15-13-12-3-2WB			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0075 FNL 2332 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 24 Township: 03.0S Range: 02.0W Meridian: U		9. API NUMBER: 43013519420000			
5. FIELD and POOL or WILDCAT: NORTH MYTON BENCH		6. COUNTY: DUCHESNE			
7. STATE: UTAH					
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION <input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 9/1/2015 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	TYPE OF ACTION <table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/> </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100px;" type="text"/>			
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Newfield Production Company respectfully requests that the Powvitch 2-24-3-2WH (tribal surface and mineral) be changed from a 640 horizontal lateral well to a 1280 horizontal lateral well and that the well name be changed to the Powvitch 15-13-12-3-2WB (see attached supplemental information).					
Approved by the September 1, 2014 Oil, Gas and Mining Date: _____ By: <u>Don Hamilton</u>					
NAME (PLEASE PRINT) Don Hamilton		PHONE NUMBER 435 719-2018			
SIGNATURE N/A		TITLE Permitting Agent (Star Point Enterprises, Inc.)			
DATE 8/25/2014					





API Number: 4301351942

Well Name: POWVITCH 15-13-12-3-2WB


Township: T03.0S Range: R02.0W Section: 24 Meridian: U

Operator: NEWFIELD PRODUCTION COMPANY

Map Prepared: 9/10/2014
Map Produced by Diana Mason

Wells Query		Units	
Status		STATUS	
APD - Approved Permit		ACTIVE	
DRL - Spudded (Drilling Commenced)		EXPLORATORY	
GRW - Gas Injection		GAS STORAGE	
GS - Gas Storage		NF PP OIL	
LOC - New Location		NF SECONDARY	
OPS - Operation Suspended		PI OIL	
PA - Plugged Abandoned		PP GAS	
PGW - Producing Gas Well		PP GEOTHERML	
POW - Producing Oil Well		PP OIL	
SGW - Shut-in Gas Well		SECONDARY	
SOW - Shut-in Oil Well		TERMINATED	
TA - Temp. Abandoned			
TW - Test Well			
WOW - Water Disposal			
WW - Water Injection Well			
WSW - Water Supply Well			

Fields	
STATUS	
Unknown	
ABANDONED	
ACTIVE	
COMBINED	
INACTIVE	
STORAGE	
TERMINATED	




Powvitch 15-13-12-3-2WB

Newfield Production Company respectfully requests that the Powvitch 2-24-3-2WH (tribal surface and mineral) be changed from a 640 horizontal lateral well to a 1280 horizontal lateral well and that the well name be changed to the Powvitch 15-13-12-3-2WB. The TVD will change from 8,249 to 8,581' and the MD will change from 12,726' to 17,836', surface location remains unchanged. Following are the updated locations along the intended well bore path:

- Surface Location: 75' FNL & 2332' FEL, NWNE, Section 24, T3S, R2W, USB&M. (unchanged from permitted);
- Top of Producing Interval: 660' FSL & 1980' FEL, SWSE, Section 13, T3S, R2W, USB&M;
- Bottom of Producing Interval: 660' FNL & 1980' FEL, NWNE, Section 12, T3S, R2W, USB&M.
- Bottom Hole: 525' FNL & 1980' FEL, NWNE, Section 12, T3S, R2W, USB&M.

Attached please find an updated plat package, drilling plan, horizontal plan, exception letter and lease plat reflecting the changes. Surface use with the Ute Indian Tribe remains in place.

● = PROPOSED WELLHEAD.
○ = TARGET BOTTOM HOLE.
▲ = SECTION CORNERS
LOCATED.
△ = SECTION CORNERS
RE-ESTABLISHED.
(Not Set on Ground.)
◆ = LANDING POINT



LINE TABLE		
LINE	DIRECTION	LENGTH
L1	N25°22'10"E	815.72'
L2	N00°03'07"W	135.00'



NAD 83 (BOTTOM OF PRODUCING)	NAD 83 (TARGET BOTTOM HOLE)
LATITUDE = 40°14'32.17" (40.242269)	LATITUDE = 40°14'33.50" (40.242639)
LONGITUDE = 110°03'19.95" (110.055542)	LONGITUDE = 110°03'19.95" (110.055542)
NAD 27 (BOTTOM OF PRODUCING)	NAD 27 (TARGET BOTTOM HOLE)
LATITUDE = 40°14'32.32" (40.242311)	LATITUDE = 40°14'33.65" (40.242681)
LONGITUDE = 110°03'17.41" (110.054836)	LONGITUDE = 110°03'17.41" (110.054836)

CERTIFICATE
THE ABOVE PLAT WAS PREPARED FROM FIELD
Y'S MADE BY ME OR UNDER MY SUPERVISION
TRUE AND CORRECT TO THE BEST OF MY
ROBERT L.

REGISTERED LAND SURVEYOR
REGISTRATION NO. 461319
STATE OF UTAH

SPOT ELEVATION LOCATED AT THE SOUTHEAST CORNER OF SECTION 20, T3S, R2W, U.S.B.&M. TAKEN FROM THE MYTON, QUADRANGLE, UTAH, DUCHESNE COUNTY, 7.5 MINUTE QUAD (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5148 FEET.

**#15-13-12-3-2WB (TARGET BOTTOM HOLE)
NW 1/4 NE 1/4, SECTION 24, T3S, R2W, U.S.B.&M.
DUCESNE COUNTY, UTAH**



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017



SURVEYED BY: J.C., G.O.	SURVEY DATE: 02-10-12
DRAWN BY: J.J.	DATE DRAWN: 02-15-12
SCALE: 1" = 1000'	REVISED: 07-28-14 C.D.


WELL LOCATION PLAT

LEGEND:

- = 90° SYMBOL
- = PROPOSED WELLHEAD.
- = TARGET BOTTOM HOLE.
- = SECTION CORNERS LOCATED.
- = SECTION CORNERS RE-ESTABLISHED. (Not Set on Ground.)

T3S, R2W, U.S.B.&M.

Bottom of Producing Interval



LINE TABLE		
LINE	DIRECTION	LENGTH
L1	N25°22'10"E	815.72'



NAD 83 (TOP OF PRODUCING)	NAD 83 (SURFACE LOCATION)
LATITUDE = 40°13'00.66" (40.216850)	LATITUDE = 40°12'53.38" (40.214828)
LONGITUDE = 110°03'19.69" (110.055469)	LONGITUDE = 110°03'24.21" (110.056725)
NAD 27 (TOP OF PRODUCING)	NAD 27 (SURFACE LOCATION)
LATITUDE = 40°13'00.80" (40.216889)	LATITUDE = 40°12'53.53" (40.214869)
LONGITUDE = 110°03'17.15" (110.054764)	LONGITUDE = 110°03'21.67" (110.056019)

CERTIFICATE OF SURVEY
THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION, AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR
REGISTRATION NO. 76319
STATE OF UTAH
07-28-14

BASIS OF BEARINGS

BASIS OF BEARINGS IS A G.P.S. OBSERVATION

BASIS OF ELEVATION

SPOT ELEVATION LOCATED AT THE SOUTHEAST CORNER OF SECTION 20, T3S, R2W, U.S.B.&M. TAKEN FROM THE MYTON, QUADRANGLE, UTAH, DUCHESNE COUNTY, 7.5 MINUTE QUAD (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5148 FEET.

NEWFIELD EXPLORATION COMPANY

#15-13-12-3-2WB (SURFACE LOCATION)
NW 1/4 NE 1/4, SECTION 24, T3S, R2W, U.S.B.&M.
DUCHESNE COUNTY, UTAH

SURVEYED BY: J.C., G.O.	SURVEY DATE: 02-10-12
DRAWN BY: J.J.	DATE DRAWN: 02-15-12
SCALE: 1" = 1000'	REVISED: 07-28-14 C.D.

WELL LOCATION PLAT



UELS, LLC
Corporate Office * 85 South 200 East
Vernal, UT 84078 * (435) 789-1017



5D Plan Report

5D Plan Report

NEWFIELD

Field Name: *UTAH_ CENTRAL ZONE_NAD83*
Site Name: *15-13-12-3-2WB*
Well Name: *15-13-12-3-2WB*
Plan: *PLAN 4*

10 September 2014



Sundry Number: 54774 API Well Number: 43013519420000

Plan Data for 15-13-12-3-2WB

Field: UTAH_CENTRAL_ZONE_NAD83
Map Unit: USFt Vertical Reference Datum (VRD):
Projected Coordinate System: NAD83 / Utah Central (ftUS)

Site: 15-13-12-3-2WB
Unit: USFeet TVD Reference:
Company Name: NEWFIELD
Position: Northing: 7250228.76USft Latitude: 40.214828°
Easting: 2043449.51USft Longitude: -110.056725°
North Reference: True Grid Convergence: 0.92°
Elevation Above VRD: 5107.00USft

Slot: 15-13-12-3-2WB
Position:
Offset is from Site centre
+N/-S: 0.00USft Northing: 7250228.76USft Latitude: 40.214828°
+E/-W: 0.00USft Easting: 2043449.51USft Longitude: -110.056725°
Elevation Above VRD: 5107.00USft

Well: 15-13-12-3-2WB
Type: Main-Well
File Number:
Vertical Section: Position offset of origin from Slot centre:
+N/-S: 0.00USft Azimuth: 1.87°
+E/-W: 0.00USft
Magnetic Parameters:
Model: Field Strength: Declination: Dip: Date:
BGGM 51971(nT) 11.05° 65.85° 2014-09-10

Plan Point Information:




DogLeg Severity Unit: °/100.00ft Position offsets from Slot centre

MD	Inc	Az	TVD	+N/-S	+E/-W	VSec	DLS	Toolface	Build	Turn
(USft)	(°)	(°)	(USft)	(USft)	(USft)	(USft)	(DLSU)	(°)	(DLSU)	(DLSU)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.0	0.00	0.00
4940.00	0.00	0.00	4940.00	0.00	0.00	0.00	0.00	0.0	0.00	0.00
5540.00	9.00	108.08	5537.54	-14.59	44.71	-13.13	1.50	108.1	1.50	0.00
7069.18	9.00	108.08	7047.89	-88.83	272.11	-79.91	0.00	0.0	0.00	0.00
8047.68	45.53	359.88	7928.00	257.88	348.86	269.13	5.00	244.1	3.73	-11.06
8097.68	48.03	359.88	7962.23	294.31	348.78	305.54	5.00	0.0	5.00	0.00
8586.18	87.11	359.88	8145.03	737.15	347.85	748.11	8.00	0.0	8.00	0.00
17856.81	87.11	359.89	8612.00	9996.00	330.23	10001.45	0.00	76.0	0.00	0.00
17991.81	87.11	359.89	8618.80	10130.83	329.98	10136.20	0.00	0.0	0.00	0.00

Target Set Information:

Name: 15-13-12-3-2WB PBHL

Name	TVD	Lat	Long
(USft)	(°)	(°)	(°)
PBHL 1	8612.00	40.242269	-110.055542



5D Plan Report



15-13-12-3-2WB

Field Name UTAH_CENTRAL ZONE_NAD83	Map Units : US ft		Company Name : NEWFIELD		
	Vertical Reference Datum (VRD) :				
	Projected Coordinate System : NAD83 / Utah Central (ftUS)				
	Comment :				
Site Name 15-13-12-3-2WB	Units : US ft		North Reference : True		
	Position	Northing : 7250228.76 US ft		Convergence Angle : 0.92	
		Easting : 2043449.51 US ft		Latitude : 40° 12' 53.38"	
	Longitude : -110° 3' 24.21"				
Elevation above VRD:5107.00 US ft					
Comment :					
Slot Name 15-13-12-3-2WB	Position (Offsets relative to Site Centre)				
	+N / -S : 0.00 US ft		Northing :7250228.76 US ft		
	+E / -W : 0.00 US ft		Easting :2043449.51 US ft		
	Latitude : 40°12'53.38"		Longitude : -110°3'24.21"		
Elevation above VRD : 5107.00 US ft					
Comment :					
Well Name 15-13-12-3-2WB	Type : Main well		UWI :		Plan : PLAN 4
	Rig Height		Well TVD Reference : 26.00 US ft		Comment :
	Relative to VRD: 5133.00 US ft				
	Closure Distance : 10136.2 US ft		Closure Azimuth : 1.86555°		
	Vertical Section (Position of Origin Relative to Slot)				
	+N / -S : 0.00 US ft		+E / -W : 0.00 US ft		Az :1.87°
	Magnetic Parameters				
	Model : BGGM	Field Strength : 51971.4nT	Dec : 11.05°	Dip : 65.85°	Date : 10/Sep/2014
Plan Archive					
Plan Folder	Date	Comment	Plans		
P1	31/Jul/2014		Plan PLAN 1	Date 31/Jul/2014 Comment	

5D Plan Report

Plan Archive				
Plan Folder	Date	Comment	Plans	
			Plan PLAN 2 PLAN 3-A PLAN 3 PLAN 3-B PLAN 4	Date 28/Aug/2014 08/Sep/2014 08/Sep/2014 10/Sep/2014 10/Sep/2014 Comment

Target Set

Name : 15-13-12-3-2WB PBHL	Number of Targets : 1
----------------------------	-----------------------

Comment :

TargetName:	Position (Relative to Slot centre)			
PBHL 1	+N / -S : 9996.00US ft	Northing : 7260228.79 US ft	Latitude : 40°14'32.17"	
Shape:	+E / -W : 330.23 US ft	Easting : 2043618.41US ft	Longitude : -110°3'19.95"	
Cuboid	TVD (Well TVD Reference) : 8612.00 US ft			
	Orientation	Azimuth : 0.00°	Inclination : 0.00°	
	Dimensions	Length : 1.00 US ft	Breadth : 1.00 US ft	Height : 1.00 US ft

Well path created using minimum curvature

Interpolated Points (Relative to Slot centre, TVD relative to Well TVD Reference)												
MD (US ft)	Inc (°)	Az (°)	TVD (US ft)	N.Offset (US ft)	E.Offset (US ft)	Latitude (° ' ")	Longitude (° ' ")	DLS (°/100 US ft)	T.Face (°)	VS (US ft)	Clos.Az (°)	Comment
0.00	0.00	0.00	0.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	TIE-ON
100.00	0.00	0.00	100.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
200.00	0.00	0.00	200.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
400.00	0.00	0.00	400.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
500.00	0.00	0.00	500.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
600.00	0.00	0.00	600.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
700.00	0.00	0.00	700.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
800.00	0.00	0.00	800.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
900.00	0.00	0.00	900.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
1000.00	0.00	0.00	1000.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
1100.00	0.00	0.00	1100.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
1200.00	0.00	0.00	1200.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	

5D Plan Report

Interpolated Points (Relative to Slot centre, TVD relative to Well TVD Reference)												
MD (US ft)	Inc (°)	Az (°)	TVD (US ft)	N.Offset (US ft)	E.Offset (US ft)	Latitude (° ' ")	Longitude (° ' ")	DLS (°/100 US ft)	T.Face (°)	VS (US ft)	Clos.Az (°)	Comment
1300.00	0.00	0.00	1300.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
1400.00	0.00	0.00	1400.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
1500.00	0.00	0.00	1500.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
1600.00	0.00	0.00	1600.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
1700.00	0.00	0.00	1700.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
1800.00	0.00	0.00	1800.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
1900.00	0.00	0.00	1900.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
2000.00	0.00	0.00	2000.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
2100.00	0.00	0.00	2100.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
2200.00	0.00	0.00	2200.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
2300.00	0.00	0.00	2300.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
2400.00	0.00	0.00	2400.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
2500.00	0.00	0.00	2500.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
2600.00	0.00	0.00	2600.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
2700.00	0.00	0.00	2700.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
2800.00	0.00	0.00	2800.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
2900.00	0.00	0.00	2900.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
3000.00	0.00	0.00	3000.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
3100.00	0.00	0.00	3100.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
3200.00	0.00	0.00	3200.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
3300.00	0.00	0.00	3300.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
3400.00	0.00	0.00	3400.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
3500.00	0.00	0.00	3500.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
3600.00	0.00	0.00	3600.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
3700.00	0.00	0.00	3700.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
3800.00	0.00	0.00	3800.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
3900.00	0.00	0.00	3900.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
4000.00	0.00	0.00	4000.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
4100.00	0.00	0.00	4100.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
4200.00	0.00	0.00	4200.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
4300.00	0.00	0.00	4300.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
4400.00	0.00	0.00	4400.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
4500.00	0.00	0.00	4500.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
4600.00	0.00	0.00	4600.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
4700.00	0.00	0.00	4700.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
4800.00	0.00	0.00	4800.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
4900.00	0.00	0.00	4900.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	
4940.00	0.00	0.00	4940.00	0.00	0.00	40°12'53.38"	-110°3'24.21"	0.00	0.00	0.00	0.00	BEGIN NUDGE @ 1.5°/100'
5000.00	0.90	108.08	5000.00	-0.15	0.45	40°12'53.38"	-110°3'24.20"	1.50	108.08	-0.13	108.08	
5100.00	2.40	108.08	5099.95	-1.04	3.19	40°12'53.37"	-110°3'24.17"	1.50	0.00	-0.94	108.08	

5D Plan Report

Interpolated Points (Relative to Slot centre, TVD relative to Well TVD Reference)												
MD (US ft)	Inc (°)	Az (°)	TVD (US ft)	N.Offset (US ft)	E.Offset (US ft)	Latitude (° ' ")	Longitude (° ' ")	DLS (°/100 US ft)	T.Face (°)	VS (US ft)	Clos.Az (°)	Comment
5199.20	3.89	108.08	5199.00	-2.73	8.36	40°12'53.35"	-110°3'24.10"	1.50	0.00	-2.45	108.08	Trona :
5200.00	3.90	108.08	5199.80	-2.75	8.41	40°12'53.35"	-110°3'24.10"	1.50	0.00	-2.47	108.08	
5241.31	4.52	108.08	5241.00	-3.69	11.29	40°12'53.34"	-110°3'24.06"	1.50	0.00	-3.32	108.08	Mahogany Bench :
5300.00	5.40	108.08	5299.47	-5.26	16.12	40°12'53.33"	-110°3'24.00"	1.50	0.00	-4.73	108.08	
5400.00	6.90	108.08	5398.89	-8.59	26.30	40°12'53.30"	-110°3'23.87"	1.50	0.00	-7.72	108.08	
5500.00	8.40	108.08	5498.00	-12.72	38.95	40°12'53.26"	-110°3'23.71"	1.50	0.00	-11.44	108.08	
5540.00	9.00	108.08	5537.54	-14.59	44.71	40°12'53.24"	-110°3'23.63"	1.50	0.00	-13.13	108.08	END NUDGE
5600.00	9.00	108.08	5596.80	-17.51	53.63	40°12'53.21"	-110°3'23.52"	0.00	0.00	-15.75	108.08	
5700.00	9.00	108.08	5695.57	-22.36	68.50	40°12'53.16"	-110°3'23.33"	0.00	0.00	-20.12	108.08	
5800.00	9.00	108.08	5794.33	-27.22	83.37	40°12'53.11"	-110°3'23.14"	0.00	0.00	-24.48	108.08	
5900.00	9.00	108.08	5893.10	-32.07	98.24	40°12'53.06"	-110°3'22.94"	0.00	0.00	-28.85	108.08	
6000.00	9.00	108.08	5991.87	-36.93	113.11	40°12'53.02"	-110°3'22.75"	0.00	0.00	-33.22	108.08	
6079.10	9.00	108.08	6070.00	-40.77	124.88	40°12'52.98"	-110°3'22.60"	0.00	0.00	-36.67	108.08	Garden Gulch Member :
6100.00	9.00	108.08	6090.64	-41.78	127.98	40°12'52.97"	-110°3'22.56"	0.00	0.00	-37.58	108.08	
6200.00	9.00	108.08	6189.41	-46.64	142.85	40°12'52.92"	-110°3'22.37"	0.00	0.00	-41.95	108.08	
6300.00	9.00	108.08	6288.18	-51.49	157.72	40°12'52.87"	-110°3'22.18"	0.00	0.00	-46.32	108.08	
6325.13	9.00	108.08	6313.00	-52.71	161.46	40°12'52.86"	-110°3'22.13"	0.00	0.00	-47.41	108.08	Garden Gulch Member-1 :
6400.00	9.00	108.08	6386.95	-56.35	172.60	40°12'52.82"	-110°3'21.99"	0.00	0.00	-50.68	108.08	
6481.05	9.00	108.08	6467.00	-60.28	184.65	40°12'52.79"	-110°3'21.83"	0.00	0.00	-54.22	108.08	Garden Gulch Member-2 :
6500.00	9.00	108.08	6485.72	-61.20	187.47	40°12'52.78"	-110°3'21.79"	0.00	0.00	-55.05	108.08	
6600.00	9.00	108.08	6584.49	-66.06	202.34	40°12'52.73"	-110°3'21.60"	0.00	0.00	-59.42	108.08	
6700.00	9.00	108.08	6683.25	-70.91	217.21	40°12'52.68"	-110°3'21.41"	0.00	0.00	-63.79	108.08	
6800.00	9.00	108.08	6782.02	-75.77	232.08	40°12'52.63"	-110°3'21.22"	0.00	0.00	-68.15	108.08	
6900.00	9.00	108.08	6880.79	-80.62	246.95	40°12'52.58"	-110°3'21.03"	0.00	0.00	-72.52	108.08	
7000.00	9.00	108.08	6979.56	-85.48	261.82	40°12'52.54"	-110°3'20.83"	0.00	0.00	-76.89	108.08	
7069.18	9.00	108.08	7047.89	-88.83	272.11	40°12'52.50"	-110°3'20.70"	0.00	0.00	-79.91	108.08	KOP, BUILD & TURN @ 5°/100'
7100.00	8.44	98.60	7078.35	-89.92	276.64	40°12'52.49"	-110°3'20.64"	5.00	244.06	-80.85	108.01	
7191.58	8.37	66.87	7169.00	-88.31	289.42	40°12'52.51"	-110°3'20.48"	5.00	253.44	-78.82	106.97	Douglas Creek Member :
7200.00	8.49	64.11	7177.33	-87.79	290.54	40°12'52.51"	-110°3'20.46"	5.00	284.84	-78.27	106.81	
7300.00	11.07	38.46	7275.91	-77.05	303.15	40°12'52.62"	-110°3'20.30"	5.00	287.57	-67.12	104.26	
7400.00	14.92	24.09	7373.36	-57.78	314.39	40°12'52.81"	-110°3'20.16"	5.00	312.87	-47.49	100.41	
7500.00	19.30	15.81	7468.93	-30.11	324.15	40°12'53.08"	-110°3'20.03"	5.00	326.88	-19.52	95.31	
7600.00	23.91	10.55	7561.89	5.73	332.36	40°12'53.44"	-110°3'19.93"	5.00	334.80	16.58	89.01	
7700.00	28.65	6.94	7651.53	49.48	338.97	40°12'53.87"	-110°3'19.84"	5.00	339.69	60.52	81.69	
7800.00	33.46	4.28	7737.18	100.80	343.93	40°12'54.38"	-110°3'19.78"	5.00	342.94	111.97	73.66	
7862.02	36.47	2.95	7788.00	136.27	346.15	40°12'54.73"	-110°3'19.75"	5.00	345.22	147.49	68.51	B Limestone :
7900.00	38.31	2.22	7818.17	159.30	347.19	40°12'54.96"	-110°3'19.73"	5.00	346.31	170.55	65.35	

5D Plan Report

Interpolated Points (Relative to Slot centre, TVD relative to Well TVD Reference)												
MD (US ft)	Inc (°)	Az (°)	TVD (US ft)	N.Offset (US ft)	E.Offset (US ft)	Latitude (° ' ")	Longitude (° ' ")	DLS (°/100 US ft)	T.Face (°)	VS (US ft)	Clos.Az (°)	Comment
8000.00	43.19	0.57	7893.91	224.54	348.73	40°12'55.60"	-110°3'19.71"	5.00	346.88	235.80	57.22	
8047.68	45.53	359.88	7928.00	257.88	348.86	40°12'55.93"	-110°3'19.71"	5.00	348.14	269.13	53.53	END BUILD & TURN
8097.68	48.03	359.88	7962.23	294.31	348.78	40°12'56.29"	-110°3'19.71"	5.00	0.00	305.54	49.84	BUILD @ 8°/100'
8100.00	48.22	359.88	7963.78	296.04	348.78	40°12'56.31"	-110°3'19.71"	8.00	0.00	307.26	49.68	
8121.71	49.95	359.88	7978.00	312.45	348.74	40°12'56.47"	-110°3'19.71"	8.00	0.00	323.66	48.14	Lower Black Shale :
8200.00	56.22	359.88	8025.00	375.00	348.61	40°12'57.09"	-110°3'19.72"	8.00	0.00	386.18	42.91	
8291.75	63.56	359.88	8071.00	454.31	348.45	40°12'57.87"	-110°3'19.72"	8.00	0.00	465.44	37.49	Castle Peak Limestone :
8300.00	64.22	359.88	8074.63	461.72	348.43	40°12'57.94"	-110°3'19.72"	8.00	0.00	472.85	37.04	
8370.13	69.83	359.88	8102.00	526.26	348.29	40°12'58.58"	-110°3'19.72"	8.00	0.00	537.35	33.50	CP1 :
8400.00	72.22	359.88	8111.71	554.51	348.24	40°12'58.86"	-110°3'19.72"	8.00	0.00	565.57	32.13	
8500.00	80.22	359.88	8135.52	651.55	348.03	40°12'59.82"	-110°3'19.72"	8.00	0.00	662.56	28.11	
8585.60	87.06	359.88	8145.00	736.57	347.85	40°13'0.66"	-110°3'19.73"	8.00	0.00	747.52	25.28	CP2 (Hz Target) :
8586.18	87.11	359.88	8145.03	737.15	347.85	40°13'0.67"	-110°3'19.73"	8.00	0.00	748.11	25.26	LANDING POINT
8600.00	87.11	359.88	8145.73	750.95	347.82	40°13'0.80"	-110°3'19.73"	0.00	0.00	761.90	24.85	
8700.00	87.11	359.88	8150.77	850.82	347.61	40°13'1.79"	-110°3'19.73"	0.00	0.00	861.71	22.22	
8800.00	87.11	359.88	8155.81	950.70	347.41	40°13'2.78"	-110°3'19.73"	0.00	0.00	961.53	20.07	
8900.00	87.11	359.88	8160.85	1050.57	347.20	40°13'3.76"	-110°3'19.73"	0.00	0.00	1061.34	18.29	
9000.00	87.11	359.88	8165.89	1150.44	346.99	40°13'4.75"	-110°3'19.74"	0.00	0.00	1161.15	16.78	
9100.00	87.11	359.88	8170.94	1250.31	346.78	40°13'5.74"	-110°3'19.74"	0.00	0.00	1260.96	15.50	
9200.00	87.11	359.88	8175.98	1350.19	346.57	40°13'6.72"	-110°3'19.74"	0.00	0.00	1360.78	14.40	
9300.00	87.11	359.88	8181.02	1450.06	346.36	40°13'7.71"	-110°3'19.74"	0.00	0.00	1460.59	13.43	
9400.00	87.11	359.88	8186.06	1549.93	346.16	40°13'8.70"	-110°3'19.75"	0.00	0.00	1560.40	12.59	
9500.00	87.11	359.88	8191.10	1649.80	345.95	40°13'9.69"	-110°3'19.75"	0.00	0.00	1660.21	11.84	
9600.00	87.11	359.88	8196.14	1749.68	345.74	40°13'10.67"	-110°3'19.75"	0.00	0.00	1760.03	11.18	
9700.00	87.11	359.88	8201.18	1849.55	345.54	40°13'11.66"	-110°3'19.76"	0.00	0.00	1859.84	10.58	
9800.00	87.11	359.88	8206.23	1949.42	345.33	40°13'12.65"	-110°3'19.76"	0.00	0.00	1959.65	10.05	
9900.00	87.11	359.88	8211.27	2049.30	345.12	40°13'13.63"	-110°3'19.76"	0.00	0.00	2059.47	9.56	
10000.00	87.11	359.88	8216.31	2149.17	344.92	40°13'14.62"	-110°3'19.76"	0.00	0.00	2159.28	9.12	
10100.00	87.11	359.88	8221.35	2249.04	344.71	40°13'15.61"	-110°3'19.77"	0.00	0.00	2259.09	8.71	
10200.00	87.11	359.88	8226.39	2348.91	344.50	40°13'16.59"	-110°3'19.77"	0.00	0.00	2358.90	8.34	
10300.00	87.11	359.88	8231.43	2448.79	344.30	40°13'17.58"	-110°3'19.77"	0.00	0.00	2458.72	8.00	
10400.00	87.11	359.88	8236.47	2548.66	344.09	40°13'18.57"	-110°3'19.77"	0.00	0.00	2558.53	7.69	
10500.00	87.11	359.88	8241.51	2648.53	343.89	40°13'19.56"	-110°3'19.78"	0.00	0.00	2658.34	7.40	
10600.00	87.11	359.88	8246.55	2748.40	343.68	40°13'20.54"	-110°3'19.78"	0.00	0.00	2758.15	7.13	
10700.00	87.11	359.88	8251.59	2848.28	343.48	40°13'21.53"	-110°3'19.78"	0.00	0.00	2857.97	6.88	
10800.00	87.11	359.88	8256.63	2948.15	343.27	40°13'22.52"	-110°3'19.78"	0.00	0.00	2957.78	6.64	
10900.00	87.11	359.88	8261.68	3048.02	343.07	40°13'23.50"	-110°3'19.79"	0.00	0.00	3057.59	6.42	
11000.00	87.11	359.88	8266.72	3147.89	342.86	40°13'24.49"	-110°3'19.79"	0.00	0.00	3157.41	6.22	

5D Plan Report

Interpolated Points (Relative to Slot centre, TVD relative to Well TVD Reference)												
MD (US ft)	Inc (°)	Az (°)	TVD (US ft)	N.Offset (US ft)	E.Offset (US ft)	Latitude (° ' ")	Longitude (° ' ")	DLS (°/100 US ft)	T.Face (°)	VS (US ft)	Clos.Az (°)	Comment
11100.00	87.11	359.88	8271.76	3247.77	342.66	40°13'25.48"	-110°3'19.79"	0.00	0.00	3257.22	6.02	
11200.00	87.11	359.88	8276.80	3347.64	342.46	40°13'26.46"	-110°3'19.79"	0.00	0.00	3357.03	5.84	
11300.00	87.11	359.88	8281.84	3447.51	342.25	40°13'27.45"	-110°3'19.80"	0.00	0.00	3456.84	5.67	
11400.00	87.11	359.88	8286.88	3547.39	342.05	40°13'28.44"	-110°3'19.80"	0.00	0.00	3556.66	5.51	
11500.00	87.11	359.88	8291.92	3647.26	341.85	40°13'29.43"	-110°3'19.80"	0.00	0.00	3656.47	5.35	
11600.00	87.11	359.88	8296.96	3747.13	341.64	40°13'30.41"	-110°3'19.81"	0.00	0.00	3756.28	5.21	
11700.00	87.11	359.88	8302.00	3847.00	341.44	40°13'31.40"	-110°3'19.81"	0.00	0.00	3856.10	5.07	
11800.00	87.11	359.88	8307.04	3946.88	341.24	40°13'32.39"	-110°3'19.81"	0.00	0.00	3955.91	4.94	
11900.00	87.11	359.88	8312.08	4046.75	341.03	40°13'33.37"	-110°3'19.81"	0.00	0.00	4055.72	4.82	
12000.00	87.11	359.88	8317.12	4146.62	340.83	40°13'34.36"	-110°3'19.82"	0.00	0.00	4155.53	4.70	
12100.00	87.11	359.88	8322.16	4246.49	340.63	40°13'35.35"	-110°3'19.82"	0.00	0.00	4255.35	4.59	
12200.00	87.11	359.88	8327.20	4346.37	340.43	40°13'36.33"	-110°3'19.82"	0.00	0.00	4355.16	4.48	
12300.00	87.11	359.88	8332.24	4446.24	340.23	40°13'37.32"	-110°3'19.82"	0.00	0.00	4454.97	4.38	
12400.00	87.11	359.88	8337.28	4546.11	340.03	40°13'38.31"	-110°3'19.83"	0.00	0.00	4554.79	4.28	
12500.00	87.11	359.88	8342.32	4645.98	339.82	40°13'39.30"	-110°3'19.83"	0.00	0.00	4654.60	4.18	
12600.00	87.11	359.88	8347.36	4745.86	339.62	40°13'40.28"	-110°3'19.83"	0.00	0.00	4754.41	4.09	
12700.00	87.11	359.88	8352.40	4845.73	339.42	40°13'41.27"	-110°3'19.83"	0.00	0.00	4854.23	4.01	
12800.00	87.11	359.88	8357.44	4945.60	339.22	40°13'42.26"	-110°3'19.84"	0.00	0.00	4954.04	3.92	
12900.00	87.11	359.88	8362.48	5045.48	339.02	40°13'43.24"	-110°3'19.84"	0.00	0.00	5053.85	3.84	
13000.00	87.11	359.89	8367.52	5145.35	338.82	40°13'44.23"	-110°3'19.84"	0.00	0.00	5153.66	3.77	
13100.00	87.11	359.89	8372.56	5245.22	338.62	40°13'45.22"	-110°3'19.84"	0.00	0.00	5253.48	3.69	
13200.00	87.11	359.89	8377.60	5345.09	338.42	40°13'46.20"	-110°3'19.85"	0.00	0.00	5353.29	3.62	
13300.00	87.11	359.89	8382.64	5444.97	338.22	40°13'47.19"	-110°3'19.85"	0.00	0.00	5453.10	3.55	
13400.00	87.11	359.89	8387.68	5544.84	338.02	40°13'48.18"	-110°3'19.85"	0.00	0.00	5552.92	3.49	
13500.00	87.11	359.89	8392.72	5644.71	337.82	40°13'49.17"	-110°3'19.85"	0.00	0.00	5652.73	3.42	
13600.00	87.11	359.89	8397.75	5744.58	337.62	40°13'50.15"	-110°3'19.86"	0.00	0.00	5752.54	3.36	
13700.00	87.11	359.89	8402.79	5844.46	337.43	40°13'51.14"	-110°3'19.86"	0.00	0.00	5852.36	3.30	
13800.00	87.11	359.89	8407.83	5944.33	337.23	40°13'52.13"	-110°3'19.86"	0.00	0.00	5952.17	3.25	
13900.00	87.11	359.89	8412.87	6044.20	337.03	40°13'53.11"	-110°3'19.86"	0.00	0.00	6051.98	3.19	
14000.00	87.11	359.89	8417.91	6144.08	336.83	40°13'54.10"	-110°3'19.87"	0.00	0.00	6151.80	3.14	
14100.00	87.11	359.89	8422.95	6243.95	336.63	40°13'55.09"	-110°3'19.87"	0.00	0.00	6251.61	3.09	
14200.00	87.11	359.89	8427.99	6343.82	336.44	40°13'56.08"	-110°3'19.87"	0.00	0.00	6351.42	3.04	
14300.00	87.11	359.89	8433.03	6443.69	336.24	40°13'57.06"	-110°3'19.87"	0.00	0.00	6451.23	2.99	
14400.00	87.11	359.89	8438.07	6543.57	336.04	40°13'58.05"	-110°3'19.88"	0.00	0.00	6551.05	2.94	
14500.00	87.11	359.89	8443.11	6643.44	335.84	40°13'59.04"	-110°3'19.88"	0.00	0.00	6650.86	2.89	
14600.00	87.11	359.89	8448.15	6743.31	335.65	40°14'0.02"	-110°3'19.88"	0.00	0.00	6750.67	2.85	
14700.00	87.11	359.89	8453.18	6843.19	335.45	40°14'1.01"	-110°3'19.88"	0.00	0.00	6850.49	2.81	
14800.00	87.11	359.89	8458.22	6943.06	335.25	40°14'2.00"	-110°3'19.89"	0.00	0.00	6950.30	2.76	
14900.00	87.11	359.89	8463.26	7042.93	335.06	40°14'2.98"	-110°3'19.89"	0.00	0.00	7050.11	2.72	
15000.00	87.11	359.89	8468.30	7142.80	334.86	40°14'3.97"	-110°3'19.89"	0.00	0.00	7149.93	2.68	
15100.00	87.11	359.89	8473.34	7242.68	334.67	40°14'4.96"	-110°3'19.89"	0.00	0.00	7249.74	2.65	

5D Plan Report

Interpolated Points (Relative to Slot centre, TVD relative to Well TVD Reference)												
MD (US ft)	Inc (°)	Az (°)	TVD (US ft)	N.Offset (US ft)	E.Offset (US ft)	Latitude (° ' ")	Longitude (° ' ")	DLS (°/100 US ft)	T.Face (°)	VS (US ft)	Clos.Az (°)	Comment
15200.00	87.11	359.89	8478.38	7342.55	334.47	40°14'5.95"	-110°3'19.90"	0.00	0.00	7349.55	2.61	
15300.00	87.11	359.89	8483.42	7442.42	334.27	40°14'6.93"	-110°3'19.90"	0.00	0.00	7449.37	2.57	
15400.00	87.11	359.89	8488.45	7542.29	334.08	40°14'7.92"	-110°3'19.90"	0.00	0.00	7549.18	2.54	
15500.00	87.11	359.89	8493.49	7642.17	333.88	40°14'8.91"	-110°3'19.90"	0.00	0.00	7648.99	2.50	
15600.00	87.11	359.89	8498.53	7742.04	333.69	40°14'9.89"	-110°3'19.91"	0.00	0.00	7748.81	2.47	
15700.00	87.11	359.89	8503.57	7841.91	333.49	40°14'10.88"	-110°3'19.91"	0.00	0.00	7848.62	2.44	
15800.00	87.11	359.89	8508.61	7941.79	333.30	40°14'11.87"	-110°3'19.91"	0.00	0.00	7948.43	2.40	
15900.00	87.11	359.89	8513.64	8041.66	333.11	40°14'12.85"	-110°3'19.91"	0.00	0.00	8048.25	2.37	
16000.00	87.11	359.89	8518.68	8141.53	332.91	40°14'13.84"	-110°3'19.92"	0.00	0.00	8148.06	2.34	
16100.00	87.11	359.89	8523.72	8241.40	332.72	40°14'14.83"	-110°3'19.92"	0.00	0.00	8247.87	2.31	
16200.00	87.11	359.89	8528.76	8341.28	332.52	40°14'15.82"	-110°3'19.92"	0.00	0.00	8347.69	2.28	
16300.00	87.11	359.89	8533.80	8441.15	332.33	40°14'16.80"	-110°3'19.92"	0.00	0.00	8447.50	2.25	
16400.00	87.11	359.89	8538.83	8541.02	332.14	40°14'17.79"	-110°3'19.93"	0.00	0.00	8547.31	2.23	
16500.00	87.11	359.89	8543.87	8640.90	331.94	40°14'18.78"	-110°3'19.93"	0.00	0.00	8647.13	2.20	
16600.00	87.11	359.89	8548.91	8740.77	331.75	40°14'19.76"	-110°3'19.93"	0.00	0.00	8746.94	2.17	
16700.00	87.11	359.89	8553.95	8840.64	331.56	40°14'20.75"	-110°3'19.93"	0.00	0.00	8846.75	2.15	
16800.00	87.11	359.89	8558.99	8940.51	331.37	40°14'21.74"	-110°3'19.94"	0.00	0.00	8946.57	2.12	
16900.00	87.11	359.89	8564.02	9040.39	331.18	40°14'22.72"	-110°3'19.94"	0.00	0.00	9046.38	2.10	
17000.00	87.11	359.89	8569.06	9140.26	330.98	40°14'23.71"	-110°3'19.94"	0.00	0.00	9146.19	2.07	
17100.00	87.11	359.89	8574.10	9240.13	330.79	40°14'24.70"	-110°3'19.94"	0.00	0.00	9246.01	2.05	
17200.00	87.11	359.89	8579.14	9340.01	330.60	40°14'25.69"	-110°3'19.95"	0.00	0.00	9345.82	2.03	
17300.00	87.11	359.89	8584.17	9439.88	330.41	40°14'26.67"	-110°3'19.95"	0.00	0.00	9445.63	2.00	
17400.00	87.11	359.89	8589.21	9539.75	330.22	40°14'27.66"	-110°3'19.95"	0.00	0.00	9545.45	1.98	
17500.00	87.11	359.89	8594.25	9639.62	330.03	40°14'28.65"	-110°3'19.95"	0.00	0.00	9645.26	1.96	
17600.00	87.11	359.89	8599.29	9739.50	329.84	40°14'29.63"	-110°3'19.96"	0.00	0.00	9745.07	1.94	
17700.00	87.11	359.89	8604.32	9839.37	329.65	40°14'30.62"	-110°3'19.96"	0.00	0.00	9844.89	1.92	
17800.00	87.11	359.89	8609.36	9939.24	329.46	40°14'31.61"	-110°3'19.96"	0.00	0.00	9944.70	1.90	
17856.82	87.11	359.89	8612.00	9996.00	330.23	40°14'32.17"	-110°3'19.95"	0.00	75.97	10001.45	1.89	TD @ 17856.81' MD
17900.01	87.11	359.89	8614.18	10039.13	330.15	40°14'32.59"	-110°3'19.95"	0.00	0.00	10044.56	1.88	
17991.82	87.11	359.89	8618.80	10130.83	329.98	40°14'33.50"	-110°3'19.95"	0.00	0.00	10136.20	1.87	RATHOLE TD

Formation Points (Relative to Slot centre, TVD relative to Well TVD Reference)									
Name	MD (US ft)	Inc (°)	Az (°)	TVD (US ft)	N.Offset (US ft)	E.Offset (US ft)	F.Dip (°)	F.Dir (°)	
Trona	5199.20	3.89	108.08	5199.00	-2.73	8.36	0	0	
Mahogany Bench	5241.31	4.52	108.08	5241.00	-3.69	11.29	0	0	
Garden Gulch Member	6079.10	9.00	108.08	6070.00	-40.77	124.88	0	0	
Garden Gulch Member-1	6325.13	9.00	108.08	6313.00	-52.71	161.46	0	0	
Garden Gulch Member-2	6481.05	9.00	108.08	6467.00	-60.28	184.65	0	0	
Douglas Creek Member	7191.58	8.37	66.87	7169.00	-88.31	289.42	0	0	

5D Plan Report

Formation Points (Relative to Slot centre, TVD relative to Well TVD Reference)								
Name	MD (US ft)	Inc (°)	Az (°)	TVD (US ft)	N.Offset (US ft)	E.Offset (US ft)	F.Dip (°)	F.Dir (°)
B Limestone	7862.02	36.47	2.95	7788.00	136.27	346.15	0	0
Lower Black Shale	8121.71	49.95	359.88	7978.00	312.45	348.74	0	0
Castle Peak Limestone	8291.75	63.56	359.88	8071.00	454.31	348.45	0	0
CP1	8370.13	69.83	359.88	8102.00	526.26	348.29	0	0
CP2 (Hz Target)	8585.60	87.06	359.88	8145.00	736.57	347.85	0	0
CP 2.5	-1.#J	0.00	0.00	5133.00	-7216313.00	-2160168.90	0	0
Uteland Butte	-1.#J	0.00	0.00	5133.00	-7216313.00	-2160168.90	0	0

Newfield Production Company**15-13-12-3-2WB****Surface Hole Location: 75' FNL, 2332' FEL, Section 24, T3S, R2W****Bottom Hole Location: 525' FNL, 1980' FEL, Section 12, T3S, R2W****Duchesne County, UT****Drilling Program****1. Formation Tops**

Uinta	surface
Green River	3,289'
Garden Gulch	6,076'
Castle Peak Lime	7,781'
0	0'
Lateral TD	8,581' TVD / 17,836' MD

2. Depth to Oil, Gas, Water, or Minerals

Base of moderately saline	5,133'	(water)
Green River	6,076' - 0'	(oil)
0	0' - 8,581'	(oil)

3. Pressure ControlSection BOP Description

Surface Diverter

Intermediate The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc for a 5M system.

Prod/Prod Liner The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc for a 5M system.

A 5M BOP system will consist of 2 ram preventers (double or two singles) and an annular preventer (see attached diagram). A choke manifold rated to at least 5,000 psi will be used.

4. Casing

Description	Interval		Weight (ppf)	Grade	Couple	Pore Press @ Shoe	MW @ Shoe	Frac Grad @ Shoe	Safety Factors		
	Top	Bottom (TVD/MD)							Burst	Collapse	Tension
Conductor	0'	60'	--	--	Weld	--	--	--	--	--	--
20									--	--	--
Surface	0'	1,500'	54.5	J-55	STC	8.33	8.4	14	2,730	1,130	514,000
13 3/8									2.89	2.63	6.29
Intrm Drilling	0'	8,000'	40	N-80	BTC	10	10.5	16	5,750	3,090	916,000
9 5/8		8,100'							1.33	1.41	2.86
Production	0'	8,581'	20	P-110	BTC	14	14.5	17	12,360	11,080	641,000
5 1/2		17,836'							2.49	2.14	1.80

Assumptions:

Surface casing MASP = (frac gradient + 1.0 ppg) - (gas gradient)
 Intermediate casing drilling MASP = 0.5 ppg gas kick with a 70 bbl gain and frac at the shoe with a 1 ppg safety factor
 Production casing MASP = (reservoir pressure) - (gas gradient)
 Intermediate collapse calculations assume 50% evacuated
 Maximum intermediate csg collapse load assumes loss of mud to a fluid level of 4,000'
 Intermediate csg run from surface to 8,000' TVD and will not experience full evacuation
 Production csg run from surface to TD will isolate intermediate csg from production loads
 Production csg withstands burst and collapse loads for anticipated production conditions
 Surface & production collapse calcs assume fully evacuated casing w/ a gas gradient
 All tension calculations assume air weight of casing
 Gas gradient = 0.15 psi/ft

All casing shall be new.

All casing strings shall have a minimum of 1 centralizer on each of the bottom 3 joints.

5. Cement

Job	Hole Size	Fill	Slurry Description	ft ³	OH excess	Weight (ppg)	Yield (ft ³ /sk)
				sacks			
Conductor	24	60'	Class G w/ 2% KCl + 0.25 lbs/sk Cello Flake	66	15%	15.8	1.17
				57			
Surface Lead	17 1/2	1,000'	Type V Cement + 16% Bentonite + 10 lbs/sk Kol Seal + 3% NaCl	799	15%	12.0	2.86
				279			
Surface Tail	17 1/2	500'	Type V Cement + 16% Bentonite + 10 lbs/sk Kol Seal + 3% NaCl	399	15%	14.0	1.4
				285			
Intermediate Lead	12 1/4	6,076'	HLC Premium - 35% Poz/65% Glass G + 10% bentonite	2189	15%	12.0	3.53
				620			
Intermediate Tail	12 1/4	2,024'	50/50 Poz/Class G + 1% bentonite	729	15%	14.0	1.29
				565			
Production Lead	8 3/4	830'	Elastiseal Unfoamed	231	10%	14.5	1.84
				125			
Production Tail	8 3/4	9,406'	Elastiseal Foamed	2376	0%	14.5 - 17.3	1.84
				1291			

The surface casing will be cemented to surface. In the event that cement does not reach surface during the primary cement job, a remedial job will be performed.

Actual cement volumes for the intermediate casing string will be calculated from an open hole caliper log or gauge hole if logs are not ran, plus 15% excess.

The 5.5" production string will be run from surface to TD and cemented to setback. The cement slurries will be adjusted for hole conditions and blend test results. The lateral will be cemented past the setback.

The wellbore will cross the heel setback @ 8,430' MD

The first perforation will be within 17,701' MD

Per the directional plan, the bore hole will be drilled 135' past the toe setback for the rat hole and shoe track. This well will not be perforated or produced outside the legal setbacks.

6. Type and Characteristics of Proposed Circulating Medium

<u>Interval</u>	<u>Description</u>
Surface - 1,500'	An air and/or fresh water system will be utilized. If an air rig is used, the blooie line discharge may be less than 100' from the wellbore in order to minimize location size. The blooie line is not equipped with an automatic igniter. The air compressor may be located less than 100' from the well bore due to the low possibility of combustion with the air/dust mixture. Water will be on location to be used as kill fluid, if necessary.

1,500' - 8,100' One of two possible mud systems may be used depending on offset well performance on ongoing wells: A
water based mud: Hole stability may be improved with additions of KCl or a similar inhibitive substance. In order to control formation pressure the system will be weighted with additions of bentonite, and if conditions warrant, with barite.

-or-

A diesel based OBM system: with an oil to water ratio between 70/30 and 80/20. Emulsifiers and wetting agents will be used to maintain adequate mud properties. A water phase salinity will be maintained in the range of 25% using CaCl (Calcium Chloride). All cuttings will be dried and centrifuged so that they can be easily transferred to a lined cuttings pit with little to no free fluid on them. The cuttings will be mixed with fly ash prior to transportation to a location on Newfield owned surface. Once on Newfield owned surface, the cuttings will be treated with the previously approved FIRMUS process and used as a construction material on future location and/or roads on Newfield owned surface. The cuttings may also be transported to a state approved disposal facility.

Anticipated maximum mud weight is 10.5 ppg.

8,100' - TD One of two possible mud systems may be used depending on offset well performance on ongoing wells: A
water based mud: Hole stability may be improved with additions of KCl or a similar inhibitive substance. In order to control formation pressure the system will be weighted with additions of bentonite, and if conditions warrant, with barite.

-or-

A diesel based OBM system: with an oil to water ratio between 70/30 and 80/20. Emulsifiers and wetting agents will be used to maintain adequate mud properties. A water phase salinity will be maintained in the range of 25% using CaCl (Calcium Chloride). All cuttings will be dried and centrifuged so that they can be easily transferred to a lined cuttings pit with little to no free fluid on them. The cuttings will be mixed with fly ash prior to transportation to a location on Newfield owned surface. Once on Newfield owned surface, the cuttings will be treated with the previously approved FIRMUS process and used as a construction material on future location and/or roads on Newfield owned surface. The cuttings may also be transported to a state approved disposal facility.

Anticipated maximum mud weight is 14.5 ppg.

7. Logging, Coring, and Testing

Logging: A dual induction, gamma ray, and caliper log may be run from KOP to the base of the surface casing. An azimuthal gamma ray LWD log will be run from the shoe of the intermediate casing to TD. A cement bond log will be run from KOP to the cement top behind the production casing and or intermediate casing.

Cores: As deemed necessary.

DST: There are no DST's planned for this well.

8. Anticipated Abnormal Pressure or Temperature

Maximum anticipated bottomhole pressure will be approximately equal to total depth (feet) multiplied by a 0.73 psi/ft gradient.

$$8,581' \times 0.73 \text{ psi/ft} = 6247 \text{ psi}$$

No abnormal temperature is expected. No H₂S is expected.

9. Other Aspects

The lateral of this well will target the Wasatch formation

After setting 9-5/8" casing, an 8-3/4" vertical hole will be drilled to a kick off point of 7,559'

Directional tools will then be used to build to 87.11 degrees inclination.

The lateral will be drilled to the bottomhole location shown on the plat. A 5-1/2" longstring will be run from surface to TD and cemented in place.

Newfield requests the following variances from Onshore Order #2:

- Variance from Onshore Order #2, III.E.1


Refer to Newfield Production Company Standard Operating Practices "Ute Tribal Green River Development Program" paragraph 9.0

If oil based mud (OBM) is used and If Newfield owns the surface rights on the same drilling site at a location where construction is desired, the cuttings may be used for construction by a Firmus® process at that location. Otherwise, after the cuttings have been made safe for transport as described in paragraph 6, they will be transported to another location on which Newfield owns surface rights and there mixed, as part of a Firmus® process, with at least one additional chemical that will convert them to a temporarily uncured cementitious mixture that will be placed and shaped into a temporary desired final structure that will spontaneously harden within seven days after placement to form the desired structure. Samples of the temporary desired final structure may be taken for testing as described below (after the samples have hardened), or samples of the starting pretreated cuttings and mud will be taken during the construction and later mixed in a laboratory, molded, and cured to simulate the final structure as well as reasonably possible. Either these laboratory-made simulations of the final structure or samples of the temporary mixture itself after hardening, will be mechanically tested directly to determine their unconfined compressive strength and their hydraulic conductivity. Leachates of the mechanically tested structures themselves or of finer particles made by crushing and size-grading of the mechanically tested structures themselves to a specified particle size range will be analyzed, according to specified methods, for their contents of arsenic, barium, cadmium, chromium, lead, mercury, selenium, silver, zinc, benzene, total petroleum hydrocarbons (TPH), and chlorides, and the pH of these leachates will also be measured. The results of all these tests will be reported by Newfield to UDOGM at intervals as requested, along with the latitude and longitude (or other comparable location data) of the site of the useful constructions built.


Water flows in the surface hole are possible. If the water flow is less than 400 bbls/hr, the well will be allowed to flow until the surface casing point is reached and water will be hauled off location. If the water flow is greater than 400 bbls/hr, the water flow will be controlled with kill weight mud which will be maintained until TD. In both situations, the cement density will be adjusted to meet or exceed the mud weight needed to kill the water flow and the well will be shut in once cement is in place. If cement fails to reach the surface or falls back, a top job will be performed to bring cement to surface. Any water flows will be sampled and tested and results will be sent to UDOGM.

A diverter will be used to drill the surface hole interval.

Typical 5M BOP stack configuration



Typical 5M choke manifold configuration



NEWFIELD EXPLORATION COMPANY

TYPICAL CROSS SECTIONS FOR

#15-13-12-3-2WB

SECTION 24, T3S, R2W, U.S.B.&M.

75' FNL 2332' FEL

1" = 40'
X-Section
Scale
1" = 100'

FIGURE #2





SCALE: 1" = 60' DATE:

02-15-12 DRAWN BY:

J.J.

REVISED: 04-03-12

REVISED: 07-30-14 C.D.



NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.

APPROXIMATE ACREAGES

WELL SITE DISTURBANCE = ± 4.591 ACRES
ACCESS ROAD DISTURBANCE = ± 0.701 ACRES
PIPELINE DISTURBANCE = ± 1.195 ACRES
TOTAL = ± 6.487 ACRES

* NOTE:

FILL QUANTITY INCLUDES 5% FOR COMPACTION

APPROXIMATE YARDAGES

(12") Topsoil Stripping = 4,740 Cu. Yds.
Remaining Location = 5,390 Cu. Yds.
TOTAL CUT = 10,130 CU.YDS.
FILL = 4,490 CU.YDS.

EXCESS MATERIAL = 5,640 Cu. Yds.
Topsoil & Pit Backfill = 5,640 Cu. Yds.
(1/2 Pit Vol.)
EXCESS UNBALANCE = 0 Cu. Yds.
(After Interim Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING

85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

RECEIVED: Sep. 11, 2014

75' FNL 2332' FEL

REVISÉ: 07-30-14 C.D.



NEWFIELD EXPLORATION COMPANY

TYPICAL RIG LAYOUT FOR

#15-13-12-3-2WB

SECTION 24, T3S, R2W, U.S.B.&M.

75' FNL 2332' FEL

FIGURE #3




SCALE: 1" = 60' DATE:

02-15-12 DRAWN BY:

J.J.

REVISED: 04-03-12

REVISED: 07-30-14 C.D.



Total Pit Capacity
W/2' of Freeboard
= 5,930 Bbls.±
Total Pit Volume
= 1,790 Cu. Yds

Proposed
Access Road

UINTAH ENGINEERING & LAND SURVEYING

85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

RECEIVED: Sep. 11, 2014

NEWFIELD EXPLORATION COMPANY

PRODUCTION FACILITY LAYOUT FOR

#15-13-12-3-2WB

SECTION 24, T3S, R2W, U.S.B.&M.

75' FNL 2332' FEL

FIGURE #4

SCALE: 1" = 60' DATE:




02-15-12 DRAWN BY:

J.J.

REVISED: 04-03-12

REVISED: 04-27-12

REVISED: 07-30-14 C.D.



RECLAIMED AREA

APPROXIMATE ACREAGES

UN-RECLAIMED = ± 1.338 ACRES

UINTAH ENGINEERING & LAND SURVEYING


85 So. 200 East * Vernal, Utah 84078 * (435) 789-1017

RECEIVED: Sep. 11, 2014

NEWFIELD EXPLORATION COMPANY
#15-13-12-3-2WB
SECTION 24, T3S, R2W, U.S.B.&M.

PROCEED IN A NORTHEASTERLY, THEN NORTHERLY DIRECTION FROM MYTON, UTAH ALONG HIGHWAY 40 APPROXIMATELY 1.0 MILES TO THE JUNCTION OF HIGHWAY 40 AND 6250 SOUTH TO THE EAST; TURN RIGHT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 0.5 MILES TO THE BEGINNING OF THE PROPOSED ACCESS ROAD TO THE NORTH; FOLLOW ROAD FLAS IN A NORTHERLY DIRECTION APPROXIMATELY 1,110' TO THE PROPOSED LOCATION.

TOTAL DISTANCE FROM MYTON, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 1.7 MILES.



LEGEND:

 PROPOSED LOCATION

NEWFIELD EXPLORATION COMPANY

#15-13-12-3-2WB
SECTION 24, T3S, R2W, U.S.B.&M.
NW 1/4 NE 1/4




Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813

ACCESS ROAD
MAP

02 14 12
MONTH DAY YEAR



SCALE: 1:100,000 DRAWN BY: B.D.H. REV: 07-30-14 L.S.



LEGEND:

	EXISTING ROAD
	PROPOSED ACCESS ROAD
	EXISTING FENCE
	EXISTING POWER LINE
	EXISTING FIBER OPTIC LINE



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813



NEWFIELD EXPLORATION COMPANY


#15-13-12-3-2WB
SECTION 24, T3S, R2W, U.S.B.&M.
NW 1/4 NE 1/4

**ACCESS ROAD
MAP**

02 14 12
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: B.D.H. REV: 07-30-14 L.S.

B
TOPO



LEGEND:

- DISPOSAL WELLS
- PRODUCING WELLS
- SHUT IN WELLS
- ABANDONED WELLS
- TEMPORARILY ABANDONED

NEWFIELD EXPLORATION COMPANY

#15-13-12-3-2WB
SECTION 24, T3S, R2W, U.S.B.&M.
NW 1/4 NE 1/4



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813




TOPOGRAPHIC
MAP

02 14 12
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: B.D.H. REV: 07-30-14 L.S.

C
TOPO



APPROXIMATE TOTAL PIPELINE DISTANCE = 1,870' +/-

LEGEND:

- PROPOSED ACCESS ROAD
- EXISTING PIPELINE
- - - - - PROPOSED PIPELINE
- - - - - PROPOSED PIPELINE (SERVICING OTHER WELLS)

NEWFIELD EXPLORATION COMPANY

#15-13-12-3-2WB
SECTION 24, T3S, R2W, U.S.B.&M.
NW 1/4 NE 1/4



Uintah Engineering & Land Surveying
85 South 200 East Vernal, Utah 84078
(435) 789-1017 * FAX (435) 789-1813



**TOPOGRAPHIC
MAP**

02 14 12
MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: B.D.H. REV: 07-30-14 L.S.

**D
TOPO**

NEWFIELD



Newfield Exploration Company

1001 17th Street | Suite 2000

Denver, Colorado 80202

PH 303-893-0102 | FAX 303-893-0103

August 12, 2014

State of Utah
Division of Oil, Gas & Mining
ATTN: Brad Hill
PO Box 145801
Salt Lake City, UT 84114

RE: Powvitch 15-13-12-3-2WB
Township 3 South, Range 2 West, Sections 12 & 13
Duchesne County, Utah

Dear Mr. Hill:

Newfield Production Company ("Newfield") proposes to drill the Powvitch 15-13-12-3-2WB from a surface location of 75' FNL and 2332' FEL of Section 24, T3S-R2W, to a bottom hole location of 525' FNL and 1980' FEL of Section 12, T3S-R2W.

The Powvitch 15-13-12-3-2WB is covered by Order No. 139-120, which requires that no producing interval of the horizontal lateral be closer than 660' from the drilling unit boundaries, and requires proper surface and sub-surface authorization be obtained when the surface location is located off of the drilling unit.

In compliance with the above referenced Order, the top of the producing interval of the Powvitch 15-13-12-3-2WB is 660' FSL and 1980' FEL of T3S-R2W Section 13, and the bottom of the producing interval is 660' FNL 1980' FEL of Section 12. Newfield shall case and cement the Powvitch 15-13-12-3-2WB from the surface location to the point where the wellbore reaches the legal setback, and the wellbore will only be completed within the legal setback.

In further compliance of the above referenced Order, Newfield has obtained authorization from the surface owner of the drilling location, as is evidenced by the Affidavit of Easement, Right-of-Way and Surface Use Agreement attached to the APD. Newfield and its partners are leasehold owners of minerals underlying the surface location and all that portion of the wellbore of the Powvitch 15-13-12-3-2WB.

Based on Newfield's compliance with the requirements of Order No. 139-120, Newfield respectfully requests the approval of our APD for the Powvitch 15-13-12-3-2WB.

Should you have questions or require further information, please do not hesitate to contact the undersigned at 303-383-4122 or by email at tdalbec@newfield.com. Your consideration of this matter is greatly appreciated.

My Regards,

Thomas Dalbec
Land Tech
Newfield Exploration Company

Plat depiction including Lease Numbers


Powvitch 15-13-12-3-2WB

SHL 75' FNL & 2332' FEL of Section 24

Top of Producing Interval 660' FSL & 1980' FEL of Section 13

Bottom of Producing Interval 660' FNL & 1980' FEL of Section 12

BHL 525' FNL & 1980' FWL of Section 12



Lessor: Fee Simple Interest
Legal: Sec. 12 W2E2

Lessor: Fee Simple Interest
Legal: Sec. 13 W2NE, NWSE

Lease: 14-20-H62-6173
Lessor: Heirs of ANNIE POWVITCH
Legal: Sec. 13 SWSE

Lease: 14-20-H62-6176
Lessor: Heirs of ANNIE POWVITCH
Legal: Sec. 24 NWNE



BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Pete Martin Rig #16
Submitted By Kylan Cook Phone Number 435-790-8236
Well Name/Number Powitch 15-13-12-3-2WB
Qtr/Qtr NW/NE Section 24 Township 3S Range 2W
Lease Serial Number 14-20-H62-6176
API Number 43-013-51942

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time 09/13/2014 09:30 AM ☒ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing
- ☐ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☐ Other

Date/Time _____ AM ☐ PM ☐

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

Date/Time _____ AM ☐ PM ☐

Remarks _____

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-H62-6176
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: POWVITCH 15-13-12-3-2WB
PHONE NUMBER: 435 646-4825 Ext		9. API NUMBER: 43013519420000
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0075 FNL 2332 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 24 Township: 03.0S Range: 02.0W Meridian: U		9. FIELD and POOL or WILDCAT: NORTH MYTON BENCH
		COUNTY: DUCHESNE
		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start: <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 9/14/2014 <input type="checkbox"/> DRILLING REPORT Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION OTHER: <input style="width: 100%;" type="text"/> </div> </div>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Pete Martin Rig #16 spudded 26" hole on 09/14/2014 and drilled to 60' GL. Set 20", 52.78# (0.250" wall), SA53B conductor pipe at 60' GL and cemented to surface with Redi Mix. Kylan Cook notified UDOGM and BLM by e-mail @ 09:30 AM on 09/12/2014 to spud conductor hole on 09/13/2014.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY October 14, 2014		
NAME (PLEASE PRINT) Cherei Neilson	PHONE NUMBER 435 646-4883	TITLE Drilling Technician
SIGNATURE N/A	DATE 10/13/2014	

NEWFIELD

Casing

Conductor

Legal Well Name Powitch 15-13-12-3-2WB				Wellbore Name Original Hole					
API/UWI 43013519420000		Surface Legal Location NWNE 75FNL 2332FEL SEC24 T3S R2W MERU		Field Name UINTA CB - BAR F HORZ		Well Type Development		Well Configuration Type Horizontal	
Well RC 500358785		County Duchesne		State/Province Utah		Spud Date		Final Rig Release Date	

Wellbore								
Wellbore Name Original Hole				Kick Off Depth (ftKB)				
Section Des		Size (in)	Actual Top Depth (MD) (ftKB)	Actual Bottom Depth (MD) (ftKB)	Start Date		End Date	
Conductor		26	26	86	9/14/2014		9/14/2014	

Wellhead				
Type	Install Date	Service	Comment	

Wellhead Components				
Des	Make	Model	SN	WP Top (psi)

Casing							
Casing Description Conductor		Set Depth (ftKB) 86		Run Date 9/14/2014		Set Tension (kips)	
Centralizers				Scratchers			

Casing Components												
Item Des	OD (in)	ID (in)	Wt (lb/ft)	Grade	Top Thread	Jts	Len (ft)	Top (ftKB)	Btm (ftKB)	Mk-up Tq (ft-lb)	Class	Max OD (in)
Conductor Pipe	20	19.000	52.78	SA53B	Welded	2	60.00	26.0	86.0			

Jewelry Details									
External Casing Packer									
Type	Setting Requirement			Release Requirements			Inflation Method	Vol Inflation (gal)	Equiv Hole Sz (in)
Inflation Fluid Type	Infl Fl Dens (lb/gal)	P AV Set (psi)	AV Acting Pressure (psi)	P ICV Set (psi)	P ICV Act (psi)	ECP Load (1000lbf)	Seal Load (1000lbf)		

Slotted Liner							
% Open Area (%)	Perforation Min Dimension (in)	Perforation Max Dimension (in)	Axial Perf Spacing (ft)	Perf Rows	Blank Top Length (ft)	Blank Bottom Length (ft)	
Slot Description	Slot Pattern			Slot Length (in)	Slot Width (in)	Slot Frequency	Screen Gauge (ga)

Liner Hanger					
Retrievable?	Elastomer Type	Element Center Depth (ft)		Polish Bore Size (in)	Polish Bore Length (ft)
Slip Description				Set Mechanics	

Setting Procedure					
Unsetting Procedure					

NEWFIELD

Casing

Surface

Legal Well Name Powwitch 15-13-12-3-2WB		Wellbore Name Original Hole	
API/UWI 43013519420000	Surface Legal Location NWNE 75FNL 2332FEL SEC24 T3S R2W MERU	Field Name UINTA CB - BAR F HORZ	Well Type Development
Well RC 500358785	County Duchesne	State/Province Utah	Spud Date
		Final Rig Release Date	

Wellbore					
Wellbore Name Original Hole			Kick Off Depth (ftKB)		
Section Des	Size (in)	Actual Top Depth (MD) (ftKB)	Actual Bottom Depth (MD) (ftKB)	Start Date	End Date
Conductor	26	26	86	9/14/2014	9/14/2014
Vertical	17 1/2	86	1,676	9/15/2014	9/17/2014
Vertical	12 1/4	1,676	8,023	9/17/2014	10/6/2014

Wellhead				
Type	Install Date	Service	Comment	

Wellhead Components				
Des	Make	Model	SN	WP Top (psi)

Casing			
Casing Description Surface	Set Depth (ftKB) 1,663	Run Date 9/18/2014	Set Tension (kips)
Centralizers 14 centralizers spaced 10' from the shoe, on top of joints #2 & #3 then every 3rd collar to surface.		Scratchers	

Casing Components												
Item Des	OD (in)	ID (in)	Wt (lb/ft)	Grade	Top Thread	Jts	Len (ft)	Top (ftKB)	Btm (ftKB)	Mk-up Tq (ft-lb)	Class	Max OD (in)
Casing Joints	13 3/8	12.615	54.50	J-55	BTC	38	1,593.97	25.8	1,619.8			
Float Collar	13 3/8	12.615			BTC	1	1.50	1,619.8	1,621.3			
Casing Joints	13 3/8	12.615	54.50	J-55	BTC	1	40.72	1,621.3	1,662.0			
Guide Shoe	13 3/8	12.615			BTC	1	1.00	1,662.0	1,663.0			

Jewelry Details							
External Casing Packer							
Type	Setting Requirement	Release Requirements			Inflation Method	Vol Inflation (gal)	Equiv Hole Sz (in)
Inflation Fluid Type	Infl FI Dens (lb/gal)	P AV Set (psi)	AV Acting Pressure (psi)	P ICV Set (psi)	P ICV Act (psi)	ECP Load (1000lbf)	Seal Load (1000lbf)

Slotted Liner							
% Open Area (%)	Perforation Min Dimension (in)	Perforation Max Dimension (in)	Axial Perf Spacing (ft)	Perf Rows	Blank Top Length (ft)	Blank Bottom Length (ft)	
Slot Description	Slot Pattern			Slot Length (in)	Slot Width (in)	Slot Frequency	Screen Gauge (ga)

Liner Hanger				
Retrievable?	Elastomer Type	Element Center Depth (ft)	Polish Bore Size (in)	Polish Bore Length (ft)
Slip Description			Set Mechanics	
Setting Procedure				
Unsetting Procedure				

3000psi - 5000psi
system


DATE	9-27-2014
COMPANY	Newfield
CONTRACTOR	Pioneer 44
WELL NAME/NO.	PONVitch 15-13-12-3-2WB


AB 013 51942
2A 3S 2W

RECEIVED

OCT 02 2014

DIV. OF OIL, GAS & MINING





WALKER INSPECTION,LLC.
REBEL TESTING • EAGER BEAVER TESTERS
 WYOMING • COLORADO • NORTH DAKOTA

Daily JSA/Observation Report

OPERATOR: Newfield
 LOCATION: Pawatch 15-13-12-3-2WB
 EMPLOYEE NAME: Dustin Redmond

DATE: 9-27-2014
 CONTRACTOR: Pioneer 44

☒ High Pressure Testing

COMMENTS: Safety awareness

☒ Working Below Platform

☒ Requires PPE

☒ Overhead Work is Occurring

☐ Confined Spaces are Involved

☐ Set up of Containment

☒ Using Rig Hoist to Lift Tools

☐ Other:

SIGNATURE: [Signature]

DATE: 9-27-2014

WALKER INSPECTION, LLC. AND AFFILIATES

ATTENDANCE:

<u>[Signature]</u>	<u>[Signature]</u>	
<u>[Signature]</u>		
<u>[Signature]</u>		
<u>[Signature]</u>		
<u>[Signature]</u>		
<u>[Signature]</u>		

Observation Report

EMPLOYEE REPORTING: Dustin Redmond SIGNATURE: [Signature]

Was job set up and performed correctly and to best of companies ability? ☒ Y ☐ N

Was all safety equipment used correctly by all involved? ☒ Y ☐ N

Any incidents or near misses to report about WI? Y ☒ N

Any incidents or near misses to report in general? Y ☒ N

Any spills or environmental issues to report? Y ☒ N

Basic Comments: _____

Mud Lines

RECEIVED

OCT 02 2014

DIV. OF OIL, GAS & MINING

Dart Valve

1 BOP

Manual BOP


TIW Valve

10000 - 5000 psi System

Riser Valve

Casing

24	35	2W
Date	9/26/14	
Company	Newfield	
Contractor	Pioneer 44	
Well Name & #	Powitch 15-13-12-3-2WB 43 013 51942	



DATE 9/26/14 COMPANY: Newfield

RIG: Pioneer 44

Well Name & #: POWITCH 15-13-12-3-248

Time	Test No.	Result:
NO TEST AM <input type="checkbox"/> PM <input type="checkbox"/>	1	Annular (caught no pressure) Pass <input type="checkbox"/> Fail <input checked="" type="checkbox"/>
3:47 AM <input type="checkbox"/> PM <input type="checkbox"/>	2	^{Upper} Lower Pipe Rams, Hyd. IBOP, Inside Kill, Manual Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/>
4:11 AM <input type="checkbox"/> PM <input type="checkbox"/>	3	Lower Pipe Rams, Man. IBOP, HCR, Outside Kill Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/>
4:44 AM <input type="checkbox"/> PM <input type="checkbox"/>	4	Check Valve, Dart Valve, TIW, Inside Choke Manifold, ^{Riser} Valve Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/>
5:25 AM <input type="checkbox"/> PM <input type="checkbox"/>	5	Blind Rams, Outside Choke Manifold Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/>
5:55 AM <input type="checkbox"/> PM <input type="checkbox"/>	6	Super Choke Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/>
6:27 AM <input type="checkbox"/> PM <input type="checkbox"/>	7	Downstream Manifold Valves Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/>
7:08 AM <input type="checkbox"/> PM <input type="checkbox"/>	8	Casing Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/>
3:22 AM <input type="checkbox"/> PM <input type="checkbox"/>	9	Annular Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	10	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	11	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	12	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	13	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	14	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	Retest	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	Retest	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	Retest	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	Retest	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	Retest	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	Retest	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	Retest	Pass <input type="checkbox"/> Fail <input type="checkbox"/>

Acc. Tank Size (inches) (W D L) ÷ 231 = gal.

Rock Springs, WY (307) 382-3350

BOP TESTING, CASING TESTING, LEAK OFF TESTING, &
 INTEGRITY TESTING
 NIPPLE UP CREWS, NITROGEN CHARGING SERVICE

DATE: 9/26/14

ACCUMULATOR FUNCTION TEST

WELL: Powerville 15-13-12-3-2W8

TO CHECK THE USABLE FLUID STORED IN THE NITROGEN BOTTLES ON THE
ACCUMULATOR (OO #2 III.A.2.c.i. or ii or iii)

1. Make sure all rams and annular are open and if applicable HCR is closed
2. Ensure accumulator is pumped up to working pressure! (Shut off all pumps)
3. Open HCR valve. (If applicable)
4. Close annular.
5. Close all pipe rams.
6. Open one set of pipe rams to simulate closing the blind rams.
7. If you have a 3 Ram stack open the annular to achieve the 50 +/- % safety factor for 5M and greater systems.
8. Accumulator pressure should be 200 psi over precharge pressure
(Accumulator working pressure (1,500 psi = 750 desired psi)
(2,000 and 3,000 psi = 1,000 desired psi)).

9. RECORD THE REMAINING PRESSURE 1700 PSI

If annular is closed, open it at this time and close HCR.

TO CHECK THE CAPACITY OF THE ACCUMULATOR PUMPS (OO #2 III.A.2.f.)

Shut the accumulator bottles or spherical (Isolate them from the pumps & manifold) open the bleed off valve to the tank (Manifold psi should go to zero psi) close bleed valve.

1. Open the HCR valve. (If applicable)
2. Close annular.
3. With pumps only, time how long it takes to re- gain manifold pressure to 200 psi over desired precharge pressure! (Accumulator working pressure (1,500 psi = 750 psi desired psi) (2,000 and 3,000 psi = 1,000 desired psi)).


4. RECORD ELAPSED TIME 0 min 54 sec PSI (2 minutes or less)


TO CHECK THE PRECHARGE ON THE BOTTLES OR SPHERICAL (OO #2 III.A.2.d.)

1. Open bottles back up to the manifold (pressure should be above the desired precharge pressure (1,500 psi = 750 psi desired psi) (2,000 and 3,000 psi = 1,000 desired psi)) may need to use pumps to pressure back up.
2. With power to pumps shut off open bleed line to tank.
3. Watch and record where the pressure drops (Accumulator psi).

4. RECORD THE PRESSURE DROP 900 PSI

If pressure drops below MINIMUM precharge (Accumulator working pressure (1,500 psi = 700 psi minimum) (2,000 and 3,000 psi = 900 psi minimum)) each bottle shall be independently checked with a guage.





CONFIDENTIAL

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Pioneer 44 Submitted
By Sam Loreda/ Walt Bowen Phone Number 970/623/7080
Well Name/Number Powvitch 15-13-12-3-2WB
Qtr/Qtr NE/NW Section 24 Township 3S Range 2W
Lease Serial Number 14-20-H62-6176
API Number 43013519420000

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time _____ AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing
- ☒ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 10-7-2014 12:01 AM ☐ PM ☒

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

Date/Time _____ AM ☐ PM ☐

Remarks We Will Be Running 9-5/8" Intermediate Casing on the Powvitch 15-13-12-3-2 WB.

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Pioneer 44 Submitted
By Sam Loreda/ Walt Bowen Phone Number 970/623/7080
Well Name/Number Powvitch 15-13-12-3-2WB
Qtr/Qtr NE/NW Section 24 Township 3S Range 2W
Lease Serial Number 14-20-H62-6176
API Number 43013519420000

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time _____ AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing
- ☐ Intermediate Casing
- ☒ Production Casing
- ☐ Liner
- ☐ Other

Date/Time 10-23-2014 11:00 AM ☐ PM ☒

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

Date/Time _____ AM ☐ PM ☐

Remarks We Will Be Running 5-1/2" Production Casing on the
Powvitch 15-13-12-3-2 WB Starting at 23:00 Hrs 10-23-14 to
06:00 Hours 10-24-14.

15-13-12-3-2 WB Starting at 23:00 Hrs 10-23-14 to
06:00 Hours 10-24-14.

CONFIDENTIAL

BLM - Vernal Field Office - Notification Form

Operator Newfield Exploration Rig Name/# Pioneer 44 Submitted
By Sam Loreda/ Walt Bowen Phone Number 970/623/7080
Well Name/Number Powitch 15-13-12-3-2WB
Qtr/Qtr NE/NW Section 24 Township 3S Range 2W
Lease Serial Number 14-20-H62-6176
API Number 43013519420000

Spud Notice – Spud is the initial spudding of the well, not drilling out below a casing string.

Date/Time _____ AM ☐ PM ☐

Casing – Please report time casing run starts, not cementing times.

- ☐ Surface Casing
- ☐ Intermediate Casing
- ☐ Production Casing
- ☐ Liner
- ☒ Other

Date/Time 10-22-2014 13:30 AM ☐ PM ☒

BOPE

- ☐ Initial BOPE test at surface casing point
- ☐ BOPE test at intermediate casing point
- ☐ 30 day BOPE test
- ☐ Other

Date/Time _____ AM ☐ PM ☐


Remarks We have reached TD at 17,977' on the Powitch 15-13-12-3-2 WB.

DATE	10-10-2014
COMPANY	Wenfield
CONTRACTOR	Pioneer 44
WELLNAME	Powitch 15-13-12-3-2W

43 013.51942
24 35 2W

RECEIVED
OCT 21 2014

DIV. OF OIL, GAS & MINING



Casing
①
FIT ②

DATE: 10-10-14 COMPANY: Newfield


RIG: Pioneer 44

WELL NAME & # Powit/L 15-13-12-3-2WB

Time	Test No.	Results
8:31 AM <input checked="" type="checkbox"/> PM <input type="checkbox"/>	1 Casing	Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/>
1:22 AM <input checked="" type="checkbox"/> PM <input type="checkbox"/>	2 FIT Test	Pass <input checked="" type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	3	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	4	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	5	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	6	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	7	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	8	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	9	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	10	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	11	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	12	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	13	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	14	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	Retest	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	Retest	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	Retest	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	Retest	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	Retest	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	Retest	Pass <input type="checkbox"/> Fail <input type="checkbox"/>
AM <input type="checkbox"/> PM <input type="checkbox"/>	Retest	Pass <input type="checkbox"/> Fail <input type="checkbox"/>

Acc. Tank Size (inches) (W D L) ÷ 231 = gal.

Rock Springs, WY (307) 342-3350
BOP TESTING, CASING TESTING, LEAK OFF TESTING, &
INTEGRITY TESTING
NIPPLE UP CREWS, NITROGEN CHARGING SERVICE.



WALKER INSPECTION, LLC.
REBEL TESTING • EAGER BEAVER TESTERS
 WYOMING • COLORADO • NORTH DAKOTA

Daily JSA/Observation Report

OPERATOR: Newfield DATE: 10-10-2014
 LOCATION: Reynolds 15-13-12-3 NWB CONTRACTOR: Pioneer 44
 EMPLOYEE NAME: Dustin Redmond

- ☒ High Pressure Testing
☒ Working Below Platform
☒ Requires PPE
☒ Overhead Work is Occurring
☐ Confined Spaces are Involved
☐ Set up of Containment
☒ Using Rig Hoist to Lift Tools
☐ Other: _____

COMMENTS: Safety used

SIGNATURE: [Signature]

DATE: 10-10-2014

WALKER INSPECTION, LLC. AND AFFILIATES

ATTENDANCE:

<u>[Signature]</u>	<u>[Signature]</u>	
<u>[Signature]</u>	<u>[Signature]</u>	
<u>[Signature]</u>	<u>[Signature]</u>	
<u>[Signature]</u>	<u>[Signature]</u>	
<u>[Signature]</u>	<u>[Signature]</u>	
<u>[Signature]</u>	<u>[Signature]</u>	
<u>[Signature]</u>	<u>[Signature]</u>	
<u>[Signature]</u>	<u>[Signature]</u>	

Observation Report

EMPLOYEE REPORTING: Dustin Redmond SIGNATURE: [Signature]

Was job set up and performed correctly and to best of companies ability? ☒ Y ☐ N

Was all safety equipment used correctly by all involved? ☒ Y ☐ N

Any incidents or near misses to report about WI? ☐ Y ☒ N

Any incidents or near misses to report in general? ☐ Y ☒ N

Any spills or environmental issues to report? ☐ Y ☒ N

Basic Comments: _____

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-H62-6176
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: POWVITCH 15-13-12-3-2WB
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0075 FNL 2332 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 24 Township: 03.0S Range: 02.0W Meridian: U		9. API NUMBER: 43013519420000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: NORTH MYTON BENCH
COUNTY: DUCHESNE		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 12/16/2014	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> CONVERT WELL TYPE	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PLUG BACK	
	<input checked="" type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. The above well was placed on production (flowing) on 12/16/2014 at 13:00 hours.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY December 19, 2014		
NAME (PLEASE PRINT) Jennifer Peatross	PHONE NUMBER 435 646-4885	TITLE Production Technician
SIGNATURE N/A	DATE 12/19/2014	

Form 3160-4
(March 2012)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB NO. 1004-0137
Expires: October 31, 2014

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Dry <input type="checkbox"/> Other b. Type of Completion: <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Work Over <input type="checkbox"/> Deepen <input type="checkbox"/> Plug Back <input type="checkbox"/> Diff. Resrv., Other: _____						5. Lease Serial No. 1420H626176			
2. Name of Operator NEWFIELD PRODUCTION COMPANY						6. If Indian, Allottee or Tribe Name UINTAH AND OURAY			
3. Address ROUTE #3 BOX 3630 MYTON, UT 84052				3a. Phone No. (include area code) Ph:435-646-3721		7. Unit or CA Agreement Name and No.			
4. Location of Well (Report location clearly and in accordance with Federal requirements)* At surface 75' FNL 2332' FEL (NW/NE) SEC 24 T3S R2W At top prod. interval reported below 756' FSL 1835' FEL (NW/NE) SEC 13 T3S R2W At total depth 589' FNL 1975' FEL (NW/NE) SEC 12 T3S R2W						8. Lease Name and Well No. POWITCH 15-13-12-3-2WB			
14. Date Spudded 09/21/2014		15. Date T.D. Reached 10/28/2014		16. Date Completed 12/17/2014 <input type="checkbox"/> D & A <input checked="" type="checkbox"/> Ready to Prod.		9. API Well No. 43-013-51942			
18. Total Depth: MD 17967 TVD 10071		19. Plug Back T.D.: MD 17920 TVD		20. Depth Bridge Plug Set: MD TVD		17. Elevations (DF, RKB, RT, GL)* 5109' GL 5135' KB			
21. Type Electric & Other Mechanical Logs Run (Submit copy of each) DUAL IND GRD, SP, COMP. NEUTRON, GR, CALIPER, CMT BOND						22. Was well cored? <input type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Was DST run? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit report) Directional Survey? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes (Submit copy)			
23. Casing and Liner Record (Report all strings set in well)									
Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cement Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)	Cement Top*	Amount Pulled
19"	13-3/8" J-55	54.50	0'	1663'		1091 CLASS G			
12-5/8"	9-5/8" N-80	40	0'	8014'		1025 Versacem			
						590Expandacem			
8-7/8"	5-1/2" P-110	20	0'	17,967		1265 Tergovis			
						2090 Elasticem			
24. Tubing Record									
Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	
2-7/8"	EOT@7945'	XN@7900'							
25. Producing Intervals					26. Perforation Record				
Formation		Top	Bottom	Perforated Interval		Size	No. Holes	Perf. Status	
A) Wasatch		8612'	17,378	8612' - 17378'		0.38	1062		
B)									
C)									
D)									
27. Acid, Fracture, Treatment, Cement Squeeze, etc.									
Depth Interval			Amount and Type of Material						
8612' - 17378'			Frac w/ 8,500,419#s of proppant sand in 147,387 bbls of clean fluid, in 41 stages.						
28. Production - Interval A									
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
12/19/14	12/29/14	24	→	1019	627	2407			Flowing
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→					PRODUCING	
28a. Production - Interval B									
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

*(See instructions and spaces for additional data on page 2)

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

29. Disposition of Gas (Solid, used for fuel, vented, etc.)

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

GEOLOGICAL MARKERS

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				GARDEN GULCH MEMBER GARDEN GULCH 2	6073' 6469'
				DOUGLAS CREEK B LIMESTON	7171' 7754'
				CASTLE PEAK UTELAND BUTTE	8044' 8330'

32. Additional remarks (include plugging procedure):

Bottom Product Interval:

1060' FNL 1951' FEL (NW/NE) SEC 12 T3S R2W

33. Indicate which items have been attached by placing a check in the appropriate boxes:

- ☐ Electrical/Mechanical Logs (1 full set req'd.)
 ☐ Geologic Report
 ☐ DST Report
 ☒ Directional Survey
☐ Sundry Notice for plugging and cement verification
 ☐ Core Analysis
 ☒ Other: Drilling daily activity

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Heather CalderTitle Regulatory TechnicianSignature Heather CalderDate 01/20/2015

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 3)

(Form 3160-4, page 2)

NEWFIELD

Directional Survey



Legal Well Name Powwitch 15-13-12-3-2WB				Wellbore Name Original Hole					
API/UWI 43013519420000		Surface Legal Location NWNE 75FNL 2332FEL SEC24 T3S R2W MERU		Field Name UINTA CB - BAR F HORZ		Well Type Development		Well Configuration Type Horizontal	
Well RC 500358785		County Duchesne	State/Province Utah		Spud Date 9/21/2014 06:00		Final Rig Release Date 10/28/2014 00:00		

Actual Deviation Survey Actual, Proposed? No	Wellbore Name Original Hole	Parent Wellbore Original Hole	Job Drilling - Original, 9/21/2014 06:00	VS Dir (°)	Profile Type	Kick Off Depth (ftKB) 7,069
---	--------------------------------	----------------------------------	---	------------	--------------	--------------------------------

Date		Definitive?		Description		Proposed?	
9/16/2014		No		Actual		No	
MD Tie In (ftKB)	TVD Tie In (ftKB)	Inclination Tie In (°)		Azimuth Tie In (°)		NSTie In (ft)	EW Tie In (ft)

Survey Data

Date	MD (ftKB)	Incl (°)	Azm (°)	TVD (ftKB)	VS (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Build (°/100ft)	Turn (°/100ft)	Unwrap Displace (ft)	Method	Survey Company
9/16/2014	26	0.00	0.00	26	0	0	0	0.00	0.00	0.00	0.00	MWD	Payzone
10/5/2014	77	31.43	15.93	75	13	13	4	61.57	61.57	31.20	13.65	MWD	Weatherford
9/16/2014	116	0.18	120.56	112	23	23	7	80.81	-80.23	268.63	24.06	MWD	Payzone
9/16/2014	144	0.26	128.30	140	23	23	7	0.30	0.29	27.64	24.16	MWD	Payzone
9/16/2014	174	0.44	158.84	170	23	23	7	0.84	0.60	101.80	24.34	MWD	Payzone
9/16/2014	205	0.44	173.87	201	23	23	7	0.37	0.00	48.48	24.58	MWD	Payzone
9/16/2014	233	0.70	162.35	229	23	22	7	1.01	0.93	-41.14	24.86	MWD	Payzone
9/16/2014	260	0.31	172.11	256	22	22	7	1.47	-1.44	36.15	25.09	MWD	Payzone
9/16/2014	288	0.70	162.75	284	22	22	7	1.42	1.39	-33.43	25.34	MWD	Payzone
9/16/2014	317	0.70	181.78	313	22	22	7	0.80	0.00	65.62	25.69	MWD	Payzone
9/16/2014	346	0.97	176.81	342	21	21	7	0.96	0.93	-17.14	26.11	MWD	Payzone
9/16/2014	373	1.05	175.80	369	21	21	7	0.30	0.30	-3.74	26.59	MWD	Payzone
9/16/2014	401	0.83	187.53	397	20	20	7	1.04	-0.79	41.89	27.04	MWD	Payzone
9/16/2014	431	1.32	173.47	427	20	20	7	1.84	1.63	-46.87	27.60	MWD	Payzone
9/16/2014	459	1.49	177.03	455	19	19	7	0.68	0.61	12.71	28.29	MWD	Payzone
9/16/2014	493	1.32	175.36	489	18	18	7	0.51	-0.50	-4.91	29.12	MWD	Payzone
9/16/2014	523	1.45	181.56	519	18	17	7	0.66	0.43	20.67	29.85	MWD	Payzone
9/16/2014	553	1.49	182.22	548	17	17	7	0.14	0.13	2.20	30.62	MWD	Payzone
9/16/2014	583	1.36	183.01	578	16	16	7	0.44	-0.43	2.63	31.36	MWD	Payzone
9/16/2014	613	1.32	169.60	608	15	15	7	1.05	-0.13	-44.70	32.06	MWD	Payzone
9/16/2014	643	1.31	169.35	638	15	15	7	0.04	-0.03	-0.83	32.75	MWD	Payzone
9/16/2014	673	0.97	163.76	668	14	14	8	1.19	-1.13	-18.63	33.34	MWD	Payzone
9/16/2014	703	0.88	156.60	698	14	14	8	0.49	-0.30	-23.87	33.83	MWD	Payzone
9/16/2014	733	0.97	151.63	728	13	13	8	0.40	0.30	-16.57	34.31	MWD	Payzone
9/16/2014	763	0.85	139.23	758	13	13	8	0.77	-0.40	-41.33	34.78	MWD	Payzone
9/16/2014	793	0.75	120.96	788	13	12	8	0.91	-0.33	-60.90	35.20	MWD	Payzone
9/16/2014	823	0.83	113.88	818	13	12	9	0.42	0.27	-23.60	35.61	MWD	Payzone
9/16/2014	853	0.97	94.59	848	12	12	9	1.11	0.47	-64.30	36.07	MWD	Payzone
9/16/2014	883	1.05	94.24	878	12	12	10	0.27	0.27	-1.17	36.60	MWD	Payzone
9/16/2014	913	1.27	87.92	908	12	12	10	0.85	0.73	-21.07	37.21	MWD	Payzone
9/16/2014	943	1.71	89.36	938	12	12	11	1.47	1.47	4.80	37.99	MWD	Payzone
9/17/2014	973	1.80	93.93	968	12	12	12	0.55	0.30	15.23	38.91	MWD	Payzone
9/17/2014	1,003	1.89	97.71	998	12	12	13	0.50	0.30	12.60	39.87	MWD	Payzone
9/17/2014	1,033	1.76	94.81	1,028	12	12	14	0.53	-0.43	-9.67	40.83	MWD	Payzone
9/17/2014	1,063	1.36	88.57	1,058	12	12	15	1.45	-1.33	-20.80	41.64	MWD	Payzone
9/17/2014	1,093	1.54	91.21	1,088	12	12	16	0.64	0.60	8.80	42.40	MWD	Payzone
9/17/2014	1,123	1.45	86.20	1,118	12	12	16	0.53	-0.30	-16.70	43.18	MWD	Payzone
9/17/2014	1,153	1.54	80.53	1,148	13	12	17	0.58	0.30	-18.90	43.97	MWD	Payzone
9/17/2014	1,183	1.14	87.38	1,178	13	12	18	1.43	-1.33	22.83	44.67	MWD	Payzone
9/17/2014	1,213	1.01	68.44	1,208	13	12	18	1.25	-0.43	-63.13	45.22	MWD	Payzone
9/17/2014	1,243	0.83	64.80	1,238	13	12	19	0.63	-0.60	-12.13	45.70	MWD	Payzone
9/17/2014	1,273	0.79	85.58	1,268	13	12	19	0.98	-0.13	69.27	46.12	MWD	Payzone
9/17/2014	1,303	0.70	74.64	1,298	13	12	20	0.56	-0.30	-36.47	46.51	MWD	Payzone
9/17/2014	1,333	0.69	77.11	1,328	13	13	20	0.11	-0.03	8.23	46.87	MWD	Payzone
9/17/2014	1,363	0.40	80.62	1,358	13	13	20	0.97	-0.97	11.70	47.16	MWD	Payzone
9/17/2014	1,393	0.66	86.11	1,388	13	13	21	0.88	0.87	18.30	47.44	MWD	Payzone
9/17/2014	1,423	0.70	73.67	1,418	13	13	21	0.51	0.13	-41.47	47.79	MWD	Payzone
9/17/2014	1,453	0.79	99.12	1,448	13	13	21	1.13	0.30	84.83	48.17	MWD	Payzone
9/17/2014	1,483	0.53	102.02	1,478	13	13	22	0.87	-0.87	9.67	48.52	MWD	Payzone

NEWFIELD

Directional Survey



Legal Well Name Powwitch 15-13-12-3-2WB				Wellbore Name Original Hole					
API/UWI 43013519420000		Surface Legal Location NWNE 75FNL 2332FEL SEC24 T3S R2W MERU		Field Name UINTA CB - BAR F HORZ		Well Type Development		Well Configuration Type Horizontal	
Well RC 500358785		County Duchesne		State/Province Utah		Spud Date 9/21/2014 06:00		Final Rig Release Date 10/28/2014 00:00	

Survey Data

Date	MD (ftKB)	Incl (°)	Azm (°)	TVD (ftKB)	VS (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Build (°/100ft)	Turn (°/100ft)	Unwrap Displace (ft)	Method	Survey Company
9/17/2014	1,513	1.05	104.08	1,508	13	13	22	1.74	1.73	6.87	48.93	MWD	Payzone
9/17/2014	1,543	1.23	99.42	1,538	13	12	23	0.67	0.60	-15.53	49.52	MWD	Payzone
9/17/2014	1,573	1.36	97.53	1,568	13	12	23	0.46	0.43	-6.30	50.20	MWD	Payzone
9/17/2014	1,586	1.23	90.99	1,581	13	12	24	1.51	-1.00	-50.31	50.50	MWD	Payzone
9/27/2014	1,707	1.72	96.88	1,702	13	12	27	0.42	0.40	4.87	53.61	MWD	Weatherford
9/27/2014	1,770	1.98	91.26	1,765	13	12	29	0.50	0.41	-8.92	55.64	MWD	Weatherford
9/27/2014	1,864	2.05	96.50	1,859	13	12	32	0.21	0.07	5.57	58.94	MWD	Weatherford
9/27/2014	1,959	2.22	92.93	1,954	13	11	36	0.23	0.18	-3.76	62.48	MWD	Weatherford
9/27/2014	2,053	2.14	98.87	2,048	12	11	39	0.25	-0.09	6.32	66.05	MWD	Weatherford
9/27/2014	2,147	2.22	100.16	2,142	12	11	43	0.10	0.09	1.37	69.62	MWD	Weatherford
9/27/2014	2,242	2.07	96.11	2,237	12	10	46	0.22	-0.16	-4.26	73.18	MWD	Weatherford
9/27/2014	2,336	2.01	96.81	2,331	11	10	49	0.07	-0.06	0.74	76.52	MWD	Weatherford
9/27/2014	2,431	1.94	92.75	2,426	11	9	53	0.16	-0.07	-4.27	79.80	MWD	Weatherford
9/27/2014	2,525	2.03	92.66	2,520	11	9	56	0.10	0.10	-0.10	83.05	MWD	Weatherford
9/27/2014	2,619	1.96	92.81	2,614	11	9	59	0.07	-0.07	0.16	86.32	MWD	Weatherford
9/28/2014	2,714	2.01	87.52	2,709	11	9	63	0.20	0.05	-5.57	89.61	MWD	Weatherford
9/28/2014	2,808	2.06	90.68	2,803	11	9	66	0.13	0.05	3.36	92.95	MWD	Weatherford
9/28/2014	2,903	2.02	92.14	2,897	11	9	69	0.07	-0.04	1.54	96.33	MWD	Weatherford
9/28/2014	2,998	1.79	92.33	2,992	11	9	72	0.24	-0.24	0.20	99.49	MWD	Weatherford
9/28/2014	3,092	1.74	91.46	3,086	11	9	75	0.06	-0.05	-0.93	102.38	MWD	Weatherford
9/28/2014	3,187	1.12	94.91	3,181	11	9	78	0.66	-0.65	3.63	104.75	MWD	Weatherford
9/28/2014	3,281	0.74	105.65	3,275	11	8	79	0.44	-0.40	11.43	106.27	MWD	Weatherford
9/28/2014	3,376	0.62	67.43	3,370	11	8	80	0.48	-0.13	-40.23	107.34	MWD	Weatherford
9/28/2014	3,469	0.39	103.38	3,463	11	9	81	0.41	-0.25	38.66	108.12	MWD	Weatherford
9/28/2014	3,564	0.78	92.55	3,558	11	8	82	0.42	0.41	-11.40	109.08	MWD	Weatherford
9/28/2014	3,658	0.46	134.15	3,652	11	8	83	0.57	-0.34	44.26	110.04	MWD	Weatherford
9/28/2014	3,753	0.68	163.45	3,747	10	7	83	0.38	0.23	30.84	110.96	MWD	Weatherford
9/28/2014	3,847	0.79	165.59	3,841	9	6	84	0.12	0.12	2.28	112.16	MWD	Weatherford
9/28/2014	3,941	1.23	177.92	3,935	8	5	84	0.52	0.47	13.12	113.81	MWD	Weatherford
9/28/2014	4,036	1.49	175.79	4,030	5	2	84	0.28	0.27	-2.24	116.06	MWD	Weatherford
9/28/2014	4,130	1.62	186.02	4,124	3	0	84	0.33	0.14	10.88	118.60	MWD	Weatherford
9/28/2014	4,225	1.96	186.60	4,219	0	-3	84	0.36	0.36	0.61	121.57	MWD	Weatherford
9/28/2014	4,319	1.92	188.86	4,313	-3	-6	83	0.09	-0.04	2.40	124.75	MWD	Weatherford
9/28/2014	4,414	2.17	182.73	4,408	-7	-10	83	0.35	0.26	-6.45	128.14	MWD	Weatherford
9/28/2014	4,508	2.36	186.23	4,502	-10	-13	83	0.25	0.20	3.72	131.85	MWD	Weatherford
9/28/2014	4,602	2.54	190.49	4,596	-14	-17	82	0.27	0.19	4.53	135.87	MWD	Weatherford
9/29/2014	4,697	2.88	186.57	4,691	-19	-22	81	0.41	0.36	-4.13	140.36	MWD	Weatherford
9/28/2014	4,789	3.55	186.54	4,783	-24	-27	81	0.73	0.73	-0.03	145.52	MWD	Weatherford
9/28/2014	4,883	3.89	173.60	4,876	-30	-33	81	0.96	0.36	-13.77	151.58	MWD	Weatherford
9/28/2014	4,978	4.31	148.44	4,971	-36	-39	83	1.93	0.44	-26.48	158.21	MWD	Weatherford
9/30/2014	5,072	4.45	130.11	5,065	-41	-45	88	1.49	0.15	-19.50	165.29	MWD	Weatherford
9/30/2014	5,167	4.29	106.30	5,160	-45	-48	94	1.90	-0.17	-25.06	172.38	MWD	Weatherford
9/30/2014	5,261	4.07	102.68	5,253	-46	-50	100	0.37	-0.23	-3.85	179.23	MWD	Weatherford
9/30/2014	5,355	4.76	95.21	5,347	-47	-51	108	0.95	0.73	-7.95	186.45	MWD	Weatherford
9/30/2014	5,450	5.28	92.29	5,442	-47	-51	116	0.61	0.55	-3.07	194.76	MWD	Weatherford
9/30/2014	5,544	5.65	87.90	5,535	-47	-51	125	0.59	0.39	-4.67	203.70	MWD	Weatherford
10/1/2014	5,639	6.20	84.61	5,630	-46	-51	135	0.68	0.58	-3.46	213.50	MWD	Weatherford
10/1/2014	5,733	5.63	84.55	5,723	-45	-50	144	0.61	-0.61	-0.06	223.19	MWD	Weatherford
10/1/2014	5,828	6.52	89.48	5,818	-44	-49	154	1.09	0.94	5.19	233.24	MWD	Weatherford
10/1/2014	6,017	5.17	88.81	6,006	-43	-49	174	0.72	-0.71	-0.35	252.48	MWD	Weatherford
10/1/2014	6,110	5.15	96.16	6,098	-43	-49	182	0.71	-0.02	7.90	260.83	MWD	Weatherford
10/2/2014	6,204	5.54	95.82	6,192	-43	-50	191	0.42	0.41	-0.36	269.59	MWD	Weatherford
10/2/2014	6,298	6.13	96.47	6,286	-44	-51	200	0.63	0.63	0.69	279.14	MWD	Weatherford

NEWFIELD

Directional Survey



Legal Well Name Powitch 15-13-12-3-2WB				Wellbore Name Original Hole					
API/UWI 43013519420000		Surface Legal Location NWNE 75FNL 2332FEL SEC24 T3S R2W MERU		Field Name UINTA CB - BAR F HORZ		Well Type Development		Well Configuration Type Horizontal	
Well RC 500358785		County Duchesne		State/Province Utah		Spud Date 9/21/2014 06:00		Final Rig Release Date 10/28/2014 00:00	

Survey Data

Date	MD (ftKB)	Incl (°)	Azm (°)	TVD (ftKB)	VS (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Build (°/100ft)	Turn (°/100ft)	Unwrap Displace (ft)	Method	Survey Company
10/2/2014	6,392	6.98	93.71	6,379	-45	-52	211	0.96	0.90	-2.94	289.87	MWD	Weatherford
10/3/2014	6,479	6.56	97.57	6,465	-45	-53	221	0.71	-0.48	4.44	300.12	MWD	Weatherford
10/3/2014	6,572	6.20	99.86	6,558	-47	-55	231	0.47	-0.39	2.46	310.45	MWD	Weatherford
10/3/2014	6,667	5.61	102.59	6,652	-48	-57	241	0.69	-0.62	2.87	320.22	MWD	Weatherford
10/3/2014	6,761	4.88	100.65	6,746	-50	-58	249	0.80	-0.78	-2.06	328.81	MWD	Weatherford
10/3/2014	6,856	5.90	95.83	6,840	-50	-60	258	1.17	1.07	-5.07	337.73	MWD	Weatherford
10/4/2014	6,950	6.80	94.47	6,934	-51	-61	268	0.97	0.96	-1.45	348.13	MWD	Weatherford
10/4/2014	7,045	7.66	77.78	7,028	-50	-60	280	2.38	0.91	-17.57	359.96	MWD	Weatherford
10/4/2014	7,071	8.48	70.14	7,054	-49	-59	284	5.19	3.15	-29.38	363.60	MWD	Weatherford
10/4/2014	7,107	9.36	66.32	7,089	-46	-57	289	2.95	2.44	-10.61	369.18	MWD	Weatherford
10/4/2014	7,138	10.57	62.52	7,120	-44	-54	294	4.44	3.90	-12.26	374.54	MWD	Weatherford
10/4/2014	7,170	11.77	59.48	7,151	-41	-51	299	4.18	3.75	-9.50	380.74	MWD	Weatherford
10/4/2014	7,202	12.93	54.27	7,183	-37	-47	305	5.02	3.63	-16.28	387.57	MWD	Weatherford
10/4/2014	7,233	14.08	51.17	7,213	-32	-43	311	4.38	3.71	-10.00	394.81	MWD	Weatherford
10/4/2014	7,265	15.48	47.46	7,244	-26	-38	317	5.28	4.38	-11.59	402.97	MWD	Weatherford
10/4/2014	7,296	16.89	42.86	7,273	-20	-32	323	6.14	4.55	-14.84	411.60	MWD	Weatherford
10/4/2014	7,327	17.70	38.25	7,303	-13	-25	329	5.13	2.61	-14.87	420.81	MWD	Weatherford
10/5/2014	7,359	18.42	33.93	7,333	-5	-17	335	4.75	2.25	-13.50	430.73	MWD	Weatherford
10/5/2014	7,390	19.32	31.72	7,363	4	-8	340	3.71	2.90	-7.13	440.75	MWD	Weatherford
10/5/2014	7,422	20.08	28.78	7,393	13	1	345	3.90	2.38	-9.19	451.53	MWD	Weatherford
10/5/2014	7,453	20.97	25.84	7,422	23	11	350	4.39	2.87	-9.48	462.40	MWD	Weatherford
10/5/2014	7,485	22.09	23.80	7,452	34	21	355	4.21	3.50	-6.38	474.14	MWD	Weatherford
10/5/2014	7,516	23.46	22.15	7,480	45	32	360	4.88	4.42	-5.32	486.14	MWD	Weatherford
10/5/2014	7,547	25.27	20.81	7,509	57	44	365	6.10	5.84	-4.32	498.93	MWD	Weatherford
10/5/2014	7,579	27.08	20.09	7,537	71	58	370	5.74	5.66	-2.25	513.04	MWD	Weatherford
10/5/2014	7,610	28.82	18.98	7,565	85	71	375	5.86	5.61	-3.58	527.57	MWD	Weatherford
10/5/2014	7,642	29.88	17.38	7,593	100	86	379	4.12	3.31	-5.00	543.26	MWD	Weatherford
10/5/2014	7,673	30.85	16.65	7,619	115	101	384	3.35	3.13	-2.35	558.93	MWD	Weatherford
10/6/2014	7,705	31.43	15.93	7,647	131	117	389	2.15	1.81	-2.25	575.47	MWD	Weatherford
10/6/2014	7,736	32.41	14.83	7,673	147	133	393	3.68	3.16	-3.55	591.86	MWD	Weatherford
10/6/2014	7,768	33.22	14.62	7,700	164	150	397	2.56	2.53	-0.66	609.20	MWD	Weatherford
10/6/2014	7,799	34.57	14.26	7,726	181	166	402	4.40	4.35	-1.16	626.49	MWD	Weatherford
10/6/2014	7,831	36.17	14.11	7,752	199	184	406	5.01	5.00	-0.47	645.02	MWD	Weatherford
10/6/2014	7,854	37.99	14.21	7,770	212	198	410	7.92	7.91	0.43	658.88	MWD	Weatherford
10/6/2014	7,893	39.49	14.62	7,801	236	221	416	3.90	3.85	1.05	683.29	MWD	Weatherford
10/6/2014	7,925	41.70	14.95	7,825	256	242	421	6.94	6.91	1.03	704.11	MWD	Weatherford
10/6/2014	7,962	43.22	15.26	7,852	281	266	428	4.15	4.11	0.84	729.08	MWD	Weatherford
10/11/2014	8,060	47.68	18.11	7,921	348	333	448	5.00	4.55	2.91	798.89	MWD	Weatherford
10/11/2014	8,091	48.00	18.75	7,942	370	354	455	1.85	1.03	2.06	821.87	MWD	Weatherford
10/11/2014	8,122	48.87	18.70	7,962	392	376	462	2.81	2.81	-0.16	845.06	MWD	Weatherford
10/11/2014	8,154	52.55	17.16	7,982	416	400	470	12.09	11.50	-4.81	869.83	MWD	Weatherford
10/11/2014	8,185	55.40	15.66	8,001	441	424	477	9.99	9.19	-4.84	894.89	MWD	Weatherford
10/11/2014	8,217	57.39	14.08	8,018	467	450	484	7.46	6.22	-4.94	921.54	MWD	Weatherford
10/11/2014	8,248	59.89	11.55	8,035	493	475	490	10.66	8.06	-8.16	948.01	MWD	Weatherford
10/11/2014	8,280	62.57	9.26	8,050	520	503	495	10.46	8.38	-7.16	976.05	MWD	Weatherford
10/11/2014	8,311	64.97	7.00	8,064	548	531	499	10.13	7.74	-7.29	1,003.86	MWD	Weatherford

NEWFIELD**Directional Survey**

Legal Well Name Powwitch 15-13-12-3-2WB				Wellbore Name Original Hole					
API/UWI 43013519420000		Surface Legal Location NWNE 75FNL 2332FEL SEC24 T3S R2W MERU		Field Name UINTA CB - BAR F HORZ		Well Type Development		Well Configuration Type Horizontal	
Well RC 500358785		County Duchesne		State/Province Utah		Spud Date 9/21/2014 06:00		Final Rig Release Date 10/28/2014 00:00	

Survey Data

Date	MD (ftKB)	Incl (°)	Azm (°)	TVD (ftKB)	VS (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Build (°/100ft)	Turn (°/100ft)	Unwrap Displace (ft)	Method	Survey Company
10/11/2014	8,343	67.00	3.47	8,077	577	560	501	11.91	6.34	-11.03	1,033.08	MWD	Weatherford
10/11/2014	8,374	68.14	0.21	8,089	606	588	502	10.39	3.68	-10.52	1,061.73	MWD	Weatherford
10/11/2014	8,406	69.41	359.32	8,100	636	618	502	4.74	3.97	1122.22	1,091.56	MWD	Weatherford
10/11/2014	8,437	71.31	358.90	8,111	665	647	502	6.26	6.13	-1.35	1,120.75	MWD	Weatherford
10/11/2014	8,469	73.57	358.94	8,120	695	678	501	7.06	7.06	0.13	1,151.26	MWD	Weatherford
10/11/2014	8,500	75.04	358.74	8,129	725	708	501	4.78	4.74	-0.65	1,181.10	MWD	Weatherford
10/11/2014	8,532	76.70	358.83	8,136	756	739	500	5.19	5.19	0.28	1,212.13	MWD	Weatherford
10/11/2014	8,563	78.71	358.34	8,143	786	769	499	6.67	6.48	-1.58	1,242.42	MWD	Weatherford
10/11/2014	8,595	80.65	357.58	8,149	818	800	498	6.50	6.06	-2.37	1,273.90	MWD	Weatherford
10/11/2014	8,626	82.39	357.19	8,153	848	831	497	5.75	5.61	-1.26	1,304.56	MWD	Weatherford
10/11/2014	8,657	84.07	357.31	8,157	879	862	495	5.43	5.42	0.39	1,335.34	MWD	Weatherford
10/11/2014	8,689	85.80	356.60	8,160	911	894	493	5.84	5.41	-2.22	1,367.22	MWD	Weatherford
10/11/2014	8,720	86.98	356.02	8,162	941	924	491	4.24	3.81	-1.87	1,398.15	MWD	Weatherford
10/11/2014	8,783	86.85	355.35	8,165	1,004	987	487	1.08	-0.21	-1.06	1,461.06	MWD	Weatherford
10/11/2014	8,873	87.16	354.43	8,170	1,093	1,077	479	1.08	0.34	-1.02	1,550.94	MWD	Weatherford
10/13/2014	8,917	87.53	354.26	8,172	1,137	1,120	474	0.93	0.84	-0.39	1,594.89	MWD	Weatherford
10/13/2014	9,011	87.47	354.60	8,176	1,230	1,214	465	0.37	-0.06	0.36	1,688.80	MWD	Weatherford
10/13/2014	9,106	86.05	354.22	8,181	1,324	1,308	456	1.55	-1.49	-0.40	1,783.65	MWD	Weatherford
10/13/2014	9,200	86.17	356.54	8,188	1,417	1,402	448	2.47	0.13	2.47	1,877.42	MWD	Weatherford
10/13/2014	9,295	87.72	358.97	8,193	1,511	1,497	445	3.03	1.63	2.56	1,972.28	MWD	Weatherford
10/13/2014	9,389	88.58	359.23	8,196	1,605	1,591	443	0.96	0.91	0.28	2,066.23	MWD	Weatherford
10/13/2014	9,484	89.32	356.85	8,198	1,700	1,685	440	2.62	0.78	-2.51	2,161.21	MWD	Weatherford
10/13/2014	9,578	88.83	354.61	8,199	1,793	1,779	433	2.44	-0.52	-2.38	2,255.19	MWD	Weatherford
10/14/2014	9,673	89.08	352.70	8,201	1,887	1,874	423	2.03	0.26	-2.01	2,350.17	MWD	Weatherford
10/14/2014	9,767	89.14	355.18	8,202	1,980	1,967	413	2.64	0.06	2.64	2,444.15	MWD	Weatherford
10/14/2014	9,861	88.52	354.43	8,204	2,074	2,061	404	1.04	-0.66	-0.80	2,538.13	MWD	Weatherford
10/14/2014	9,956	87.60	353.15	8,207	2,168	2,155	394	1.66	-0.97	-1.35	2,633.07	MWD	Weatherford
10/14/2014	10,050	87.36	349.36	8,211	2,260	2,248	380	4.04	-0.26	-4.03	2,726.96	MWD	Weatherford
10/14/2014	10,144	87.47	349.42	8,216	2,351	2,340	362	0.13	0.12	0.06	2,820.87	MWD	Weatherford

NEWFIELD

Directional Survey



Legal Well Name Powitch 15-13-12-3-2WB				Wellbore Name Original Hole					
API/UWI 43013519420000		Surface Legal Location NWNE 75FNL 2332FEL SEC24 T3S R2W MERU		Field Name UINTA CB - BAR F HORZ		Well Type Development		Well Configuration Type Horizontal	
Well RC 500358785		County Duchesne		State/Province Utah		Spud Date 9/21/2014 06:00		Final Rig Release Date 10/28/2014 00:00	

Survey Data

Date	MD (ftKB)	Incl (°)	Azm (°)	TVD (ftKB)	VS (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Build (°/100ft)	Turn (°/100ft)	Unwrap Displace (ft)	Method	Survey Company
10/14/2014	10,239	87.66	353.39	8,220	2,445	2,434	348	4.18	0.20	4.18	2,915.76	MWD	Weatherford
10/14/2014	10,333	87.66	354.22	8,224	2,538	2,527	338	0.88	0.00	0.88	3,009.68	MWD	Weatherford
10/14/2014	10,428	87.72	354.37	8,227	2,632	2,622	329	0.17	0.06	0.16	3,104.61	MWD	Weatherford
10/14/2014	10,522	88.95	357.63	8,230	2,725	2,715	322	3.71	1.31	3.47	3,198.55	MWD	Weatherford
10/14/2014	10,616	89.26	359.73	8,232	2,819	2,809	320	2.26	0.33	2.23	3,292.53	MWD	Weatherford
10/14/2014	10,711	89.38	359.01	8,233	2,914	2,904	319	0.77	0.13	-0.76	3,387.53	MWD	Weatherford
10/14/2014	10,805	88.95	359.37	8,234	3,008	2,998	317	0.60	-0.46	0.38	3,481.52	MWD	Weatherford
10/15/2014	10,900	87.41	359.88	8,237	3,103	3,093	317	1.71	-1.62	0.54	3,576.47	MWD	Weatherford
10/15/2014	10,994	88.83	2.76	8,240	3,197	3,187	319	3.41	1.51	-379.91	3,670.40	MWD	Weatherford
10/15/2014	11,088	88.64	2.09	8,242	3,291	3,281	323	0.74	-0.20	-0.71	3,764.38	MWD	Weatherford
10/15/2014	11,183	88.52	0.46	8,245	3,386	3,376	325	1.72	-0.13	-1.72	3,859.35	MWD	Weatherford
10/15/2014	11,277	87.78	0.96	8,248	3,479	3,470	326	0.95	-0.79	0.53	3,953.30	MWD	Weatherford
10/15/2014	11,371	87.84	359.09	8,251	3,573	3,564	326	1.99	0.06	380.99	4,047.22	MWD	Weatherford
10/15/2014	11,466	88.46	6.93	8,254	3,668	3,659	331	8.27	0.65	-370.69	4,142.10	MWD	Weatherford
10/15/2014	11,561	88.09	5.75	8,257	3,763	3,753	342	1.30	-0.39	-1.24	4,237.05	MWD	Weatherford
10/16/2014	11,655	89.01	5.11	8,260	3,857	3,847	351	1.19	0.98	-0.68	4,331.02	MWD	Weatherford
10/16/2014	11,749	87.41	2.62	8,263	3,951	3,940	357	3.15	-1.70	-2.65	4,424.97	MWD	Weatherford
10/16/2014	11,844	86.98	4.67	8,267	4,045	4,035	363	2.20	-0.45	2.16	4,519.85	MWD	Weatherford
10/16/2014	11,938	86.85	1.79	8,272	4,139	4,129	368	3.06	-0.14	-3.06	4,613.70	MWD	Weatherford
10/16/2014	12,033	87.16	2.49	8,277	4,234	4,224	372	0.80	0.33	0.74	4,708.57	MWD	Weatherford
10/16/2014	12,127	86.73	0.68	8,282	4,328	4,317	374	1.98	-0.46	-1.93	4,802.43	MWD	Weatherford
10/16/2014	12,221	88.89	0.57	8,286	4,422	4,411	375	2.30	2.30	-0.12	4,896.36	MWD	Weatherford
10/16/2014	12,316	89.38	3.55	8,287	4,517	4,506	379	3.18	0.52	3.14	4,991.34	MWD	Weatherford
10/16/2014	12,410	87.66	357.99	8,290	4,611	4,600	380	6.19	-1.83	377.06	5,085.27	MWD	Weatherford
10/16/2014	12,505	87.60	355.63	8,294	4,705	4,695	375	2.48	-0.06	-2.48	5,180.18	MWD	Weatherford
10/16/2014	12,599	88.21	355.15	8,297	4,799	4,789	367	0.83	0.65	-0.51	5,274.11	MWD	Weatherford
10/16/2014	12,693	87.47	354.23	8,301	4,892	4,882	359	1.26	-0.79	-0.98	5,368.05	MWD	Weatherford
10/16/2014	12,788	86.73	356.40	8,305	4,986	4,977	351	2.41	-0.78	2.28	5,462.92	MWD	Weatherford
10/17/2014	12,882	85.31	356.27	8,312	5,079	5,070	345	1.52	-1.51	-0.14	5,556.69	MWD	Weatherford

NEWFIELD

Directional Survey



Legal Well Name Powitch 15-13-12-3-2WB				Wellbore Name Original Hole					
API/UWI 43013519420000		Surface Legal Location NWNE 75FNL 2332FEL SEC24 T3S R2W MERU		Field Name UINTA CB - BAR F HORZ		Well Type Development		Well Configuration Type Horizontal	
Well RC 500358785		County Duchesne	State/Province Utah		Spud Date 9/21/2014 06:00		Final Rig Release Date 10/28/2014 00:00		

Survey Data

Date	MD (ftKB)	Incl (°)	Azm (°)	TVD (ftKB)	VS (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Build (°/100ft)	Turn (°/100ft)	Unwrap Displace (ft)	Method	Survey Company
10/17/2014	12,977	86.67	356.97	8,319	5,174	5,165	339	1.61	1.43	0.74	5,651.45	MWD	Weatherford
10/17/2014	13,071	87.35	357.55	8,323	5,267	5,259	335	0.95	0.72	0.62	5,745.32	MWD	Weatherford
10/17/2014	13,166	87.59	357.74	8,328	5,362	5,353	331	0.32	0.25	0.20	5,840.23	MWD	Weatherford
10/17/2014	13,260	88.15	357.50	8,331	5,455	5,447	327	0.65	0.60	-0.26	5,934.17	MWD	Weatherford
10/17/2014	13,355	88.52	356.83	8,334	5,550	5,542	322	0.81	0.39	-0.71	6,029.12	MWD	Weatherford
10/17/2014	13,544	88.24	2.58	8,339	5,739	5,731	321	3.04	-0.15	-187.43	6,217.97	MWD	Weatherford
10/17/2014	13,638	87.90	2.37	8,342	5,833	5,825	325	0.43	-0.36	-0.22	6,311.92	MWD	Weatherford
10/18/2014	13,732	87.84	2.50	8,346	5,927	5,919	329	0.15	-0.06	0.14	6,405.85	MWD	Weatherford
10/18/2014	13,826	87.47	1.38	8,350	6,021	6,013	333	1.25	-0.39	-1.19	6,499.77	MWD	Weatherford
10/18/2014	13,921	88.52	0.65	8,353	6,115	6,107	334	1.35	1.11	-0.77	6,594.71	MWD	Weatherford
10/18/2014	14,015	88.58	0.59	8,355	6,209	6,201	335	0.09	0.06	-0.06	6,688.68	MWD	Weatherford
10/18/2014	14,109	87.53	1.17	8,359	6,303	6,295	337	1.28	-1.12	0.62	6,782.62	MWD	Weatherford
10/18/2014	14,204	87.53	1.65	8,363	6,398	6,390	339	0.50	0.00	0.51	6,877.54	MWD	Weatherford
10/18/2014	14,298	86.55	0.59	8,368	6,492	6,484	341	1.53	-1.04	-1.13	6,971.41	MWD	Weatherford
10/18/2014	14,393	87.23	0.43	8,373	6,587	6,579	342	0.74	0.72	-0.17	7,066.27	MWD	Weatherford
10/18/2014	14,487	87.66	0.29	8,377	6,681	6,673	342	0.48	0.46	-0.15	7,160.17	MWD	Weatherford
10/18/2014	14,582	88.06	1.17	8,381	6,776	6,768	344	1.02	0.42	0.93	7,255.11	MWD	Weatherford
10/18/2014	14,676	87.96	1.17	8,384	6,870	6,862	345	0.11	-0.11	0.00	7,349.05	MWD	Weatherford
10/18/2014	14,771	87.90	0.95	8,387	6,965	6,957	347	0.24	-0.06	-0.23	7,443.99	MWD	Weatherford
10/18/2014	14,866	87.90	0.15	8,391	7,059	7,052	348	0.84	0.00	-0.84	7,538.92	MWD	Weatherford
10/18/2014	14,960	87.96	359.87	8,394	7,153	7,145	348	0.30	0.06	382.68	7,632.86	MWD	Weatherford
10/18/2014	15,054	88.09	0.23	8,397	7,247	7,239	348	0.41	0.14	-382.60	7,726.81	MWD	Weatherford
10/19/2014	15,149	87.90	0.59	8,401	7,342	7,334	349	0.43	-0.20	0.38	7,821.75	MWD	Weatherford
10/19/2014	15,243	87.84	0.38	8,404	7,436	7,428	350	0.23	-0.06	-0.22	7,915.68	MWD	Weatherford
10/19/2014	15,338	87.90	0.44	8,408	7,531	7,523	350	0.09	0.06	0.06	8,010.62	MWD	Weatherford
10/19/2014	15,432	87.96	358.88	8,411	7,625	7,617	350	1.66	0.06	381.32	8,104.55	MWD	Weatherford
10/19/2014	15,527	88.24	358.17	8,414	7,720	7,712	347	0.80	0.29	-0.75	8,199.50	MWD	Weatherford
10/19/2014	15,622	88.64	358.79	8,417	7,814	7,807	345	0.78	0.42	0.65	8,294.46	MWD	Weatherford
10/19/2014	15,716	89.01	0.52	8,419	7,908	7,901	344	1.88	0.39	-381.14	8,388.44	MWD	Weatherford

NEWFIELD**Directional Survey**

Legal Well Name Powvitch 15-13-12-3-2WB				Wellbore Name Original Hole					
API/UWI 43013519420000		Surface Legal Location NWNE 75FNL 2332FEL SEC24 T3S R2W MERU		Field Name UINTA CB - BAR F HORZ		Well Type Development		Well Configuration Type Horizontal	
Well RC 500358785		County Duchesne		State/Province Utah		Spud Date 9/21/2014 06:00		Final Rig Release Date 10/28/2014 00:00	

Survey Data

Date	MD (ftKB)	Incl (°)	Azm (°)	TVD (ftKB)	VS (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Build (°/100ft)	Turn (°/100ft)	Unwrap Displace (ft)	Method	Survey Company
10/19/2014	15,811	87.59	359.48	8,422	8,003	7,996	344	1.85	-1.49	377.85	8,483.39	MWD	Weatherford
10/20/2014	15,905	86.23	359.21	8,427	8,097	8,090	343	1.47	-1.45	-0.29	8,577.26	MWD	Weatherford
10/20/2014	16,000	85.31	0.93	8,434	8,192	8,185	343	2.05	-0.97	-377.14	8,671.99	MWD	Weatherford
10/20/2014	16,094	86.48	4.10	8,440	8,285	8,278	347	3.59	1.24	3.37	8,765.74	MWD	Weatherford
10/20/2014	16,188	85.99	6.15	8,447	8,379	8,372	356	2.24	-0.52	2.18	8,859.53	MWD	Weatherford
10/20/2014	16,283	85.68	4.26	8,453	8,474	8,466	364	2.01	-0.33	-1.99	8,954.27	MWD	Weatherford
10/20/2014	16,377	85.38	1.37	8,461	8,567	8,560	369	3.08	-0.32	-3.07	9,047.98	MWD	Weatherford
10/20/2014	16,471	85.62	1.09	8,468	8,661	8,653	371	0.39	0.26	-0.30	9,141.69	MWD	Weatherford
10/20/2014	16,566	85.43	1.61	8,476	8,756	8,748	373	0.58	-0.20	0.55	9,236.40	MWD	Weatherford
10/20/2014	16,660	85.55	359.36	8,483	8,849	8,842	374	2.39	0.13	380.59	9,330.10	MWD	Weatherford
10/21/2014	16,755	85.24	359.40	8,491	8,944	8,936	373	0.33	-0.33	0.04	9,424.79	MWD	Weatherford
10/21/2014	16,849	85.24	359.76	8,498	9,037	9,030	372	0.38	0.00	0.38	9,518.47	MWD	Weatherford
10/21/2014	16,943	87.96	1.23	8,504	9,131	9,124	373	3.29	2.89	-381.41	9,612.29	MWD	Weatherford
10/21/2014	17,037	84.13	358.82	8,510	9,225	9,218	373	4.81	-4.07	380.41	9,706.04	MWD	Weatherford
10/21/2014	17,132	84.26	0.81	8,520	9,319	9,312	373	2.09	0.14	-376.85	9,800.55	MWD	Weatherford
10/21/2014	17,226	85.99	3.32	8,528	9,413	9,406	376	3.23	1.84	2.67	9,894.20	MWD	Weatherford
10/21/2014	17,321	86.30	1.13	8,534	9,508	9,500	380	2.32	0.33	-2.31	9,988.98	MWD	Weatherford
10/21/2014	17,415	87.10	0.23	8,540	9,602	9,594	381	1.28	0.85	-0.96	10,082.82	MWD	Weatherford
10/21/2014	17,509	86.73	360.00	8,545	9,695	9,688	381	0.46	-0.39	382.73	10,176.69	MWD	Weatherford
10/21/2014	17,604	86.11	359.18	8,551	9,790	9,783	381	1.08	-0.65	-0.86	10,271.50	MWD	Weatherford
10/22/2014	17,698	85.55	356.02	8,558	9,884	9,877	377	3.41	-0.60	-3.36	10,365.24	MWD	Weatherford
10/22/2014	17,793	85.56	353.51	8,565	9,978	9,971	368	2.63	0.01	-2.64	10,459.95	MWD	Weatherford
10/22/2014	17,888	85.33	353.76	8,573	10,071	10,065	357	0.36	-0.24	0.26	10,554.65	MWD	Weatherford

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Job Category	Job Start Date	Job End Date

Daily Operations

Report Start Date 11/4/2014	Report End Date 11/5/2014	24hr Activity Summary We are attempting to open RSI toe sleeve. Pinned to 7565psi walked pressure to 9000psi on several attempts to open RSI to no avail. Currently holding 9500psi as per NFX engineer .
Start Time 10:00	End Time 12:30	Comment 10:00 Spot in Halliburton and 11:30 rig up Halliburton
Start Time 12:30	End Time 13:30	Comment Pressure test pumps and lines to 6000 PSI 12:47 Pressure test pump and line Start pumping - pressure up to 720 psi Shut down, reboot computer on Acid pump 12:59 Open HCR Valve and pressure dropped to 0 psi 13:00 Start pumping in with 2 bpm pressure began climbing immediately reduced rate to 1.5 bpm at 4500 psi then reduced rate to 1 bpm at 5500 psi 13:05 Pressured up to 6040 psi and stopped pumping Found a leak on the pump in line and shut in line at 2" manifold and monitor pressure for 30 minutes 13:35 Pressure bleed to 5967 so the total pressure lost was 173 psi 13:37 Bleed pressure of HALLIBURTON line and fix leak on iron then pressure test line to 6000 and open to well. 13:39 Bleed pressure off well back to acid truck 13:44 Close in bleed off
Start Time 13:30	End Time 17:00	Comment Pump in to open RSI / discuss plan to pump in with frac pump at 7.5 bpm 13:45 Start pumping at 7.5 with kicks set at 9000 psi 13:48 Pumps kicked out at 8770 with 10.56 bbls pumped pressure holding at 8750 psi 13:51 Bleed pressure back to truck to 5100 psi 13:54 Start boost and begin pumping (pump in again at same pump settings but rate was not reading) pressure up to 8970 pumps kicked out. Help pressure for 5 minutes 14:00 Bleed pressure to zero 14:06 Close in bleed off start boost and begin pumping at 4.7 bpm pump in 9.5 bbls to pressure up to 9040 psi 14:10 Pressure holding at 9000 psi 14:30 Close in frac iron and open up to B&C test truck 15:38 Pump in at 1/8 bpm bring pressure up to 9500 psi! 15:06 Bumped pressure up to 9800 psi at 1/8 bpm 15:20 Bleed down to 9000 psi washed bleeder valve on test truck, shut in well and bleed off then change bleeder valve and open well up 15:30 Pressure up to 10000 psi 15:58 Bleed pressure off of well 16:04 Start pumping in at 7 bpm with frac pump pressure up to 9130 and stop pumping 16:07 Close in Halliburton iron 16:08 Bump in with B&C test truck at 1/8 bpm from 9130 to 9900 psi 16:12 Hold 9900 psi 16:35 Bumped pressure up to 10,100 Psi with B&C test truck 17:05 bleed pressure off to 0 hold Pressure while decisions are made weather or not to shut down for the night Trouble Shoot Frack Pump (Kicking out before set Kickout pressure)

Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	17:00	End Time	18:30	Comment
				Pickle up pumps and lines with Brine and Rig down Frac pump
				17:10 Rig down DFIT gauges /Trouble shoot frac pump / Drain up and rig down frac pump
				Prime up acid pump with brine water to pickle up pump and lines
				18:03 Begin pumping with Acid pump at 3.8 bpm set kicks at 9000 psi
				18:05 Drop rate to 2.5 bpm
				18:06 Pressured up to 9100 stop pumps
				18:07 Begin pumping at 1/8 bpm with B&C quick test pump to 9500 psi with brine to pickle well head and valves.
				Shut in HCR and bottom frac valve for double barrier then shut inside wing valves and break off HALLIBURTON iron and B&C Quick Test truck
Start Time	18:30	End Time	00:00	Comment
Report Start Date	11/5/2014	Report End Date	11/6/2014	24hr Activity Summary
				Shut down for night / 9500 PSI on well.
Start Time	00:00	End Time	08:00	Comment
				Wait on Daylight
Start Time	08:00	End Time	09:00	Comment
				B&C Quick Test arrived at 08:00 and held PJSM with Location supervisors and then checked pressure on the well (9400 PSI)
				Halliburton called to let us know that they were Delayed by road-side UDOT inspection. (Frac truck Passed DOT Inspection perfectly)
Start Time	09:00	End Time	12:00	Comment
				Rig up Halliburton and Pressure test pump and lines to 9000 then open well to halliburton and Bleed pressure off of well.
				Communicate with Leadership team to make a plan forward.
Start Time	12:00	End Time	14:00	Comment
				Weltech and JW Wireline arrived on location at 12:00
				Hold PJSM with B&C Quick test and JW wireline
				Nippled down 7 1/16 flange on top frac head and remove "Night cap" then Nipple up Wireline lubricator adapter (Wireline crane Broke down and it took JW approxamatly 15 minutes to get a new crane on location so no Downtime was recorded) Rig up crane and begin rigging up Wireline.
Start Time	14:00	End Time	18:00	Comment
				Rig up Wire line and lubricator
				Rig up 5 1/2" 10K lubricator, test 10k with B&C quick test, Pick up Tractor tool with perf gun string
				Tractor string: 22.38
				Gun String:21.96
				Total length:44.34
				Total weight: 755.5 lbs
Start Time	18:00	End Time	00:00	Comment
				RIH with WL tractor and perf guns. Correlate to csg tally at 7719'. RIH and set down at 8575'. Dn wt 870, up wt 1500, static 1340. Pressure csg to 3000 psi. Tractor guns IH at 38 fpm and 940 LTEN. Unable to locate marker jt at 10,495'. Correlate to csg tally at 12,753' and 15,261'.

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Daily Operations

Report Start Date	Report End Date	24hr Activity Summary
11/6/2014	11/7/2014	Tractor perf gun IH.
Start Time	End Time	Comment
00:00	01:00	Tractor perf gun IH. Tag at 17,422'. HES holding 3890 psi on csg. POH and perforate 9 holes at 17,375' to 17378'.
Start Time	End Time	Comment
01:00	04:30	POH running CCL to surf. Correlate to csg tally. All shots fired. All tools recovered. Install night cap on WL BOP. SICP 2800 psi.
Start Time	End Time	Comment
04:30	06:00	Install data traps. Equalize pressure on frac tree and open middle master valve. SICP 2,697 psi. Pump DFIT at 7 bpm. With 12 bbl pumped got a break at 7,648 psi. With 17 bbl pumped got a second break at 8,220 psi. With 23 bbl pumped got a break at 8,605 psi. Pumped 35 bbl with final pressure of 7,838 psi. Last 14 bbl pumped were brine water. ISIP 7,324 psi
Start Time	End Time	Comment
06:00	08:00	Continue DFIT Final Shut in Pressure after 1 Hour is 3084 PSI. / Rig down Wireline, install Night cap and nipple up, Rig down and move out Halliburton, Weltech and JW wireline.
Start Time	End Time	Comment
08:00	17:00	Continue DFIT 09:00 Pressure Gauge 7 = 2930.96 / Pressure gauge 8 = 2930.96 11:00 Pressure Gauge 7 = 2859.12 / Pressure gauge 8 = 2859.12 13:00 Pressure Gauge 7 = 2808.24 / Pressure gauge 8 = 2808.09 15:00 Pressure Gauge 7 = 2757.44 / Pressure gauge 8 = 2757.05 17:00 Pressure Gauge 7 = 2733.92 / Pressure gauge 8 = 2733.64 Select rental delivered Air heater Cardwell Petroleum Delivered fuel Ute Tribal UTERO commission Came to inspect location Weatherford Rigged up Tarp around well head Started Air heater at 16:30
Start Time	End Time	Comment
17:00	00:00	19:00 Pressure Gauge #7 - 2700.79 / Pressure Gauge #8 - 2700.38 21:00 Pressure Gauge #7 - 2672.5 / Pressure Gauge #8 - 2672.14 23:00 Pressure Gauge #7 - 2647.98 / Pressure Gauge #8 - 2647.62
Report Start Date	Report End Date	24hr Activity Summary
11/7/2014	11/8/2014	DFIT
Start Time	End Time	Comment
00:00	00:00	01:00 Pressure Gauge #7 - 2627.11 / Pressure Gauge #8 - 2626.8 03:00 Pressure Gauge #7 - 2608.14 / Pressure Gauge #8 - 2607.73 05:00 Pressure Gauge #7 - 2590.69 / Pressure Gauge #8 - 2590.37 07:00 Pressure Gauge #7 - 2574.46 / Pressure Gauge #8 - 2574.19 15:00 Pressure Gauge #7 - 2522.72 / Pressure Gauge #8 - 2522.32 23:00 Pressure Gauge #7 - 2485.58 / Pressure Gauge #8 - 2485.17
Report Start Date	Report End Date	24hr Activity Summary
11/8/2014	11/9/2014	DFIT
Start Time	End Time	Comment
00:00	00:00	07:00 Current Pressure Gauge 7= 2485.58 / Gauge 8= 2485.17. 15:00 pressure readings Gauge 7= 2429.71 / Gauge 8= 2429.27. 23:00 Gauge 7- 2409.28 / Gauge 8- 2408.88.

Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Daily Operations

Report Start Date	Report End Date	24hr Activity Summary
11/9/2014	11/10/2014	DFIT
Start Time	00:00	End Time 00:00
Comment 7:00 Current Pressure Gauge 7- 2390.51 / Gauge 8- 2390.30. 23:00 Gauge 7- 2362.11 / Gauge 8- 2361.69.		
Report Start Date	Report End Date	24hr Activity Summary
11/10/2014	11/11/2014	DFIT
Start Time	00:00	End Time 00:00
Comment Monitor Pressure and record every 8 Hours / Current Pressure at 07:00 Gauge 7- 2349.94 / Gauge 8- 2349.66 Monitor Pressure and record every 8 Hours / Current Pressure at 15:00 Gauge 7- 2339.87 / Gauge 8- 2338.64 23:00 DFIT pressure-- Gauge 7- 2328.68 / Gauge 8- 2328.33.		
Report Start Date	Report End Date	24hr Activity Summary
11/11/2014	11/12/2014	DFIT
Start Time	00:00	End Time 00:00
Comment Monitor Pressure and record every 8 Hours / Current pressure at 07:00 Gauge 7- 2320.27 / Gauge 8- 2320.33 / Current Pressure at 15:00 Gauge 7- 2312.29 , Gauge 8- 2311.96 23:00--Gauge 7-2304.10/Gauge 8-2303.96		
Report Start Date	Report End Date	24hr Activity Summary
11/12/2014	11/13/2014	DFIT
Start Time	00:00	End Time 00:00
Comment Monitor Pressure and record every 8 Hours / Current pressure at 06:00 Gauge 7-2297.31/Gauge 8-2297.22 / Current Pressure at 15:00 Gauge 7- 2290.89, Gauge 8- 2290.66 23:00 Gauge 7-2280.20/Gauge 8-2280.31		
Report Start Date	Report End Date	24hr Activity Summary
11/13/2014	11/14/2014	DFIT
Start Time	00:00	End Time 00:00
Comment Monitor Pressure and record every 8 Hours / Current pressure at 07:00 Gauge 7- 2278.30, Gauge 8- 2278.44 / Current Pressure at 15:00 Gauge 7- 2273.38, Gauge 8- 2273.18 23:00 Gauge 7-2268.17/gauge 8-2268.15		
Report Start Date	Report End Date	24hr Activity Summary
11/14/2014	11/15/2014	DFIT
Start Time	00:00	End Time 00:00
Comment 7 AM - Monitor Pressure and record every 8 Hours / Current Pressure Gauge 7- 2262.77, Gauge 8- 2262.52 3 PM - Monitor Pressure and record every 8 Hours / Current Pressure Gauge 7- 2258.88, Gauge 8- 2258.51\ 23:00 Gauge 7-2253.62/gauge 8-2253.25		
Report Start Date	Report End Date	24hr Activity Summary
11/15/2014	11/16/2014	DFIT
Start Time	00:00	End Time 00:00
Comment 7 AM - Monitor Pressure and record every 8 Hours / Current Pressure Gauge 7- 2249.33, Gauge 8- 2249.25 3 PM - Monitor Pressure and record every 8 Hours / Current Pressure Gauge 7- 2244.81, Gauge 8- 2244.50 23:00 -- Gauge 7-2241.81/Gauge 8-2241.72		
Report Start Date	Report End Date	24hr Activity Summary
11/16/2014	11/17/2014	DFIT
Start Time	00:00	End Time 00:00
Comment 7 AM - Monitor Pressure and record every 8 Hours / Current Pressure Gauge 7- 2237.71, Gauge 8- 2238.13 3 PM - Monitor Pressure and record every 8 Hours / Current Pressure Gauge 7- 2235.33, Gauge 8- 2234.84 23:00--Gauge 7-2231.12/Gauge 8-2230.82		

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Daily Operations

Report Start Date	Report End Date	24hr Activity Summary
11/17/2014	11/18/2014	DFIT
Start Time	End Time	Comment
00:00	09:00	7 AM - Monitor Pressure and record every 8 Hours / Current Pressure Gauge 7- 2227.59, Gauge 8- 2227.40
Start Time	End Time	Comment
09:00	18:00	Halliburton & crane showed up on location getting everything spotted in & ready to wireline. RD DFIT gauges & night cap. RU Halliburton wireline & pressure test lube to 9,000 psi RIH W/ gauge ring. RIH pump down to 17,700'. POOH W/gauge ring.
Start Time	End Time	Comment
18:00	00:00	LD gauge ring & PU CAST-M logging tools & pressure test lubricator per Newfield standards. Refill water tanks. Pump down CAST-M tool at 5 bpm, LTEN 60, 10 fpm, 5050 psi to 1500'. Tool started falling at that depth.
Report Start Date	Report End Date	24hr Activity Summary
11/18/2014	11/19/2014	RU WL truck. Run Gauge ring.
Start Time	End Time	Comment
00:00	02:00	RIH with CAST-M logging tool to 8200'. Tool not working when rotating the head. POH to reset the telemetry on the head.
Start Time	End Time	Comment
02:00	07:00	POH. LD and repair logging tool. PU tool and lubricator. Check tool before starting IH, found CBL not working, work on CBL.
Start Time	End Time	Comment
07:00	11:00	Halliburton had picked up tools & tested lube & RIH a couple hundred foot & tested tool it didn't respond so came back out repair logging tool. PU tool and lubricator. Check tool before starting IH.
Start Time	End Time	Comment
11:00	15:00	Checking connection on drum to make sure that it is hooked up correctly. Waiting on a new communication box for wireline truck. Got all new stuff put on Halliburton truck & still not working 100% of the time. POOH W/wireline & tools. Re-head wireline & check all things out on surface.
Start Time	End Time	Comment
15:00	20:00	Wait on another WL truck from Rock Springs.
Start Time	End Time	Comment
20:00	00:00	Change out HES WL trucks. PU and check logging tools. Test lubricator per Newfield's guidelines. GIH to 30', PU to work logging tool in as centralizers were dragging. Started losing hole as we worked the tool up and down, working down to only 5'.
Report Start Date	Report End Date	24hr Activity Summary
11/19/2014	11/20/2014	CAST-M log
Start Time	End Time	Comment
00:00	02:00	LD tool logging tool. Found problem with lubricator pack off rubbers and repaired. PU tool and test lubricator to Newfield's standards.
Start Time	End Time	Comment
02:00	04:00	RIH with CAST-M log to 7900' then pump down tools. Pump pressure 6320 psi at 11.8 bpm. Line speed 210 fpm with 750 LTEN. Max pressure 7100 psi. Pumped 590 bbl. Max depth 17,320'.
Start Time	End Time	Comment
04:00	12:00	Run CAST-M log from 17,320' to 1,800'. POOH LD tools & RD Halliburton wireline. Had Halliburtons pump truck brine wellhead. RD Halliburton pump trucks & MO.
Start Time	End Time	Comment
12:00	00:00	Clean up location & finish poly transfer line from the Earl pad.
Report Start Date	Report End Date	24hr Activity Summary
11/20/2014	11/21/2014	CAST-M log
Start Time	End Time	Comment
00:00	00:00	SDFN - Rock Water is on location finishing up poly tranfer line testing & dry pigging.

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

--

Daily Operations

Report Start Date 11/21/2014	Report End Date 11/22/2014	24hr Activity Summary Finish poly transfer line from the Earl pad.
Start Time 00:00	End Time 06:00	Comment SDFN
Start Time 06:00	End Time 18:00	Comment Well is shut in . Rockwater is pumping frac water back to Earl pad to avoid freezing in tanks . Haul approx: 1800 bbls
Start Time 18:00	End Time 00:00	Comment SDFN
Report Start Date 11/22/2014	Report End Date 11/23/2014	24hr Activity Summary Finish poly transfer line from the Earl pad.
Start Time 00:00	End Time 00:00	Comment Shut Down, Wait on Frac
Report Start Date 11/23/2014	Report End Date 11/24/2014	24hr Activity Summary Wait on Frac
Start Time 00:00	End Time 00:00	Comment Shut Down, Wait on Frac
Report Start Date 11/24/2014	Report End Date 11/25/2014	24hr Activity Summary Wait on Frac
Start Time 00:00	End Time 00:00	Comment Shut down, Wait on Frac
Report Start Date 11/25/2014	Report End Date 11/26/2014	24hr Activity Summary Wait on Frac
Start Time 00:00	End Time 06:00	Comment SDFN
Start Time 06:00	End Time 10:00	Comment Rig up Pro's Flowback Lines & Manifold
Start Time 10:00	End Time 17:00	Comment Pressure Test Flowback Lines & Manifold to Newfield Guidelines, Construction widen road at entrance to location, Spot in & set 500 bbl. Acid tank, Move in Halliburton Mountain Movers, Nipple Down Blanking Flange, Nipple Up 7 1/16"X 10K JW Wireline Flange, Pressure Test Wireline Flange to Newfields Guidelines
Start Time 17:00	End Time 00:00	Comment Wait on Frac to start, SDFN
Report Start Date 11/26/2014	Report End Date 11/27/2014	24hr Activity Summary Wait on Frac
Start Time 00:00	End Time 06:00	Comment SDFN
Start Time 06:00	End Time 11:00	Comment Goff Trucking loading frac sand into Halliburton Mountain Movers
Start Time 11:00	End Time 00:00	Comment Wait on Frac to start, SDFN
Report Start Date 11/27/2014	Report End Date 11/28/2014	24hr Activity Summary Wait on Frac
Start Time 00:00	End Time 00:00	Comment Waiting for frac
Report Start Date 11/28/2014	Report End Date 11/29/2014	24hr Activity Summary Wait on Frac
Start Time 00:00	End Time 06:00	Comment SDFN

Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time 06:00		End Time 18:00	Comment Move in Halliburton Frac Equip. RU and test frac lines. Move in & Rig up JW Wireline, Heating Water on Earl pad for Frac.
Report Start Date 11/29/2014	Report End Date 11/30/2014	24hr Activity Summary MIRU Halliburton equipment & transfer water for frac.	
Start Time 00:00		End Time 07:00	Comment Transferring water for Frac.
Start Time 07:00		End Time 16:00	Comment Hold JSA, Bucket Test, Halliburton working on Blender Computer, Pressure test frac lines to 10,000psi, Pump lateral volume, Start Frac Stage #1. Global Kick Outs set at 9500 psi. Pressure tested to 10400 psi. Job pumped Produced Water with 1.0% KCl .2. Calculated 8 holes open, 1813 psi perf friction, 997 psi NWB as per FracPro. Developed a leak after coming back on from FET. Shut down to fix. Made some minor design changes as per NF engineering. Started back into job and established XL and pumped 100 Mesh Displaced 100 Mesh with linear gel. Pressure started coming up with XL fluid on formation. Rate dropped to 14 bpm @ 9,100 psi. Decision made to swap back to FR. and flush the well. Placed approx. 6,900 lbs. of 100 Mesh in formation. Good job by crew with all the changes, move on to stage 2. Had multiple problems at the start of the job with data communication between IFS and Fracpro. WG-36-2.3% (15.5), BC-200-8.6% (2), FR-76-9.5% (2.3), BA-20-53.3% (5.7), CL-31-44.8% (1.5), BE-9-24.9% (5), MO-67-73.7% (4.2), MC S-2510T-6.1% (2.3) Vicon NF-4.4% (4.3), Losurf 300D-6.1% (4.6) Cat 3/4-168.4% (10.7),
Start Time 16:00		End Time 18:30	Comment P&P stage 2. RIH with guns and Plug to KOP. pumped down guns at 13.2 bpm @ 6785 Psi, @208 fpm, 724 LT, pumped guns to 17,345', Pulled up and got line tension and set plug @ 17,316'. Line tension prior to setting plug 2009, line tension after plug set 1748, plug set time 1 min. perf'd at (17,275' - 17,278') (17,210' - 17,213'). POOH with tools, max pressure for pump down: 7768. Max rate for pump down- 13.2 bpm. Total BBIs pumped-547.71. POOH w/tools all shots fired. Drop ball & turn over to Frac.
Start Time 18:30		End Time 21:00	Comment Start Frac Stage #2. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10400 psi. Job pumped Produced Water with 1.0% KCl . 2. Calculated 15 holes open, 1095 psi perf friction, 262 psi NWB as per FracPro. 3. Ran a little heavy on 100 Mesh sand and 30/50 prop. 4. Stage went well. All proppant placed. WG-36-2.9% (63.6), BC-200-4.3% (6.1), MO-67-4.1% (1.5), MC S-2510T-2.3% (1.7) Vicon NF-2.9% (6.7), Losurf 300D-5% (7.3) FE-2A-5.3% (1.7),
Start Time 21:00		End Time 00:00	Comment P&P stage 3. RIH with guns and Plug to KOP. Pumped down guns at 13.2 bpm @ 4,518 Psi, @220 fpm, 860 LT, pumped guns to 17,140', Pulled up and got line tension and set plug @ 17,110'. LT prior to setting plug 2,122, LT after plug set 1,772, plug set time 50 sec. perforated at (17,100' - 17,103') (17,050' - 17,053') (17,000-17,003). Max pressure for pump down was 4,518 psi. Max rate for pump down- 13.2 bpm. Total Bbls pumped - 522.2. POOH w/tools all shots fired. Drop ball & turn over to Frac.
Report Start Date 11/30/2014	Report End Date 12/1/2014	24hr Activity Summary Pressure test lines & start frac. Frac stage 1 & 2. P&P stages 1, 2 & 3.	
Start Time 00:00		End Time 02:00	Comment Start Frac on Stage #3. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water with 1.0% KCl . 2. Calculated 17 holes open, 778 psi perf friction, 663 psi NWB as per FracPro. 3. T-Belt sanded off during 3.0# sand stage. Sand fell off completely. 10,000 gallons after losing sand, operators were able to clean up and get going again. Redesigned and worked back up to 3.5# to resume stage. 4. Started losing tub on flush. Had to drop 4 bpm down to 56 bpm. 5. Good effort in recovering by crew. WG-36-4.9% (166.2), BC-200-2.8% (6.1), FR-76-39.7% (12.8), BA-20-9.6% (5.2), CL-31-4.5% (1.5) MO-67-2.5% (1.5), Losurf 300D-4.6% (9.1) FE-2A-22.7% (9.4), Cat 3/4-9.3% (2.7), BE-9-3.4% (1)

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	02:00	End Time	04:30	Comment
				P&P stage 4. RIH with guns and Plug to KOP. Pumped down guns at 13.1 bpm @ 4,611 Psi, @240 fpm, 850 LT, pumped guns to 16,990', Pulled up and got line tension and set plug @ 16,945'. LT prior to setting plug 1,886, LT after plug set 1,665, plug set time 53 sec. perforated at (16,950' - 16,953') (16,900' - 16,903') (16,823-16,826). Max pressure for pump down was 4,611 psi. Max rate for pump down- 13.1 bpm. Total Bbls pumped – 525. POOH w/tools all shots fired. Drop ball & turn over to Frac.
Start Time	04:30	End Time	06:30	Comment
				Start Frac stage #4. 1. Global Kick Outs set at 9400 psi. Pressure tested to 9400 psi. Job pumped Produced Water with 1.0% KCl. 2. Calculated 14 holes open, 1125 psi perf friction, 536 psi NWB as per FracPro.3. 30/50 Ran long. Operator overestimated how much was in hopper and T-Belt at end of stage. Ran approx. 10,000 lbs heavy. ball Seat Stage Pressures and Rate: 4575 psi @ 14.7 bpm, 4575 psi Pressure before Seating, 4575 psi Pressure after Seating. WG-36-4.7% (122.7), BC-200-3.5% (7.3), BA-20-15.6% (6.5), MO-67-6.1% (6.4), Vicon NF-5% (13.4), FE-2A-16% (6.3), BE-9-17% (8.2)
Start Time	06:30	End Time	10:00	Comment
				JW wireline Jumped Sheave kinked wireline and will have to replace Sheave and cut 400' of wireline and re-head. before RIH w/ stage #5 P&P.
Start Time	10:00	End Time	12:30	Comment
				Plug and Perf: Stage #5 RIH with guns and Plug to KOP. pumped down guns at 13.3 bpm @ 4703 Psi, @250 fpm, 880 LT, pumped guns to 16,800, Pulled up and got line tension and set plug. Line tension prior to setting plug 1869, line tension after plug set 1630, plug set time 1min30secs. POH and perf'd at (16,725' - 16,728') (16,660' - 16,663') (16,600' - 16,603'). POOH with tools, max pressure for pump down: 4703 Max rate for pump down- 13.3bpm. Total BBlS pumped-415.8. POOH W/Wireline all shots fired, Turn well over to Frac
Start Time	12:30	End Time	15:30	Comment
				Start Frac stage #5 Global Kick Outs set at 9730 psi. Pressure tested to 10490 psi. Job pumped Produced Water.2. Calculated 21 holes open, 1085 psi perf friction, 600 psi NWB as per FracPro.3. Able to get to 60 bpm with no problems.4. Good job execution by the crew, all proppant placed. Ball Seat Stage Pressures and Rate: 5252 psi @ 14.7 bpm, 4773 psi Pressure before Seating, 5247 psi Pressure after Seating WG-36-13.8% (323.2), BC-200-2.2% (3.4), CL-31-12.3% (2.8) MO-67-2.9% (2.2), MC S-2510T-4.5% (3.9) Vicon NF -11.4% (32.3), Losurf 300D-5% (8.9) Cat 3/4-22.4% (6.6), BE-9-7.9% (4.2)
Start Time	15:30	End Time	17:30	Comment
				Plug and Perf: Stage #6. RIH with guns and Plug to KOP. pumped down guns at 13.1 bpm @ 4418 Psi, @245 fpm, 870 LT, pumped guns to 16,572', Pulled up and got line tension and set plug. Line tension prior to setting plug 1907, line tension after plug set 1705, plug set time 1min40secs. POH and perf'd at (16,505'-16508') (16,421'-16,424'). POOH with tools, max pressure for pump down: 4492 Max rate for pump down- 13.2 bpm. Total BBlS pumped-411. POOH W/Wireline all shots fired.
Start Time	17:30	End Time	18:30	Comment
				Weatherford Grease all valves on Frac Stack
Start Time	18:30	End Time	20:30	Comment
				Drop ball & Start Frac stage #6, Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. Calculated 17 holes open, 1700 psi perf friction, 248 psi NWB as per FracPro. CFT 1200 - 13 cups Protechnics tracer. Ball Seat Stage Pressures and Rate: 5169 psi @ 14.5 bpm, 4528 psi Pressure before Seating, psi Pressure after Seating, WG-36-4.9% (80.1), BC-200-3.6% (3.8), FR-76-3.3% (1.2), BA-20-4.7% (1.2), MC S-2510T-4.2% (3) Losurf 300D-4.2% (5.9), FE-2A-6.6% (2.9), BE-9-4.8% (2)

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	20:30	End Time
		23:00
Comment		
Plug and Perf: Stage #7, RIH with guns and Plug to KOP. Pumped down guns at 12.1 bpm @ 4,209 Psi, @220 fpm, 830 LT, pumped guns to 16,380', Pulled up and got line tension and set plug @16,340'. Line tension prior to setting plug 1,870, line tension after plug set 1,640, plug set time 50secs. POOH and perforated at (16,282'-16,285') (16,200'-16,203'). POOH with tools, max pressure for pump down: 4,209 Max rate for pump down- 12.2 bpm. Total BBIs pumped-434. POOH W/Wireline all shots fired, Turn well over to Frac		
Start Time	23:00	End Time
		00:00
Comment		
Start Frac stage #7		
Report Start Date	Report End Date	24hr Activity Summary
12/1/2014	12/2/2014	Frac stages 3,4,5,& 6. P&P stages 4,5,6, &7.
Start Time	00:00	End Time
		00:30
Comment		
Start Frac stage #7, Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. Calculated 17 holes open, 766 psi perf friction, 1207 psi NWB as per FracPro.CFT 1300 - 15 cups Protechnics tracer. WG-36-4.9% (80.4), FR-76-2.9% (1), MC S-2510T-4.4% (3) Vicon NF-4% (8.1), Losurf 300D-4.4% (6), BE-9-2.9% (1.2)		
Start Time	00:30	End Time
		02:30
Comment		
Plug and Perf: Stage #8, RIH with guns and Plug to KOP. Pumped down guns at 14 bpm @ 4,449 Psi, @250 fpm, 900 LT, pumped guns to 16,195', Pulled up and got line tension and set plug @16,168'. Line tension prior to setting plug 1,870, line tension after plug set 1,650, plug set time 68 secs. POOH and perforated at (16,104'-16,107') (16,040'-16,043'). POOH with tools, max pressure for pump down: 4,449 Max rate for pump down- 14 bpm. Total BBIs pumped- 432. POOH W/Wireline all shots fired, Turn well over to Frac		
Start Time	02:30	End Time
		04:30
Comment		
Start Frac stage #8 Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. Calculated 15 holes open, 1087 psi perf friction, 671 psi NWB as per FracPro. 14.5 cups 1300 CFT Protechnics. BC-200-2.8% (3), FR-76-4.6% (1.6), CL-31-7.4% (1.2), MC S-2510T-4.8% (3.3) Vicon NF-4% (8), Losurf 300D-4.1% (5.6)FE-2A-8.1% (3.3), BE-9-3.4% (1.4)		
Start Time	04:30	End Time
		06:30
Comment		
Plug and Perf: Stage #9, RIH with guns and Plug to KOP. pumped down guns at 13.9 bpm @ 4340 Psi, @250 fpm, 900 LT, pumped guns to 15,996', Pulled up and got line tension and set plug. Line tension prior to setting plug 1960, line tension after plug set 1600, plug set time 1min30secs. POH and perf'd at (15,940'-15,943') (15,880'-15,883') (15,820'-15,823'). POOH with tools, max pressure for pump down:4340 Max rate for pump down- 14bpm. Total BBIs pumped-438.5. POOH W/Wireline all shots fired, Turn well over to Frac		
Start Time	06:30	End Time
		08:30
Comment		
Start Frac stage #9, 1. Global Kick Outs set at 9500 psi. Pressure tested to 10450 psi. Job pumped Produced Water. 2. Calculated 22 holes open, 988 psi perf friction, 885 psi NWB as per FracPro. 3. Good job execution by the crew, all sand placed in formation. Ball Seat Stage Pressures and Rate: 5575 psi @ 15.2 bpm , 4723 psi Pressure before Seating , 5590 psi Pressure after Seating BC-200-2.9% (4.7), MO-67-2.3% (1.9), MC S-2510T-4.7% (4) Vicon NF-4.3% (11.8), Losurf 300D-4.7% (8), FE-2A-6.7% (3.1), BE-9-4.7% (2.4)		
Start Time	08:30	End Time
		10:30
Comment		
Plug and Perf: Stage #10 RIH with guns and Plug to KOP. pumped down guns at 13.2 bpm @ 4206 Psi, @250 fpm, 915 LT, pumped guns to 15,670', Pulled up and got line tension and set plug. Line tension prior to setting plug 1820, line tension after plug set 1545, plug set time 1min15secs. POH and perf'd at (15,620'-15,623') (15,550'-15,553') (15,480'-15,483'), POOH with tools, max pressure for pump down: 4206, Max rate for pump down- 13.2bpm. Total BBIs pumped-386.8. . POOH W/Wireline all shots fired, Turn well over to Frac		

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	10:30	End Time	13:00	Comment
				Start Frac stage #10, 1. Global Kick Outs set at 9500 psi. Pressure tested to 10533 psi. Job pumped Produced Water. 2. Calculated 20 holes open, 1188 psi perf friction, 693 psi NWB as per FracPro. 3. Did not see a 200 psi loss across the 15 minute shutdown. 4. Good job execution by the crew, all sand placed. 5. Minor rate fluctuation during middle of job, rate loss 1 bpm or less. Lined out for remainder of job. Ball Seat Stage Pressures and Rate: 4900 psi @ 15.1 bpm, 4300 psi Pressure before Seating, 4910 psi Pressure after Seating. FR-76-5.2% (2), CL-31-4.3% (1), MC S-2510T-3.7% (3.2), Losurf 300D-3.1% (5.3), FE-2A-5% (2.2), BE-9-4.1% (2.1)
Start Time	13:00	End Time	15:30	Comment
				Plug and Perf: Stage #11 RIH with guns and Plug to KOP. pumped down guns at 13.6 bpm @ 4109 Psi, @246 fpm, 915 LT, pumped guns to 15,436', Pulled up and got line tension and set plug. Line tension prior to setting plug 1730, line tension after plug set 1458, plug set time 31secs. POH and perfed at (15,411'-15,414') (15,341'-15,344') (15,281'-15,284'), POOH with tools, max pressure for pump down: 4109, Max rate for pump down-13.6bpm. Total BBIs pumped-385.5. POOH W/Wireline all shots fired, Turn well over to Frac
Start Time	15:30	End Time	16:00	Comment
				Weatherford Greasing 7 1/16" Frac stack
Start Time	16:00	End Time	17:30	Comment
				Start Frac stage #11 (Chemical pump down 45 mins, resume frac with no other issues. Fracing stage #11 at present.) 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 21 holes open, 1186 psi perf friction, 350 psi NWB as per FracPro. 3. Lost the mixing bowl on the Growler at the end of 1.5 ppa sand, staged and dropped rate to see if it could recover. Gel was essentially gone, cut prop and flushed the well. Down 45 minutes.
Start Time	17:30	End Time	18:15	Comment
				Chemical blending pump down, repaired and continue with frac of stage #11 with no other issues.
Start Time	18:15	End Time	19:30	Comment
				Finisht Frac stage #11 Continue frac of stage #11 (Chemical pump down 45 mins, resume frac with no other issues. Fracing stage #11 at present.) 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 21 holes open, 1186 psi perf friction, 350 psi NWB as per FracPro. 3. Lost the mixing bowl on the Growler at the end of 1.5 ppa sand, staged and dropped rate to see if it could recover. Gel was essentially gone, cut prop and flushed the well. Down 45 minutes. Continue frac stage #11 4. Had a dip in prop con on 1.5 ppa stage, able to recover. Hopper dropped too low. 5. Remainder of the job went well with all proppant placed. Ball Seat Stage Pressures and Rate: 4770 psi @ 15.2 bpm, 4200 psi Pressure before Seating, 4775 psi Pressure after Seating WG-36-4.6% (143.5), BC-200-3.6% (8), FR-76-2.7% (1.3), BA-20-3.2% (1.6), CL-31-3.7% (1.3), MO-67-3.1% (3.5), Losurf 300D-4.4% (9.6), BE-9-3.3% (2.2)
Start Time	19:30	End Time	22:00	Comment
				Plug and Perf: Stage #12 RIH with guns and Plug to KOP. pumped down guns at 14.1 bpm @ 4131 Psi, @238 fpm, 958 LT, pumped guns to 15,236', Pulled up and got line tension and set plug. Line tension prior to setting plug 1764, line tension after plug set 1526, plug set time 55 secs. POH and perfed at (15,216'-15,219') (15,141'-15,144') (15,065'-15,068'), POOH with tools, max pressure for pump down: 4131, Max rate for pump down- 14.1 bpm. Total BBIs pumped-386.02. POOH W/Wireline all shots fired, Turn well over to Frac.

Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	22:00	End Time	00:00	Comment
				Start Frac stage #12 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 20 holes open, 1055 psi perf friction, 335 psi NWB as per FracPro. 3. 100 Mesh bin emptied late resulting in longer 1 ppg 100 Mesh stage. 4. Stage went well with all proppant placed. Ball Seat Stage Pressures and Rate: 4842 psi @ 14.9 bpm , 4441 psi Pressure before Seating , 4842 psi Pressure after Seating WG-36-3.7% (83.6) , BC-200-2.5% (4) , FR-76-4.2% (1.8) , BA-20-4.1% (1.5) , Losurf 300D-3.6% (6.5) , FE-2A-3.1% (1.5) , BE-9-2.1% (1.1)
Report Start Date	Report End Date	24hr Activity Summary		
12/2/2014	12/3/2014	Frac stages 13,14,15,16,17,18,19 P&P stages 13,14,15,16,17,18,19		
Start Time	00:00	End Time	00:30	Comment
				Finish stage #12 frac.
Start Time	00:30	End Time	02:45	Comment
				Plug and Perf: Stage #13 RIH with guns and Plug to KOP. pumped down guns at 12.1 bpm @ 4,161 Psi, @234 fpm, 890 LT, pumped guns to 15,021', Pulled up and got line tension and set plug. Line tension prior to setting plug 1722, line tension after plug set 1,460, plug set time 46 secs. POH and perfed at (14,985'-14,988') (14,910'-14,913') (14,834'-1,837'), POOH with tools, max pressure for pump down: 4,161, Max rate for pump down 12.1 bpm. Total BBIs pumped 331.40, POOH W/Wireline all shots fired, Turn well over to Frac.
Start Time	02:45	End Time	05:00	Comment
				Start Frac stage #13. Global Kick outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water.2. Calculated 24 holes open, 28 psi perf friction, 697 psi NWB as per FracPro.3. Stage went well with all proppant placed.4. Protechnics pumped 19.5 cups of FTP 1600.Ball Seat Stage Pressures and Rate: 4218 psi @ 15 bpm , 4115 psi Pressure before Seating , 4218 psi Pressure after Seating, FR-76-4.6% (1.7) , MC S-2510T-3.9% (3.2) Vicon NF-4.4% (11.1) , Losurf 300D-4% (6.6) , FE-2A-4.2% (1.8) , BE-9-3.4% (1.7) .
Start Time	05:00	End Time	07:00	Comment
				Plug and Perf: Stage #14 RIH with guns and Plug to KOP. pumped down guns at 12 bpm @ 4,043 Psi, @240 fpm, 900 LT, pumped guns to 14,794' Pulled up and got line tension and set plug. Line tension prior to setting plug 1642, line tension after plug set 1,390, plug set time 1min. POH and perfed at (14,754'-14,757') (14,679'-14,682') (14,603'-14,606'), POOH with tools, max pressure for pump down: 4,050, Max rate for pump down 12.1 bpm. Total BBIs pumped 316, POOH W/Wireline all shots fired, Turn well over to Frac.
Start Time	07:00	End Time	09:30	Comment
				Start Frac Stage #14. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 23 holes open, 765 psi perf friction, 145 psi NWB as per FracPro. 3. Good job execution by the crew, all sand pumped. Ball Seat Stage Pressures and Rate: 4212 psi @ 15.8 bpm , 4053 psi Pressure before Seating , 4220 psi Pressure after Seating WG-36-3.1% (69.4) , CL-31-6.3% (1.5) MO-67-2% (1.6) , Losurf 300D-2.6% (4.2) BE-9-3.7% (1.8)
Start Time	09:30	End Time	11:30	Comment
				Plug and Perf: Stage #15 RIH with guns and Plug to KOP. pumped down guns at 14.1 bpm @ 3,921 Psi, @256 fpm, 950 LT, pumped guns to 14,537' Pulled up and got line tension and set plug @14,551'. Line tension prior to setting plug 1,819, line tension after plug set 1,540, plug set time 1min 25 sec. POH and perfed at (14,523'-14,526') (14,448'-14,451') (14,372'-14,375'), POOH with tools, max pressure for pump down: 3,921, Max rate for pump down 14.1 bpm. Total BBIs pumped 303, POOH W/Wireline all shots fired, Turn well over to Frac.

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	11:30	End Time	13:30	Comment
				Start Frac Stage #15. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10480 psi. Job pumped Produced Water. 2. Calculated 24 holes open, 751 psi perf friction, 310 psi NWB as per FracPro. 3. Good job execution by the crew, all proppant placed. Ball Seat Stage Pressures and Rate: 4225 psi @ 15.5 bpm , 4080 psi Pressure before Seating , 4228 psi Pressure after Seating WG-36-5.9% (129.7) , BC-200-5.2% (8.2) , FR-76-5.1% (1.8) ,BA-20-6.7% (2.4) , CL-31-6.3% (1.5) MO-67-2% (1.6) , MC S-2510T-5.6% (4.4) Vicon NF-7.5% (19.5) , Losurf 300D-5.1% (8.1) FE-2A-4.4% (1.8) , BE-9-4.9% (2.3)
Start Time	13:30	End Time	15:30	Comment
				Plug and Perf: Stage #16 RIH with guns and Plug to KOP. pumped down guns at 13 bpm @ 3,930 Psi, @250 fpm, 900 LT, pumped guns to 14,340' Pulled up and got line tension and set plug @14,330'. Line tension prior to setting plug 1,830, line tension after plug set 1,560, plug set time 1min. POH and perf'd at (14,292'-14,295') (14,217'-14,220') (14,141'-14,144'), POOH with tools, max pressure for pump down: 3,930, Max rate for pump down 13.1 bpm. Total BBls pumped 315.
Start Time	15:30	End Time	16:30	Comment
				Grease Frac Tree.
Start Time	16:30	End Time	18:30	Comment
				Drop Ball & turn over to frac. Start Frac Stage #16. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 21 holes open, 909 psi perf friction, 128 psi NWB as per FracPro. 3. Gel ran about 200 lbs low, early time visc was running 1-2 cp light. 4. Good job execution by the crew, all sand placed. Ball Seat Stage Pressures and Rate: 4376 psi @ 15.8 bpm , 4163 psi Pressure before Seating , 4380 psi Pressure after Seating WG-36-10.5% (221.8) , BC-200-4% (6.2) , FR-76-3.1% (1) , MO-67-3.8% (2.9) , Vicon NF-6.1% (15.3) , Losurf 300D-4.9% (7.5) , FE-2A-3.4% (1.3) , BE-9-4.9% (2.2)
Start Time	18:30	End Time	20:30	Comment
				Plug and Perf: Stage #17 RIH with guns and Plug to KOP. pumped down guns at 12.1 bpm @ 3,869 Psi, @208 fpm, 857 LT, pumped guns to 14,094', Pulled up and got line tension and set plug. Line tension prior to setting plug 1,634, line tension after plug set 1,383, plug set time 39 secs. POH and perf'd at (14,061'-14,064') (13,986'-13,989') (13,910'-13,913'), POOH with tools, max pressure for pump down: 9,936, Max rate for pump down 12.1 bpm. Total BBls pumped 317.73, POOH W/Wireline all shots fired, Turn well over to Frac.
Start Time	23:00	End Time	01:00	Comment
				frac 17
Start Time	20:30	End Time	23:00	Comment
				Start Frac Stage #17. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 27 holes open, 586 psi perf friction, 76 psi NWB as per FracPro. 3. Stage went well with all proppant placed. 4. ProTechnics pumped 18 Cups of CFT 1900. BC-200-4% (6.4) , FR-76-3.5% (1.2) , MO-67-3.5% (2.8) , MC S-2510T-2.6% (2) Vicon NF-3.9% (9.5) , Losurf 300D-4.5% (7) FE-2A-4.2% (1.6) , BE-9-4.7% (2.2)
Start Time	02:00	End Time	02:00	Comment
				P&P 18
Start Time	01:00	End Time	02:00	Comment
				RIH to P&P Stage # 18.
Report Start Date	Report End Date	24hr Activity Summary		
12/3/2014	12/4/2014	Frac stages 13,14,15,16,17,18,19 P&P stages 13,14,15,16,17,18,19		
Start Time	00:00	End Time	01:00	Comment
				Plug and Perf: Stage #18 RIH with guns and Plug to KOP. pumped down guns at 12.1 bpm @ 4,037 Psi, @247 fpm, 880 LT, pumped guns to 13,853', Pulled up and got line tension and set plug. Line tension prior to setting plug 1,564, line tension after plug set 1,333, plug set time 64 secs. POH and perf'd at (13,830'-13,833') (13,755'-13,758') (13,679'-13,682'), POOH with tools, max pressure for pump down: 4,037, Max rate for pump down 12.1 bpm. Total BBls pumped 278.27, POOH W/Wireline all shots fired, Turn well over to Frac.

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	01:00	End Time	03:00	Comment
				Start Frac Stage # 18. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 24 holes open, 714 psi perf friction, 37 psi NWB as per FracPro. 3. Stage went well with all proppant placed. 4. ProTechnics pumped 17 cups of CFT 2000 during the stage. Ball Seat Stage Pressures and Rate: 4286 psi @ 14.9 bpm , 4102 psi Pressure before Seating , 4286 psi Pressure after Seating. BC-200-4.3% (6.8) , FR-76-3.8% (1.3) , MO-67-2.7% (2.1) , MC S-2510T-4.2% (3.3) Vicon NF-3.8% (9.4) , Losurf 300D-4.2% (6.5) BE-9-2.2% (1)
Start Time	03:00	End Time	05:00	Comment
				Plug and Perf: Stage #19 RIH with guns and Plug to KOP. pumped down guns at 12.1 bpm @ 4,139 Psi, @236 fpm, 913 LT, pumped guns to 13,630', Pulled up and got line tension and set plug. Line tension prior to setting plug 1,485, line tension after plug set 1,201, plug set time 90 secs. POH and perfed at (13,599'-13,602') (13,524'-13,527') (13,448'-13,451'), POOH with tools, max pressure for pump down: 4,139, Max rate for pump down 12.1 bpm. Total BBIs pumped 265.12, POOH W/Wireline. All shots fired. Drop ball & turn over to Frac.
Start Time	05:00	End Time	07:00	Comment
				Start Frac Stage #19. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 25 holes open, 713 psi perf friction, 58 psi NWB as per FracPro. 3. Observed a pressure build with 1 ppg 100 mesh on formation and again with 1.5 ppg 30/50 on formation. 4. Stage went well with all proppant placed. Ball Seat Stage Pressures and Rate: 4262 psi @ 15.4 bpm , 4135 psi Pressure before Seating , 4262 psi Pressure after Seating. WG-36-11.8% (260.5) , BC-200-5% (7.8) , FR-76-3.1% (1) , BA-20-4.1% (1.5) , MO-67-3.9% (3.1) , MC S-2510T-4.2% (3.3) Vicon NF-4.2% (10.2) , Losurf 300D-4.7% (7.4) Cat 3/4-5.3% (1.2) , BE-9-4.3% (2)
Start Time	07:00	End Time	09:00	Comment
				Plug and Perf: Stage #20 RIH with guns and Plug to KOP. pumped down guns at 12.1 bpm @ 3,844 Psi, @245 fpm, 905 LT, pumped guns to 13,395' Pulled up and got line tension and set plug @13,396'. Line tension prior to setting plug 1,593, line tension after plug set 1,370, plug set time 47 sec. POH and perfed at (13,368'-13,371') (13,293'-13,296') (13,217'-13,220'), POOH with tools, max pressure for pump down: 3,844, Max rate for pump down 13.1 bpm. Total BBIs pumped 269. All shots fired. Drop ball & turn over to Frac.
Start Time	09:00	End Time	11:00	Comment
				Start Frac Stage #20. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 26 holes open, 705 psi perf friction, 298 psi NWB as per FracPro. 3. Good job execution by the crew, all sand placed. Ball Seat Stage Pressures and Rate: 4300 psi @ 15.8 bpm , 4015 psi Pressure before Seating , 4311 psi Pressure after Seating. WG-36-5% (104.6) , BC-200-4.9% (7.4) , FR-76-25.8% (7.2) , MO-67-3.7% (2.8) , MC S-2510T-5% (3.8) Vicon NF-9.8% (24.5) , Losurf 300D-4.4% (6.7) FE-2A-6.7% (2.4) , Cat 3/4-7.4% (1.7) ,
Start Time	11:00	End Time	12:30	Comment
				: Plug and Perf: Stage #21 RIH with guns and Plug to KOP. pumped down guns at 13 bpm @ 3,921 Psi, @260 fpm, 905 LT, pumped guns to 13,195' Pulled up and got line tension and set plug @13,165'. Line tension prior to setting plug 1,638, line tension after plug set 1,408, plug set time 50 sec. POH and perfed at (13,137'-13,140') (13,062'-13,065') (12,986'-12,989'), POOH with tools, max pressure for pump down: 3,921, Max rate for pump down 13 bpm. Total BBIs pumped 259. All shots fired. Shut HCR valve.
Start Time	12:30	End Time	13:30	Comment
				Grease Frac Tree.
Start Time	13:30	End Time	15:30	Comment
				Start Frac Stage #21. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 23 holes open, 969 psi perf friction, 405 psi NWB as per FracPro. 3. Gel coming during job a 1-2 points light. XL samples looked good throughout. 4. Good job execution by the crew, all sand placed. Ball Seat Stage Pressures and Rate: 4472 psi @ 15.5 bpm , 4126 psi Pressure before Seating , 4475 psi Pressure after Seating BC-200-2.1% (3.3) , FR-76-13.7% (3.6) , BA-20-14.4% (5.3) , MC S-2510T-4.3% (3.3) Vicon NF-8.4% (23) , Losurf 300D-3.6% (5.7) FE-2A-17.1% (5.5) , Cat 3/4-30.7% (8) , BE-9-4.3% (2)

Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	15:30	End Time	17:00	Comment
				Plug and Perf: Stage #22 RIH with guns and Plug to KOP. pumped down guns at 13.1 bpm @ 4,033 Psi, @254 fpm, 900 LT, pumped guns to 12,950' Pulled up and got line tension and set plug @12,934'. Line tension prior to setting plug 1,850, line tension after plug set 1,600, plug set time 19 sec. POH and perfed at (12,906'-12,909') (12,831'-12,834') (12,755'-12,758'), POOH with tools, max pressure for pump down: 4,033, Max rate for pump down 13.1 bpm. Total BBIs pumped 254. POOH W/tools & check guns. Drop ball & turn over to Frac
Start Time	17:00	End Time	19:00	Comment
				Frac Stage #22, 1. Global Kick Outs set at 9500 psi. Pressure tested to 10400 psi. Job pumped Produced Water. 2. Calculated 25 holes open, 853 psi perf friction, 663 psi NWB as per FracPro. 3. Lost a pump due to power end problem, made up rate with remaining 9 pumps. 4. Stage treated well with all proppant placed. Ball Seat Stage Pressures and Rate: 4742 psi @ 15.2 bpm, 4343 psi Pressure before Seating, 4744 psi Pressure after Seating, WG-36-2.5% (43.4), BC-200-4.7% (7.1), FR-76-3.8% (1.2), BA-20-3.6% (1.3), MO-67-4.7% (3.6), MC S-2510T-3% (2.3) Vicon NF-4.5% (10.8), Losurf 300D-4.3% (6.6), FE-2A-2.7% (1), BE-9-3.9% (1.8)
Start Time	19:00	End Time	21:00	Comment
				Plug and Perf: Stage #23 RIH with guns and Plug to KOP. pumped down guns at 11.0 bpm @ 3,938 Psi, @231 fpm, 820 LT, pumped guns to 12,717', Pulled up and got line tension and set plug. Line tension prior to setting plug 1,620, line tension after plug set 1,440, plug set time 30 secs. POH and perfed at (12,675'-12,678') (12,600'-12,603') (12,495'-12,498'), POOH with tools, max pressure for pump down: 3,938, Max rate for pump down 11.0 bpm. Total BBIs pumped 246.28, POOH W/Wireline all shots fired, Turn well over to Frac.
Start Time	21:00	End Time	23:30	Comment
				Start Frac Stage #23, 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 24 holes open, 422 psi perf friction, 613 psi NWB as per FracPro. 3. Stage went well with all proppant placed. Ball Seat Stage Pressures and Rate: 4716 psi @ 14.6 bpm, 4300 psi Pressure before Seating, 4716 psi Pressure after Seating, WG-36-2.6% (45.3), BC-200-4.2% (6.5), BA-20-3.9% (1.3), MO-67-3.5% (2.7), Vicon NF-3.5% (7.9), Losurf 300D-4.6% (6.8)
Start Time	23:30	End Time	00:00	Comment
Report Start Date	Report End Date	24hr Activity Summary		Start in hole to P&P stage #24 at report time.
12/4/2014	12/5/2014	Frac stages 24,25,26,27,28 & 29 P&P stages 24,25,26,27,28,29 & 30		
Start Time	00:00	End Time	01:30	Comment
				Plug and Perf: Stage #24 RIH with guns and Plug to KOP. pumped down guns at 12.0 bpm @ 3,980 Psi, @235 fpm, 829 LT, pumped guns to 12,462', Pulled up and got line tension and set plug. Line tension prior to setting plug 1,540, line tension after plug set 1,278, plug set time 54 secs. POH and perfed at (12,444'-12,447') (12,369'-12,372'), POOH with tools, max pressure for pump down: 3,980, Max rate for pump down 12.0 bpm. Total BBIs pumped 215.10, POOH W/Wireline all shots fired, Turn well over to Frac.
Start Time	01:30	End Time	03:30	Comment
				Start Frac Stage #24, 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 17 holes open, 1216 psi perf friction, 370 psi NWB as per FracPro. 3. Hopper dropped off during 0.5 ppg 100 mesh resulting in a dip in proppant concentration. WG-36-4.8% (70.5), BC-200-4.7% (5.2), FR-76-4.1% (1.2), MO-67-3.8% (2.1), MC S-2510T-4.2% (2.6) Vicon NF-4.8% (8.9), Losurf 300D-4% (4.9), BE-9-4.8% (1.7).

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	03:30	End Time	05:00	Comment
				Plug and Perf: Stage #25 RIH with guns and Plug to KOP. pumped down guns at 12.0 bpm @ 4,293 Psi, @230 fpm, 820 LT, pumped guns to 12,248'. Pulled up and got line tension and set plug. Line tension prior to setting plug 1,570, line tension after plug set 1,270, plug set time 53 secs. POH and perf'd at (12,293'-12,296') (12,196'-12,199') (12,062'-12,065'), POOH with tools, max pressure for pump down: 4,293, Max rate for pump down 12.0 bpm. Total BBIs pumped 196.55, POOH W/Wireline all shots fired, Turn well over to Frac.
Start Time	05:00	End Time	07:00	Comment
				Start Frac Stage #25. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 24 holes open, 576 psi perf friction, 352 psi NWB as per FracPro. 3. Stage went well with all proppant placed. Ball Seat Stage Pressures and Rate: 4521 psi @ 14.9 bpm, 4249 psi Pressure before Seating, 4521 psi Pressure after Seating WG-36-20.1% (332.9), BC-200-4.5% (7.2), BA-20-3.6% (1.2), MO-67-3.9% (3.1), MC S-2510T-4.1% (3.1) Vicon NF-4.4% (10.2), Losurf 300D-3.5% (5.2) FE-2A-4.1% (1.4), BE-9-2.4% (1.1)
Start Time	07:00	End Time	08:30	Comment
				P&P Stage #26. RIH with guns and Plug to KOP. pumped down guns at 13.1 bpm @ 4,046 Psi, @250 fpm, 910 LT, pumped guns to 12,020' Pulled up and got line tension and set plug @12,010'. Line tension prior to setting plug 1,414, line tension after plug set 1,270, plug set time 56 sec. POH and perf'd at (11,984'-11,987') (11,924'-11,927') (11,868'-11,871'), POOH with tools, max pressure for pump down: 4,046, Max rate for pump down 13.1 bpm. Total BBIs pumped 201. POOH W/tools. All shots fired. Drop ball & turn over to Frac.
Start Time	08:30	End Time	10:30	Comment
				Start Frac Stage #26. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10450 psi. Job pumped Produced Water. 2. Calculated 26 holes open, 683 psi perf friction, 747 psi NWB as per FracPro. 3. A few minor pump problems up front with the rate, was able to line out at 60 bpm for job. 4. Had a quick sand spike on 1.5 ppa stage, fat fingered number in the van. 5. Overall good job execution by the crew, all sand placed. Ball Seat Stage Pressures and Rate: 5170 psi @ 16.2 bpm, 4558 psi Pressure before Seating, 5179 psi Pressure after Seating. WG-36-9.8% (170.9), BC-200-4% (6.2), BA-20-3% (1), MO-67-4% (3.1), MC S-2510T-5.1% (3.8) Vicon NF-4.5% (10.8), Losurf 300D-4.3% (6.4) BE-9-4.7% (2.1)
Start Time	10:30	End Time	12:00	Comment
				Plug and Perf: Stage #27 RIH with guns and Plug to KOP. pumped down guns at 12.6 bpm @ 4,165 Psi, @257 fpm, 892 LT, pumped guns to 11,850' Pulled up and got line tension and set plug @11,835'. Line tension prior to setting plug 1,595, line tension after plug set 1,396, plug set time 44 sec. POH and perf'd at (11,804'-11,807') (11,744'-11,747') (11,684'-11,687'), POOH with tools, max pressure for pump down: 4,165, Max rate for pump down 12.6 bpm. Total BBIs pumped 184. POOH w/ tools. All shots fired. Shut HCR.
Start Time	12:00	End Time	13:00	Comment
				Grease Frac Tree.
Start Time	13:00	End Time	15:00	Comment
				Start Frac Stage # 27. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10460 psi. Job pumped Produced Water. 2. Calculated 27 holes open, 450 psi perf friction, 1092 psi NWB as per FracPro. 3. Good job execution, all sand placed. 4. Gel continues to run heavy, visc is still running 16-17 cp at 75F. WG-36-17.9% (305.8), BC-200-5.3% (8.1), FR-76-4.2% (1.3), BA-20-3.6% (1.2), MO-67-4.6% (3.5), MC S-2510T-3.3% (2.5) Vicon NF-5.3% (12.5), Losurf 300D-4.7% (7.1) FE-2A-3.4% (1.2), BE-9-5.2% (2.3)
Start Time	15:00	End Time	16:30	Comment
				Plug and Perf: Stage #28 RIH with guns and Plug to KOP. pumped down guns at 12.8 bpm @ 4,160 Psi, @264 fpm, 928 LT, pumped guns to 11,650' Pulled up and got line tension and set plug @11,630'. Line tension prior to setting plug 1,301, line tension after plug set 1,158, plug set time 67 sec. POH and perf'd at (11,605'-11,608') (11,550'-11,553') (11,475'-11,478'), POOH with tools, max pressure for pump down: 4,160, Max rate for pump down 12.8 bpm. Total BBIs pumped 169. POOH w/ tools. All shots fired. Drop ball & turn over to frac.

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	16:30	End Time
		18:30
Comment		
Start Frac Stage #28. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 25 holes open, 808 psi perf friction, 647 psi NWB as per FracPro. 3. Good job execution, all sand placed. Ball Seat Stage Pressures and Rate: 4675 psi @ 15 bpm , 4300 psi Pressure before Seating , 4690 psi Pressure after Seating. WG-36-4.6% (80.8) , BC-200-2.7% (4.3) , FR-76-4.2% (1.2) , BA-20-4.5% (1.5) , CL-31-4.6% (1.1) MO-67-5% (4) , MC S-2510T-4.7% (3.4) Vicon NF-4.8% (11) , Losurf 300D-4.7% (6.7) FE-2A-3.7% (1.2) , BE-9-4.7% (2)		
Start Time	18:30	End Time
		20:00
Comment		
Plug and Perf: Stage #29 RIH with guns and Plug to KOP. pumped down guns at 12.9 bpm @ 4,100 Psi. @ 288 fpm, 870 LT, pumped guns to 11,450' Pulled up and got line tension and set plug @11,410'. Line tension prior to setting plug 1,290, line tension after plug set 1,120, plug set time 69 sec. POOH and perf'd at (11,400'-403') (11,325'-328') (11,250'-253'), POOH with tools, max pressure for pump down: 4,100, Max rate for pump down 12.9 bpm. Total BBIs pumped 150. POOH w/ tools. All shots fired . Drop ball & turn over to frac. To Frac Stage #29.		
Start Time	20:00	End Time
		22:00
Comment		
Frac stage #29 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 23 holes open, 724 psi perf friction, 357 psi NWB as per FracPro. 3. Stage treated well with all proppant placed. 4. Had rate fluctuate shortly after going to flush. WG-36-3.9% (68) , BC-200-4.2% (6.5) , FR-76-4.5% (1.3) , BA-20-3.5% (1.1) , MO-67-4.9% (3.8) , MC S-2510T-4.5% (3.1) Losurf 300D-4.5% (6.3) FE-2A-4.1% (1.3) , BE-9-4.1% (1.7)		
Start Time	22:00	End Time
		23:30
Comment		
Plug and Perf: Stage #30 RIH with guns and Plug to KOP. pumped down guns at 12.7 bpm @ 4,128 Psi. @ 302 fpm, 834 LT, pumped guns to 11,190' Pulled up and got line tension and set plug @11,170'. Line tension prior to setting plug 1,320, line tension after plug set 1,160, plug set time 65 sec. POOH and perf'd at (11,175'-178') (11,100'-103') (11,025'-028'), POOH with tools, max pressure for pump down: 4,128, Max rate for pump down 12.7 bpm. Total BBIs pumped 130. POOH w/ tools. All shots fired . Drop ball & turn over to frac. To Frac Stage #30.		
Start Time	23:30	End Time
		00:00
Comment		
Frac stg #30		
Report Start Date	Report End Date	24hr Activity Summary
12/5/2014	12/6/2014	Frac stgs 30,31,32,33 & 34. Perf'd stgs 31,32,33,34 & 35
Start Time	00:00	End Time
		01:30
Comment		
Frac stg #30 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 21 holes open, 861 psi perf friction, 347 psi NWB as per FracPro. 3. Had rate fluctuating from the middle of 1.5 ppg to 2.5 ppg and again during flush. 4. Cat 3/4 had trouble lining out until 2.5 ppg and gel ran heavy throughout the stage. 5. Stage treated well with all proppant placed. Ball Seat Stage Pressures and Rate: 4591 psi @ 14.9 bpm , 4319 psi Pressure before Seating , 4591 psi Pressure after Seating. WG-36-16.7% (281.8) , BC-200-4.8% (7.5) , FR-76-4.6% (1.3) , BA-20-5% (1.7) , MO-67-4.2% (3.2) , MC S-2510T-4.6% (3.2) Vicon NF-5.4% (12.2) , Losurf 300D-5.3% (Cat 3/4-28.8% (6.1) , BE-9-5% (2.1)		
Start Time	01:30	End Time
		03:30
Comment		
Plug and Perf: Stage #31 RIH with guns and Plug to KOP. pumped down guns at 13.1 bpm @ 3,950 Psi. @ 287 fpm, 880 LT, pumped guns to 10,955' Pulled up and got line tension and set plug @10,945'. Line tension prior to setting plug 1,280, line tension after plug set 1,115, plug set time 74 sec. POOH and perf'd at (10,950'-953') (10,875'-878') (10,800'-803'), POOH with tools, max pressure for pump down: 3,950, Max rate for pump down 13.1 bpm. Total BBIs pumped 82. POOH w/ tools. To Frac Stage #31.		

Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time 03:30	End Time 06:00	Comment Had to wait on stg #31 frac due to Halliburton working on horsepower. Start Frac Stage #31. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 25 holes open, 645 psi perf friction, 352 psi NWB as per FracPro. 3. Stage treated well with all proppant placed. 4. Pump operator unintentionally dropped rate just after staging to flush. Rate was completely recovered. 5. Gel ran heavy to get the correct visc. Ball Seat Stage Pressures and Rate: 4456 psi @ 14.8 bpm, 4183 psi Pressure before Seating, 4456 psi Pressure after Seating. WG-36-17.7% (292.5), BC-200-4.8% (7.6), CL-31-4.6% (1.1) MO-67-4.6% (3.7), MC S-2510T-3.7% (2.6) Vicon NF-5.2% (11.7), Losurf 300D-5.2% (7.3) FE-2A-4.8% (1.5), BE-9-4.2% (1.8)
Start Time 06:00	End Time 07:00	Comment Plug and Perf: Stage #32 RIH with guns and Plug to KOP. pumped down guns at 13.1 bpm @ 4,180 Psi, @ 258 fpm, 920 LT, pumped guns to 10,790' Pulled up and got line tension and set plug @10,756'. Line tension prior to setting plug 1,242, line tension after plug set 1,093, plug set time 40 sec. POOH and perfed at (10,725'-728') (10,675'-678') (10,578'-581'), POOH with tools, max pressure for pump down: 4,180, Max rate for pump down 13.1 bpm. Total BBIs pumped 131. POOH w/ tools. All shot fired. Shut in HCR.
Start Time 07:00	End Time 08:00	Comment Grease Frac Tree.
Start Time 08:00	End Time 10:00	Comment Start Frac Stage #32. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 25 holes open, 728 psi perf friction, 736 psi NWB as per FracPro. 3. MO-67 tote was swapped before job start. Had XL confirmed and went to sand. Lost XL towards end of 1.5 ppa stage. Increased set point and regained XL. Will check tote after job. 4. Good job execution by the crew, all sand placed. Ball Seat Stage Pressures and Rate: 4890 psi @ 15.2 bpm, 4483 psi Pressure before Seating, 4895 psi Pressure after Seating WG-36-17% (284.2), FR-76-5.7% (1.6), BA-20-4.4% (1.5), CL-31-6.4% (1.5) MO-67-9.8% (10.7), MC S-2510T-5.4% (3.7) Vicon NF-5.8% (12.8), Losurf 300D-6.1% (8.5) BE-9-3.5% (1.4)
Start Time 10:00	End Time 14:00	Comment Ran in hole W/wireline & pumped down to 10,500' and lost communication W/CCL tried a few things to get it to work with no luck. Pooh W/tools & cut off 1000' of wireline. Fixed some wiring in truck. Checked everything on surface everything working like designed.
Start Time 14:00	End Time 16:00	Comment Plug and Perf: Stage #33 RIH with guns and Plug to KOP. pumped down guns at 12.9 bpm @ 4,439 Psi, @ 256 fpm, 899 LT, pumped guns to 10,565' Pulled up and got line tension and set plug @10,550'. Line tension prior to setting plug 1,246, line tension after plug set 1,063, plug set time 50 sec. POOH and perfed at (10,525'-528') (10,455'-458') (10,385'-388'), POOH with tools, max pressure for pump down: 4,439, Max rate for pump down 12.9 bpm. Total BBIs pumped 131. POOH w/ tools. All shot fired. Drop ball & turn over to Frac.
Start Time 16:00	End Time 18:00	Comment Start Frac Stage #34. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 24 holes open, 751 psi perf friction, 740 psi NWB as per FracPro. 3. Had problems starting MO-67, dropped rate to trouble shoot. The tote was closed, re-prime the line and got going. Once good XL was established, proceeded with sand. The XL pad ran long before starting the 30/50. 4. Started to MO-67 at 1.5 gpt, pH started creeping higher during job. Backed off to a 1 gpt for the remainder of the job. 5. Overall good job execution by the crew, all sand placed. Ball Seat Stage Pressures and Rate: 4860 psi @ 14.9 bpm, 4610 psi Pressure before Seating, 4865 psi Pressure after Seating. WG-36-9.8% (183.4), BC-200-4.9% (8.5), FR-76-4.7% (1.3), BA-20-4.1% (1.5), MO-67-3.5% (3.8), MC S-2510T-4.7% (3.5) Vicon NF-4.3% (10.3), Losurf 300D-4.7% (7) FE-2A-3.6% (1.1), BE-9-2.9% (1.3)

NEWFIELD



Summary Rig Activity

Well Name: Powitch 15-13-12-3-2WB

Start Time	18:00	End Time
		19:30
Comment		
Plug and Perf: Stage #34 RIH with guns and Plug to KOP. pumped down guns at 12.8 bpm @ 4,200 Psi, @ 286 fpm, 882 LT, pumped guns to 10,355' Pulled up and got line tension and set plug @10,310'. Line tension prior to setting plug 1,250 line tension after plug set 1,110, plug set time 75 sec. POOH and perfed at (10,315'-318') (10,245'-248') (10,175'-178'), POOH with tools, max pressure for pump down: 4,200, Max rate for pump down 12.8 bpm. Total BBIs pumped 101. POOH w/ tools.		
Start Time	19:30	End Time
		21:30
Comment		
Frac stg #34 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 21 holes open, 892 psi perf friction, 28 psi NWB as per FracPro. 3. Stage went well with all proppant placed. Ball Seat Stage Pressures and Rate: 4802 psi @ 15.1 bpm , 4435 psi Pressure before Seating , 4802 psi Pressure after Seating. WG-36-17% (287.8) , BC-200-4.9% (8) , MO-67-4.4% (3.5) , MC S-2510T-4.1% (2.9) Vicon NF-4.7% (10.6) , Losurf 300D-4.4% BE-9-3.4% (1.5)		
Start Time	21:30	End Time
		23:00
Comment		
Plug and Perf: Stage #35 RIH with guns and Plug to KOP. pumped down guns at 12.8 bpm @ 4,200 Psi, @ 286 fpm, 882 LT, pumped guns to 10,355' Pulled up and got line tension and set plug @10,310'. Line tension prior to setting plug 1,250 line tension after plug set 1,110, plug set time 75 sec. POOH and perfed at (10,315'-318') (10,245'-248') (10,175'-178'), POOH with tools, max pressure for pump down: 4,200, Max rate for pump down 12.8 bpm. Total BBIs pumped 101. POOH w/ tools.		
Start Time	23:00	End Time
		00:00
Comment		
Frac stg #35		
Report Start Date	Report End Date	24hr Activity Summary
12/6/2014	12/7/2014	Frac Stgs 35,36,37,38,39,40 & 41. Perf Stgs 36,37,38,39,40 & 41. Set First kill plug.
Start Time	00:00	End Time
		01:00
Comment		
Frac Stg #35. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 22 holes open, 818 psi perf friction, 254 psi NWB as per FracPro. 3. Stage treated well with all proppant placed. 4. Had to drop a pump during flush to due to a broken pony rod. Ball Seat Stage Pressures and Rate: 4733 psi @ 15 bpm , 5380 psi Pressure before Seating , 4733 psi Pressure after Seating. WG-36-3.4% (68.2) , BC-200-5.1% (8) , MO-67-4.5% (3.5) , MC S-2510T-4.5% (3.1) Vicon NF-4.6% (10.2) , Losurf 300D-4.3% (5.9) . FE-2A-4.4% (1.3) , BE-9-2.9% (1.2)		
Start Time	01:00	End Time
		02:30
Comment		
Plug and Perf: Stage #36 RIH with guns and Plug to KOP. pumped down guns at 12.9 bpm @ 4,150 Psi, @ 308 fpm, 870 LT, pumped guns to 9,925' Pulled up and got line tension and set plug @9,910'. Line tension prior to setting plug 1,160 line tension after plug set 1,020, plug set time 56 sec. POOH and perfed at (9,858'-861') (9,797'-800') POOH with tools, max pressure for pump down: 4,150, Max rate for pump down 12.9 bpm. Total BBIs pumped 76. POOH w/ tools.		
Start Time	02:30	End Time
		05:00
Comment		
Frac stg #36. Halliburton had issues with crosslinker before going to 30/50 sand had to shut down until the issue was resolved. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 18 holes open, 1061 psi perf friction, 374 psi NWB as per FracPro. 3. Could not get crosslinker going and had issues with MO-67 during pad. Shutdown and resolved the issues prior to going to 30/50. 4. Issue was resolved in ~45 mins. 5. 30/50 ran ~10,000 lbs long out of the mover. 6. Stage treated well. Ball Seat Stage Pressures and Rate: 4540 psi @ 15.1 bpm , 4224 psi Pressure before Seating , 4540 psi Pressure after Seating WG-36-26.6% (494.9) , BC-200-5.1% (8.7) , BA-20-3.3% (1.1) , MO-67-5.1% (4.4) , MC S-2510T-4.3% (3) Losurf 300D-4.3% (6) BE-9-3.9% (1.6)		

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	05:00	End Time	07:00	Comment
				Plug and Perf: Stage #37 RIH with guns and Plug to KOP. pumped down guns at 12.3 bpm @ 4,335 Psi, @ 258 fpm, 878 LT, pumped guns to 9,690' Pulled up and got line tension and set plug @9,740'. Line tension prior to setting plug 1,178 line tension after plug set 1,050, plug set time 76 sec. POOH and perfed at (9,672'-675') (9,600'-603')(9,521'-524') POOH with tools, max pressure for pump down: 4,335, Max rate for pump down 12.3 bpm. Total BBIs pumped 77. POOH w/ tools. All shots fired. Drop ball & turn over to Frac.
Start Time	07:00	End Time	09:00	Comment
				Frac Stg #37. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 20 holes open, 867 psi perf friction, 136 psi NWB as per FracPro. 3. 20 cups 3700 CFT Protechnics tracer. WG-36-7.8% (140), BC-200-4.3% (6.8), BA-20-4.3% (1.4), MO-67-3.9% (3.1), MC S-2510T-4.2% (2.8) Vicon NF-4.2% (9.2), Losurf 300D-4.2% (5.6) BE-9-3.2% (1.3)
Start Time	09:00	End Time	10:30	Comment
				: Plug and Perf: Stage #38 RIH with guns and Plug to KOP. pumped down guns at 12.3 bpm @ 4,080 Psi, @ 252 fpm, 920 LT, pumped guns to 9,510' Pulled up and got line tension and set plug @9,490'. Line tension prior to setting plug 1,168 line tension after plug set 1,017, plug set time 46 sec. POOH and perfed at (9,441'-444') (9,366'-369')(9,290'-293') POOH with tools, max pressure for pump down: 4,080, Max rate for pump down 12.4 bpm. Total BBIs pumped 62. POOH w/ tools. All shots fired. Shut HCR.
Start Time	10:30	End Time	11:00	Comment
				Grease Frac Tree.
Start Time	11:00	End Time	12:30	Comment
				Frac stg #38. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 25 holes open, 767 psi perf friction, 556 psi NWB as per FracPro. 3. 20 cups 3900 CFT Protechnics tracer. WG-36-13.8% (232.8), BC-200-4% (6.3), FR-76-5.3% (1.4),BA-20-4.1% (1.4), CL-31-5.9% (1.4) MO-67-3.4% (2.7), MC S-2510T-4.9% (3.3) Vicon NF-3.8% (8.4), Losurf 300D-4.9% (6.7) FE-2A-13.1% (3.4), Cat 3/4-4.8% (1), BE-9-3.4% (1.4)
Start Time	12:30	End Time	14:00	Comment
				Plug and Perf: Stage #39 RIH with guns and Plug to KOP. pumped down guns at 11.8 bpm @ 4,041 Psi, @ 245 fpm, 929 LT, pumped guns to 9,250' Pulled up and got line tension and set plug @9,238'. Line tension prior to setting plug 1,222 line tension after plug set 1,042, plug set time 60 sec. POOH and perfed at (9,210'-213') (9,137'-140')(9,059'-062') POOH with tools, max pressure for pump down: 4,041, Max rate for pump down 11.8 bpm. Total BBIs pumped 48. POOH w/ tools. All shots fired. Drop ball & turn over to Frac.
Start Time	14:00	End Time	16:00	Comment
				Frac stg #39. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 27 holes open, 585 psi perf friction, 112 psi NWB as per FracPro. 3. 22 cups CFT 3900 Protechnics tracer. WG-36-7.9% (134.9), CL-31-6.5% (1.6) MO-67-2.9% (2.4), Vicon NF-4.3% (9.5), Losurf 300D-4.3% (5.8) Cat 3/4-6.7% (1.4), BE-9-4.7% (1.9)
Start Time	16:00	End Time	17:30	Comment
				Plug and Perf: Stage #40 RIH with guns and Plug to KOP. pumped down guns at 11 bpm @ 3,932 Psi, @ 248 fpm, 853 LT, pumped guns to 9,055' Pulled up and got line tension and set plug @9,020'. Line tension prior to setting plug 1,192 line tension after plug set 1,046, plug set time 24 sec. POOH and perfed at (8,979'-982') (8,904'-907')(8,828'-831') POOH with tools, max pressure for pump down: 3,932, Max rate for pump down 11 bpm. Total BBIs pumped 37. POOH w/ tools. All shots fired. Drop ball & turn over to Frac.

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time 17:30	End Time 19:30	Comment Frac stg #40. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 25 holes open, 776 psi perf friction, 279 psi NWB as per FracPro. 3. Stage went well with all proppant. WG-36-18.4% (316.2), BC-200-4.6% (7.4), BA-20-4.7% (1.6), MO-67-4.1% (3.3), MC S-2510T-4.2% (2.8) Vicon NF-4.3% (9.5), Losurf 300D-4.2% (5.6). BE-9-4.8% (1.9)
Start Time 19:30	End Time 21:00	Comment Plug and Perf: Stage #41 RIH with guns and Plug to KOP. pumped down guns at 12 bpm @ 3,660 Psi, @ 260 fpm, 960 LT, pumped guns to 8,753' Pulled up and got line tension and set plug @ 8,776'. Line tension prior to setting plug 1,190 line tension after plug set 1,040, plug set time 81 sec. POOH and perfed at (8,748'-751') (8,673'-676')(8,612'-615') POOH with tools, max pressure for pump down: 3,660, Max rate for pump down 12 bpm. Total BBIs pumped 34. POOH w/ tools.
Start Time 21:00	End Time 22:45	Comment Frac Stg #41. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 23 holes open, 738 psi perf friction, 219 psi NWB as per FracPro. 3. 100 Mesh emptied out late. 4. Lost prime to the blender during flush. Reduced rate to alleviate issue and successfully flush the well. Ball Seat Stage Pressures and Rate: 4166 psi @ 15.3 bpm , 4013 psi Pressure before Seating , 4166 psi Pressure after Seating. WG-36-29.7% (485.4), BC-200-5% (7.9), FR-76-4.1% (1), BA-20-4.1% (1.3), MC S-2510T-4.3% (2.8) Vicon NF-4.3% (9.2), Losurf 300D-4.9% (6.4). FE-2A-4.6% (1.2), BE-9-3.7% (1.5)
Start Time 22:45	End Time 00:00	Comment First kill plug is set at 7,930'
Report Start Date 12/7/2014	Report End Date 12/8/2014	24hr Activity Summary Finished up the fracs. RD frac and W/L equipment and ND frac stack and NU BOP stack. Pressure test stack and flowback iron to NFX testing procedures.
Start Time 00:00	End Time 01:30	Comment Set Second Kill plug at 7,890'
Start Time 01:30	End Time 06:00	Comment RD W/L and Frac Equipment and MOL.
Start Time 06:00	End Time 11:00	Comment Clean up location & move off tanks that are not needed. Level out location.
Start Time 11:00	End Time 15:00	Comment ND frac tree & NU BOPS & night cap on top.
Start Time 15:00	End Time 17:00	Comment Testing BOPS & accumulator as per Newfield procedures 250 low 10K high.
Start Time 17:00	End Time 00:00	Comment Wait on daylight.
Report Start Date 12/8/2014	Report End Date 12/9/2014	24hr Activity Summary RU Snubbing unit and WOR and all the equipment on location to do the drillout.
Start Time 00:00	End Time 07:00	Comment Wait on daylight.
Start Time 07:00	End Time 10:00	Comment MIRU WOR
Start Time 10:00	End Time 14:00	Comment MIRU Snub unit
Start Time 14:00	End Time 18:00	Comment Pressure test snub unit as per Newfield's pressure testing Procedures. Test annular to 5K. Spot in Weatherford pump & lines.
Start Time 18:00	End Time 00:00	Comment Finish RU Snubbing unit and WOR equipment.
Report Start Date 12/9/2014	Report End Date 12/10/2014	24hr Activity Summary RIH with PH-6 Workstring and drill out the two kill plugs.

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	00:00	End Time 04:00
		Comment Finish RU Snubbing unit and WOR equipment.
Start Time	04:00	End Time 06:00
		Comment Snubbing unit has blown two hydraulic fitting.
Start Time	06:00	End Time 17:00
		Comment PU BHA. BHA is as follows from bottom to top: Concave Mill (4.625" OD x 1.79'), 2 7/8" ECTD Motor (2.875" OD x 12.00'), Circ Sub (2.875" OD x .750" ID x 0.69'), Dual Flapper (2.875" OD x 1.00" ID x 1.28'), Pup Jt. (2-3/8" x 9.82'), X-Over Sub (2.906" OD x 1.560" ID x 1.13') RN-Nipple (2.906" OD x 1.560" ID x 0.75'). For a total length of 27.64'. PU 256 jts 2-3/8" 5.96# P110 PH6 tbq. Fill tbq every 25 jts. Tag kill plug #2 at 7904' by tbq tally. 14' deeper than WL. Fill WS.
Start Time	17:00	End Time 20:00
		Comment RU power swivel. Power swivel is RU on jt 256 2-3/8" 5.96# P110 PH6 tbq. Tag kill plug #2 at 7904' by tbq tally. 14' deeper than WL. We will break circulation and start to drill up the first kill plug.
Start Time	20:00	End Time 00:00
		Comment 21:06-Tagged First kill plug at 7904' on jt #256, Up weight 53k, down weight 50k, neutral 52. 1750 free torque, 2100 drill torque. WOB: 5-6pts, RPM @ 60-75. 2 bbl in @ 1750psi, 1.5bbl out @ 0psi on full open " choke. 29 minutes to drill plug. Pumped 70bbbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. 22:06-Tagged Second kill plug at 7,944' on jt #258, Up weight 53k, down weight 50k, neutral 52. 1200 free torque, 2350 drill torque. WOB: 5-6pts, RPM @ 60-75. 2 bbl in @ 1200psi, 2.1bbl out @ 2500psi on 18/64 " choke. 54 minutes to drill plug. Pumped 110bbbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. 23:00- Pumping a bottoms up here 135bbbls.
Report Start Date	Report End Date	24hr Activity Summary
12/10/2014	12/11/2014	Drilled out Frac Plugs 41,40,39,38,37,36,35,34,33,32 & 31
Start Time	00:00	End Time 02:30
		Comment Had to PU 26 jts to get to the first flow through frac plug.
Start Time	02:30	End Time 03:30
		Comment 02:43-Tagged Frac plug #41 at 8,788' on jt #285 8' out, Up weight 43k, down weight 38k, neutral 41. 3400 free torque, 4100 drill torque. WOB: 5-6pts, RPM @ 60-75. 2 bbl in @ 3400psi, 2.3bbl out @ 2350psi on 22/64 " choke. 21 minutes to drill plug. Pumped 57bbbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	03:30	End Time 06:00
		Comment 04:28-Tagged Frac plug #40 at 9,032' on jt #293 9' out, Up weight 43k, down weight 38k, neutral 41. 3300 free torque, 3900 drill torque. WOB: 5-6pts, RPM @ 60-75. 2 bbl in @ 3300psi, 2.4bbl out @ 2400psi on 25/64 " choke. 20 minutes to drill plug. Pumped 55bbbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	06:00	End Time 08:00
		Comment 06:00-Tagged Frac plug #40 at 9,249' on jt #300 with 7' out, Up weight 46k, down weight 40k, neutral 43k. 3500 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500psi, 2. bbl out @ 2400 psi on 22/64 " choke. Well head pressure 2300 psi. 37 minutes to drill plug. Pumped 135 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. Circulated 20 minutes while thawing out torq gauge to driller's stand.
Start Time	08:00	End Time 10:00
		Comment 08:10-Tagged Frac plug #38 at 9,500' on jt #308 with 2' out, Up weight 46k, down weight 40k, neutral 43k. 3300 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3300 psi, 2. bbl out @ 2400 psi on 20/64 " choke. Well head pressure 2500 psi. 58 minutes to drill plug. Pumped 112 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	End Time	Comment
10:00	11:00	09:57-Tagged Frac plug #37 at 9,749' on jt #317 with 29' out, Up weight 46k, down weight 40k, neutral 43k. 3300 free torque, 3600 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3300 psi, 2. bbl out @ 2400 psi on 20/64 " choke. Well head pressure 2500 psi. 37 minutes to drill plug. Pumped 90 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
11:00	12:00	Circulate 165 bbl bottoms up.
Start Time	End Time	Comment
12:00	13:00	12:32-Tagged Frac plug #36 at 9,923' on jt #322 with 10' out, Up weight 45k, down weight 39k, neutral 42k. 3800 free torque, 4500 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3800 psi, 2. bbl out @ 2500 psi on 18/64 " choke. Well head pressure 2500 psi. 35 minutes to drill plug. Pumped 76 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
13:00	14:00	13:30-Tagged Frac plug #35 at 10,141' on jt #329 with 7' out, Up weight 45k, down weight 39k, neutral 42k. 3400 free torque, 3600 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3400 psi, 2. bbl out @ 2500 psi on 20/64 " choke. Well head pressure 2500 psi. 46 minutes to drill plug. Pumped 105 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
14:00	17:00	Wash 7 jts sand to plug circulating 20 bbl each jt. 16:34-Tagged Frac plug #34 at 10,352' on jt #336 with 11' out, Up weight 45k, down weight 40k, neutral 42k. 3500 free torque, 3600 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.5 bbl out @ 2400 psi on 27/64 " choke. Well head pressure 2500 psi. 25 minutes to drill plug. Pumped 62 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
17:00	19:00	Circulate 195 bbl bottoms up.
Start Time	End Time	Comment
19:00	20:30	19:41-Tagged Frac plug #33 at 10,559' on jt #343 20' out, Up weight 45k, down weight 40k, neutral 42. 3800 free torque, 4100 drill torque. WOB: 5-6pts, RPM @ 60-75. 2 bbl in @ 3800psi, 2.4bbl out @ 2350psi on 21/64 "choke 31 minutes to drill plug. Pumped 69bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
20:30	22:30	21:44-Tagged Frac plug #32 at 10,765' on jt #350 29' out, We washed 70' of sand to get to the plug. Up weight 45k, down weight 40k, neutral 42k. 3800 free torque, 4100 drill torque. WOB: 5-6pts, RPM @ 60-75. 2 bbl in @ 3800psi, 2.4bbl out @ 2400psi on 21/64 "choke 31 minutes to drill plug. Pumped 82bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
22:30	23:00	Circulate 70 bbl while Nabors has to fix the drill line so we are goking to pump a bottoms up while the y fix the drill line.
Start Time	End Time	Comment
23:00	00:00	Washed two joints of sand.
Report Start Date	Report End Date	24hr Activity Summary
12/11/2014	12/12/2014	Drilled up Frac plugs 30,29,28,27,26,25,24,23,22,21 & 20
Start Time	End Time	Comment
00:00	01:30	00:53-Tagged Frac plug #31 at 10,987' on jt #357 20' out, We washed 222' of sand to get to the plug. Up weight 45k, down weight 40k, neutral 42k. 3600 free torque, 4000 drill torque. WOB: 5-6pts, RPM @ 60-75. 2 bbl in @ 3600psi, 2.7bbl out @ 2400psi on 23/64 "choke 16 minutes to drill plug. Pumped 36bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. We are going to pump a bottoms up here.
Start Time	End Time	Comment
01:30	03:00	Pump a bootoms up at 210bbls.

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	03:00	End Time	04:30	Comment
				03:50-Tagged Frac plug #30 at 11,203' on jt #364 15' out, Up weight 45k, down weight 40k, neutral 42k. 3700 free torque, 4100 drill torque. WOB: 5-6pts, RPM @ 60-75. 2 bbl in @ 3700psi, 2.6bbl out @ 2450psi on 23/64 "choke 33 minutes to drill plug. Pumped 74bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	04:30	End Time	06:30	Comment
				Sand-circulate every jt down to plug. 05:56-Tagged Frac plug #29 at 11,449' on jt #372 with 11' out, Up weight 45k, down weight 39k, neutral 42k. 3600 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3600 psi, 2.4 bbl out @ 2400 psi on 19/64 " choke. Well head pressure 2500 psi. 18 minutes to drill plug. Pumped 40 bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	06:30	End Time	07:45	Comment
				0705-Tagged Frac plug #28 at 11,635' on jt #378 with 18' out, Up weight 45k, down weight 39k, neutral 42k. 3600 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3700 psi, 2.5 bbl out @ 2400 psi on 19/64 " choke. Well head pressure 2500 psi. 35 minutes to drill plug. Pumped 75 bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	07:45	End Time	09:15	Comment
				08:28-Tagged Frac plug #27 at 11,841' on jt #385 with 27' out, Up weight 45k, down weight 39k, neutral 42k. 3500 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.4 bbl out @ 2400 psi on 19/64 " choke. Well head pressure 2500 psi. 36 minutes to drill plug. Pumped 90 bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep
Start Time	09:15	End Time	10:30	Comment
				09:53-Tagged Frac plug #26 at 12,015' on jt #390 with 4' out, Up weight 45k, down weight 39k, neutral 42k. 3500 free torque, 4300 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.4 bbl out @ 2400 psi on 20/64 " choke. Well head pressure 2500 psi. 27 minutes to drill plug. Pumped 73 bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	10:30	End Time	12:30	Comment
				Circulate 240 bbl bottoms up.
Start Time	12:30	End Time	14:15	Comment
				14:15-Tagged Frac plug #25 at 12,337' on jt #401 with 20' out, Up weight 47k, down weight 40k, neutral 43k. 3600 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3600 psi, 2.3 bbl out @ 2300 psi on 20/64 " choke. Well head pressure 2400 psi. 13 minutes to drill plug. Pumped 52 bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	14:15	End Time	15:30	Comment
				15:30-Tagged Frac plug #24 at 12,477' on jt #405 with 3' out, Up weight 47k, down weight 40k, neutral 43k. 3700 free torque, 4100 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3700 psi, 2.3 bbl out @ 2300 psi on 22/64 " choke. Well head pressure 2400 psi. 19 minutes to drill plug. Pumped 56 bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	15:30	End Time	17:00	Comment
				17:05-Tagged Frac plug #23 at 12,716' on jt #413 with 10' out, Up weight 47k, down weight 40k, neutral 43k. 3500 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.4 bbl out @ 2400 psi on 21/64 " choke. Well head pressure 2500 psi. 15 minutes to drill plug. Pumped 38 bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	17:00	End Time	19:00	Comment
				18:25-Tagged Frac plug #22 at 12,944' on jt #421 with 28' out, Up weight 46k, down weight 38k, neutral 41k. 3600 free torque, 4200 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3600 psi, 2.3bbl out @ 2350 psi on 19/64 " choke 23 minutes to drill plug. Pumped 55 bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.

Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	19:00	End Time	20:30	Comment
				19:27-Tagged Frac plug #21 at 13,169' on jt #428 with 19' out, Up weight 46k, down weight 38k, neutral 41k. 3400 free torque, 4200 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3400 psi, 2.8bbl out @ 2300 psi on 17/64 " choke 32 minutes to drill plug. Pumped 69 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. We are going to pump a bottoms up here of 260bbls.
Start Time	20:30	End Time	22:30	Comment
				Pumped a bottoms up of 260bbls
Start Time	22:30	End Time	23:30	Comment
				22:40-Tagged Frac plug #20 at 13,403' on jt #435 with 3' out, Up weight 46k, down weight 38k, neutral 41k. 3700 free torque, 4000 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3700 psi, 2.3bbl out @ 2400 psi on 17/64 " choke 26 minutes to drill plug. Pumped 67 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	23:30	End Time	00:00	Comment
				PU tbg to get down to Frac plug #19.
Report Start Date	Report End Date	24hr Activity Summary		
12/12/2014	12/13/2014	Drilled out frac plugs 19,18,17,16,15,14,13,12,11,10,9,8,7 & 6		
Start Time	00:00	End Time	00:30	Comment
				22:40-Tagged Frac plug #20 at 13,403' on jt #435 with 3' out, Up weight 46k, down weight 38k, neutral 41k. 3700 free torque, 4000 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3700 psi, 2.3bbl out @ 2400 psi on 17/64 " choke 26 minutes to drill plug. Pumped 67 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	00:30	End Time	04:00	Comment
				01:05-Tagged Frac plug #18 at 13,880' on jt #451 with 15' out, Up weight 46k, down weight 38k, neutral 41k. 3400 free torque, 4000 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3400 psi, 2.3bbl out @ 2200 psi on 19/64"choke 30 minutes to drill plug. Pumped 75 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
				02:13-Tagged Frac plug #17 at 14,094' on jt #458 with 16' out, Up weight 46k, down weight 38k, neutral 41k. 3400 free torque, 4000 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3400 psi, 2.1bbl out @ 2325 psi on 17/64"choke 33 minutes to drill plug. Pumped 62 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	04:00	End Time	05:30	Comment
				04:10-Tagged Frac plug #16 at 14,334' on jt #466 with 22' out, Up weight 46k, down weight 38k, neutral 41k. 3400 free torque, 4000 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3400 psi, 2.3bbl out @ 2400 psi on 17/64"choke 28 minutes to drill plug. Pumped 64 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. We are going to pump a bottoms up here of 280bbls.
Start Time	05:30	End Time	07:00	Comment
				Circulate 280 bbl bottoms up.
Start Time	07:00	End Time	08:00	Comment
				07:38-Tagged Frac plug #15 at 4,555' on jt #473 with 16' out, Up weight 50k, down weight 38k, neutral 43k. 3500 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.1 bbl out @ 2400 psi on 22/64 " choke. Well head pressure 2500 psi. 36 minutes to drill plug. Pumped 83 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep
Start Time	08:00	End Time	10:00	Comment
				09:37-Tagged Frac plug #14 at 14,800' on jt #481 with 17' out, Up weight 50k, down weight 38k, neutral 43k. 3500 free torque, 4100 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.3 bbl out @ 2300 psi on 22/64 " choke. Well head pressure 2500 psi. 14 minutes to drill plug. Pumped 42 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	End Time	Comment
10:00	11:15	Pump 5 gal POP. 10:43-Tagged Frac plug #13 at 15,016' on jt #488 with 16' out, Up weight 50k, down weight 38k, neutral 43k. 3500 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.5 bbl out @ 2400 psi on 23/64 " choke. Well head pressure 2500 psi. 27 minutes to drill plug. Pumped 61 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep
Start Time	End Time	Comment
11:15	12:15	12:43-Tagged Frac plug #12 at 15,244' on jt #495 with 4' out, Up weight 50k, down weight 38k, neutral 43k. 4000 free torque, 4500 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 4000 psi, 2.4 bbl out @ 2200 psi on 23/64 " choke. Well head pressure 2400 psi. 19 minutes to drill plug. Pumped 47 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
12:15	13:15	13:40-Tagged Frac plug #11 at 15,437' on jt #502 with 26' out, Up weight 50k, down weight 38k, neutral 43k. 3500 free torque, 4100 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.5 bbl out @ 2200 psi on 23/64 " choke. Well head pressure 2400 psi. 31 minutes to drill plug. Pumped 62 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
13:15	15:15	Circulate 280 bbl bottoms up
Start Time	End Time	Comment
15:15	17:30	16:58-Tagged Frac plug #10 at 15,677' on jt #509 with 7' out, Up weight 50k, down weight 38k, neutral 43k. 3500 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.1 bbl out @ 2300 psi on 21/64 " choke. Well head pressure 2400 psi. 25 minutes to drill plug. Pumped 59 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
17:30	20:30	18:31-Tagged Frac plug #9 at 16,000' on jt #520 with 16' out, Up weight 50k, down weight 38k, neutral 43k. 3500 free torque, 4000 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3500 psi, 2.5 bbl out @ 2400 psi on 17/64 " choke. Well head pressure 2400 psi. 40 minutes to drill plug. Pumped 89 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. 20:12-Tagged Frac plug #8 at 16,173' on jt #526 with 27' out, Up weight 50k, down weight 38k, neutral 43k. 3500 free torque, 4000 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3500 psi, 2.3 bbl out @ 2400 psi on 16/64 " choke. Well head pressure 2400 psi. 18 minutes to drill plug. Pumped 47 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
20:30	23:00	21:03-Tagged Frac plug #7 at 16,343' on jt #5310 with 11' out, Up weight 50k, down weight 38k, neutral 43k. 3600 free torque, 4000 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3600 psi, 2.0 bbl out @ 2300 psi on 17/64 " choke. Well head pressure 2300 psi. 22 minutes to drill plug. Pumped 46 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. 22:03-Tagged Frac plug #6 at 16,553' on jt #538 with 16' out, Up weight 50k, down weight 38k, neutral 43k. 3900 free torque, 4600 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3900 psi, 2.30 bbl out @ 2300 psi on 17/64 " choke. Well head pressure 2300 psi. 34 minutes to drill plug. Pumped 76 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. We are pumping a bottoms up here 330bbls.
Start Time	End Time	Comment
23:00	00:00	We are pumping a bottoms up here 330bbls.
Report Start Date	Report End Date	24hr Activity Summary
12/13/2014	12/14/2014	
Start Time	End Time	Comment
00:00	01:30	We are done pumping a bottoms up here at 16,553' on jt #538 330bbls.


NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	01:30	End Time	03:30	Comment
				01:54-Tagged Frac plug #5 at 16,761' on jt #545 with 23' out, Up weight 50k, down weight 38k, neutral 43k. 3800 free torque, 4300 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3800 psi, 2.5 bbl out @ 2375 psi on 17/64 " choke. Well head pressure 2375 psi. 31 minutes to drill plug. Pumped 72 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
				02:58-Tagged Frac plug #4 at 16,973' on jt #552 with 26' out, Up weight 50k, down weight 38k, neutral 43k. 3700 free torque, 4300 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3700 psi, 2.4 bbl out @ 2300 psi on 18/64 " choke. Well head pressure 2300 psi. 47 minutes to drill plug. Pumped 100 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	03:30	End Time	05:00	Comment
				04:28-Tagged Frac plug #3 at 17,128' on jt #557 with 24' out, Up weight 50k, down weight 38k, neutral 43k. 3800 free torque, 4300 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3800 psi, 2.2 bbl out @ 2350 psi on 17/64 " choke. Well head pressure 2350 psi. 14 minutes to drill plug. Pumped 35 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. Washed sand from frac plug #4 to frac plug #3 we will pump 60 extra bbls here to get the sand way up above us.
Start Time	05:00	End Time	07:00	Comment
				Circulate 300 bbl bottoms up.
Start Time	07:00	End Time	08:00	Comment
				07:36-Tagged Frac plug #2 at 17,319' on jt #563 with 17' out, Up weight 57k, down weight 38k, neutral 43k. 3500 free torque, 4100 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.5 bbl out @ 2400 psi on 18/64 " choke. Well head pressure 2500 psi. 35 minutes to drill plug. Pumped 87 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	08:00	End Time	09:00	Comment
				Clean out to 17,473' on jt #576.
Start Time	09:00	End Time	14:15	Comment
				Pump 10 bbl sweep, 20 bbl spacer, then 10 bbl sweep. Circulate 750 bbl (2.5 times bottoms up).
Start Time	14:15	End Time	18:00	Comment
				SIP 2400 psi. Swivel 10 jts OH. Tie back swivel. LD 2-3/8" WS.
Start Time	18:00	End Time	23:00	Comment
				Con't LD 2 3/8" tbg. With 319 jts of 2 3/8" PH-6 tbg on the ground stop and get ready to circulate bottoms up. EOT @8366'
Start Time	23:00	End Time	00:00	Comment
				Get good jt count on tbg. RU power swivel to circulate bottoms up.
Report Start Date	Report End Date	24hr Activity Summary		
12/14/2014	12/15/2014	Continue the drill out to PBTD. POOH LD tbg.		
Start Time	00:00	End Time	02:00	Comment
				Circulated 180 bbls bottoms up with two 12 bbl sweeps 20 bbls apart. EOT @8366'.
Start Time	02:00	End Time	03:00	Comment
				RD power swivel & rack out. Pickle pumps & flowback iron.
Start Time	03:00	End Time	06:00	Comment
				Continue to LD 2 3/8" 5.95# PH-6 tbg. There is 460 jts out 130 jts in the hole putting EOT @4028'. Shut in & secure well.
Start Time	06:00	End Time	07:30	Comment
				Wait for day light to snub out.
Start Time	07:30	End Time	14:30	Comment
				Finish laying down WS with rig assist snubbing unit. LD BHA. Secure well.
Start Time	14:30	End Time	20:30	Comment
				Change out pipe rams.
Start Time	20:30	End Time	22:30	Comment
				Test BOP stack & snub unit to Newfields testing Procedures.



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time			22:30	End Time		00:00	Comment		SDFN & wait on daylight.
Report Start Date		Report End Date		24hr Activity Summary					
12/15/2014		12/16/2014		Snub WS out of hole. PUMU production string & RIH.					
Start Time			00:00	End Time		07:00	Comment		
Start Time			07:00	End Time		08:30	SDFN & secure well. Wait on daylight.		
Start Time			08:30	End Time		16:30	Comment		
Start Time			16:30	End Time		20:00	PU 2-7/8" notched collar (3.688" OD x 3.00" ID x 0.44' L), 2-7/8" x 2.09' pup jt, 2-7/8" x 4.13' perf pup, 10K ceramic burst disc (3.688" OD x 2.441" ID x 0.78' L), 2-7/8" TUBAL gauge (3.600" OD x 2.200" ID x 3.61' L) 1 jt 2 -7/8" 6.5# EUE 8rd L-80 tbg, 2-7/8" x 2.313" ID x 1.20'L X-nipple. Equalize pressure in BOP stack and open blind/shears and HCR valve. Snub -7/8" 6.5# EUE 8rd L-80 tbg IH.		
Start Time			20:00	End Time		22:00	Comment		
Start Time			22:00	End Time		23:00	RIH on elevators W/111 jts of 2 7/8" 6.5# EUE tbg filling every 25 jts. To get 2-7/8" notched collar (3.688" OD x 3.00" ID x 0.44' L), 2-7/8" x 2.09' pup jt, 2-7/8" x 4.13' perf pup, 10K ceramic burst disc (3.688" OD x 2.441" ID x 0.78' L), 2-7/8" TUBAL gauge (3.600" OD x 2.200" ID x 3.61' L) 1 jt 2-7/8" 6.5# EUE 8rd L-80 tbg, 2-7/8" x 2.313" ID x 1.20'L X-nipple, 140 jts 2 7/8" L-80 6.5# tbg.		
Start Time			23:00	End Time		00:00	Comment		
Report Start Date		Report End Date		24hr Activity Summary					
12/16/2014		12/17/2014		PUMU production string & RIH.					
Start Time			00:00	End Time		04:00	Comment		
Start Time			04:00	End Time		05:00	RD snub unit & spools		
Start Time			05:00	End Time		06:00	Comment		
Start Time			06:00	End Time		07:30	ND BOP stack & HCR valve.		
Start Time			07:30	End Time		09:30	Comment		
Start Time			09:30	End Time		10:15	NU Production tree		
Start Time			10:15	End Time		18:00	Comment		
Start Time			18:00	End Time		00:00	Wait on daylight.		
Start Time			00:00	End Time		04:00	Comment		
Start Time			04:00	End Time		05:00	RDMO WOR,		
Start Time			05:00	End Time		06:00	Comment		
Start Time			06:00	End Time		07:30	POP well at 10:15 AM and turn over to production. Pumped 90 bbls water down tubing and rupture disc, (two tbg volumes), Disc ruptured at 3,000 psi,		
Start Time			07:30	End Time		09:30	Clean location and release equipment.		
Start Time			09:30	End Time		10:15	Comment		
Start Time			10:15	End Time		18:00	Shut down for night		
Start Time			18:00	End Time		00:00			

Form 3160-4
(March 2012)UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB NO. 1004-0137
Expires: October 31, 2014

WELL COMPLETION OR RECOMPLETION REPORT AND LOG

1a. Type of Well <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Dry <input type="checkbox"/> Other b. Type of Completion: <input checked="" type="checkbox"/> New Well <input type="checkbox"/> Work Over <input type="checkbox"/> Deepen <input type="checkbox"/> Plug Back <input type="checkbox"/> Diff. Resrv., Other: _____						5. Lease Serial No. 1420H626176	
2. Name of Operator NEWFIELD PRODUCTION COMPANY						6. If Indian, Allottee or Tribe Name UINTAH AND OURAY	
3. Address ROUTE #3 BOX 3630 MYTON, UT 84052				3a. Phone No. (include area code) Ph:435-646-3721		7. Unit or CA Agreement Name and No.	
4. Location of Well (Report location clearly and in accordance with Federal requirements)* At surface 75' FNL 2332' FEL (NW/NE) SEC 24 T3S R2W At top prod. interval reported below 756' FSL 1835' FEL (NW/NE) SEC 13 T3S R2W At total depth 589' FNL 1975' FEL (NW/NE) SEC 12 T3S R2W						8. Lease Name and Well No. POWITCH 15-13-12-3-2WB	
14. Date Spudded 09/21/2014		15. Date T.D. Reached 10/28/2014		16. Date Completed 12/17/2014 <input type="checkbox"/> D & A <input checked="" type="checkbox"/> Ready to Prod.		9. API Well No. 43-013-51942	
18. Total Depth: MD 17967 TVD 10071		19. Plug Back T.D.: MD 17920 TVD		20. Depth Bridge Plug Set: MD TVD		10. Field and Pool or Exploratory NATURAL BUTTES	
21. Type Electric & Other Mechanical Logs Run (Submit copy of each) DUAL IND GRD, SP, COMP. NEUTRON, GR, CALIPER, CMT BOND						11. Sec., T., R., M., on Block and Survey or Area SEC 24 T3S R2W	
22. Was well cored? <input type="checkbox"/> No <input type="checkbox"/> Yes (Submit analysis) Was DST run? <input checked="" type="checkbox"/> No <input type="checkbox"/> Yes (Submit report) Directional Survey? <input type="checkbox"/> No <input checked="" type="checkbox"/> Yes (Submit copy)						12. County or Parish DUCHESNE	
23. Casing and Liner Record (Report all strings set in well)						13. State UT	
Hole Size	Size/Grade	Wt. (#/ft.)	Top (MD)	Bottom (MD)	Stage Cement Depth	No. of Sk. & Type of Cement	Slurry Vol. (BBL)
19"	13-3/8" J-55	54.50	0'	1663'		1091 CLASS G	
12-5/8"	9-5/8" N-80	40	0'	8014'		1025 Versacem	
						590Expandacem	
8-7/8"	5-1/2" P-110	20	0'	17,967		1265 Tergovis	
						2090 Elasticem	
24. Tubing Record							
Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)	Packer Depth (MD)	Size	Depth Set (MD)
2-7/8"	EOT@7945'	XN@7900'					
25. Producing Intervals				26. Perforation Record			
Formation	Top	Bottom	Perforated Interval	Size	No. Holes	Perf. Status	
A) Wasatch	8612'	17,378	8612' - 17378'	0.38	1062		
B)							
C)							
D)							
27. Acid, Fracture, Treatment, Cement Squeeze, etc.							
Depth Interval		Amount and Type of Material					
8612' - 17378'		Frac w/ 8,500,419#s of proppant sand in 147,387 bbls of clean fluid, in 41 stages.					
28. Production - Interval A							
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API
12/19/14	12/29/14	24	→	1019	627	2407	Gas Gravity
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio
			→				Well Status PRODUCING
28a. Production - Interval B							
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API
			→				Gas Gravity
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio
			→				Well Status

*(See instructions and spaces for additional data on page 2)

28b. Production - Interval C

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

28c. Production - Interval D

Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
			→						
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas/Oil Ratio	Well Status	
			→						

29. Disposition of Gas (Solid, used for fuel, vented, etc.)

30. Summary of Porous Zones (Include Aquifers):

Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.

31. Formation (Log) Markers

GEOLOGICAL MARKERS

Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top
					Meas. Depth
				GARDEN GULCH MEMBER GARDEN GULCH 2	6073' 6469'
				DOUGLAS CREEK B LIMESTON	7171' 7754'
				CASTLE PEAK UTELAND BUTTE	8044' 8330'

32. Additional remarks (include plugging procedure):

Bottom Product Interval:

1060' FNL 1951' FEL (NW/NE) SEC 12 T3S R2W

33. Indicate which items have been attached by placing a check in the appropriate boxes:

- ☐ Electrical/Mechanical Logs (1 full set req'd.)
 ☐ Geologic Report
 ☐ DST Report
 ☒ Directional Survey
- ☐ Sundry Notice for plugging and cement verification
 ☐ Core Analysis
 ☒ Other: Drilling daily activity

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions)*

Name (please print) Heather CalderTitle Regulatory TechnicianSignature Heather CalderDate 01/20/2015

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 3)

(Form 3160-4, page 2)

NEWFIELD

Directional Survey



Legal Well Name Powwitch 15-13-12-3-2WB				Wellbore Name Original Hole					
API/UWI 43013519420000		Surface Legal Location NWNE 75FNL 2332FEL SEC24 T3S R2W MERU		Field Name UINTA CB - BAR F HORZ		Well Type Development		Well Configuration Type Horizontal	
Well RC 500358785		County Duchesne	State/Province Utah		Spud Date 9/21/2014 06:00		Final Rig Release Date 10/28/2014 00:00		

Actual Deviation Survey Actual, Proposed? No	Wellbore Name Original Hole	Parent Wellbore Original Hole	Job Drilling - Original, 9/21/2014 06:00	VS Dir (°)	Profile Type	Kick Off Depth (ftKB) 7,069
---	--------------------------------	----------------------------------	---	------------	--------------	--------------------------------

Date		Definitive?		Description		Proposed?	
9/16/2014		No		Actual		No	
MD Tie In (ftKB)	TVD Tie In (ftKB)	Inclination Tie In (°)		Azimuth Tie In (°)		NSTie In (ft)	EW Tie In (ft)

Survey Data

Date	MD (ftKB)	Incl (°)	Azm (°)	TVD (ftKB)	VS (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Build (°/100ft)	Turn (°/100ft)	Unwrap Displace (ft)	Method	Survey Company
9/16/2014	26	0.00	0.00	26	0	0	0	0.00	0.00	0.00	0.00	MWD	Payzone
10/5/2014	77	31.43	15.93	75	13	13	4	61.57	61.57	31.20	13.65	MWD	Weatherford
9/16/2014	116	0.18	120.56	112	23	23	7	80.81	-80.23	268.63	24.06	MWD	Payzone
9/16/2014	144	0.26	128.30	140	23	23	7	0.30	0.29	27.64	24.16	MWD	Payzone
9/16/2014	174	0.44	158.84	170	23	23	7	0.84	0.60	101.80	24.34	MWD	Payzone
9/16/2014	205	0.44	173.87	201	23	23	7	0.37	0.00	48.48	24.58	MWD	Payzone
9/16/2014	233	0.70	162.35	229	23	22	7	1.01	0.93	-41.14	24.86	MWD	Payzone
9/16/2014	260	0.31	172.11	256	22	22	7	1.47	-1.44	36.15	25.09	MWD	Payzone
9/16/2014	288	0.70	162.75	284	22	22	7	1.42	1.39	-33.43	25.34	MWD	Payzone
9/16/2014	317	0.70	181.78	313	22	22	7	0.80	0.00	65.62	25.69	MWD	Payzone
9/16/2014	346	0.97	176.81	342	21	21	7	0.96	0.93	-17.14	26.11	MWD	Payzone
9/16/2014	373	1.05	175.80	369	21	21	7	0.30	0.30	-3.74	26.59	MWD	Payzone
9/16/2014	401	0.83	187.53	397	20	20	7	1.04	-0.79	41.89	27.04	MWD	Payzone
9/16/2014	431	1.32	173.47	427	20	20	7	1.84	1.63	-46.87	27.60	MWD	Payzone
9/16/2014	459	1.49	177.03	455	19	19	7	0.68	0.61	12.71	28.29	MWD	Payzone
9/16/2014	493	1.32	175.36	489	18	18	7	0.51	-0.50	-4.91	29.12	MWD	Payzone
9/16/2014	523	1.45	181.56	519	18	17	7	0.66	0.43	20.67	29.85	MWD	Payzone
9/16/2014	553	1.49	182.22	548	17	17	7	0.14	0.13	2.20	30.62	MWD	Payzone
9/16/2014	583	1.36	183.01	578	16	16	7	0.44	-0.43	2.63	31.36	MWD	Payzone
9/16/2014	613	1.32	169.60	608	15	15	7	1.05	-0.13	-44.70	32.06	MWD	Payzone
9/16/2014	643	1.31	169.35	638	15	15	7	0.04	-0.03	-0.83	32.75	MWD	Payzone
9/16/2014	673	0.97	163.76	668	14	14	8	1.19	-1.13	-18.63	33.34	MWD	Payzone
9/16/2014	703	0.88	156.60	698	14	14	8	0.49	-0.30	-23.87	33.83	MWD	Payzone
9/16/2014	733	0.97	151.63	728	13	13	8	0.40	0.30	-16.57	34.31	MWD	Payzone
9/16/2014	763	0.85	139.23	758	13	13	8	0.77	-0.40	-41.33	34.78	MWD	Payzone
9/16/2014	793	0.75	120.96	788	13	12	8	0.91	-0.33	-60.90	35.20	MWD	Payzone
9/16/2014	823	0.83	113.88	818	13	12	9	0.42	0.27	-23.60	35.61	MWD	Payzone
9/16/2014	853	0.97	94.59	848	12	12	9	1.11	0.47	-64.30	36.07	MWD	Payzone
9/16/2014	883	1.05	94.24	878	12	12	10	0.27	0.27	-1.17	36.60	MWD	Payzone
9/16/2014	913	1.27	87.92	908	12	12	10	0.85	0.73	-21.07	37.21	MWD	Payzone
9/16/2014	943	1.71	89.36	938	12	12	11	1.47	1.47	4.80	37.99	MWD	Payzone
9/17/2014	973	1.80	93.93	968	12	12	12	0.55	0.30	15.23	38.91	MWD	Payzone
9/17/2014	1,003	1.89	97.71	998	12	12	13	0.50	0.30	12.60	39.87	MWD	Payzone
9/17/2014	1,033	1.76	94.81	1,028	12	12	14	0.53	-0.43	-9.67	40.83	MWD	Payzone
9/17/2014	1,063	1.36	88.57	1,058	12	12	15	1.45	-1.33	-20.80	41.64	MWD	Payzone
9/17/2014	1,093	1.54	91.21	1,088	12	12	16	0.64	0.60	8.80	42.40	MWD	Payzone
9/17/2014	1,123	1.45	86.20	1,118	12	12	16	0.53	-0.30	-16.70	43.18	MWD	Payzone
9/17/2014	1,153	1.54	80.53	1,148	13	12	17	0.58	0.30	-18.90	43.97	MWD	Payzone
9/17/2014	1,183	1.14	87.38	1,178	13	12	18	1.43	-1.33	22.83	44.67	MWD	Payzone
9/17/2014	1,213	1.01	68.44	1,208	13	12	18	1.25	-0.43	-63.13	45.22	MWD	Payzone
9/17/2014	1,243	0.83	64.80	1,238	13	12	19	0.63	-0.60	-12.13	45.70	MWD	Payzone
9/17/2014	1,273	0.79	85.58	1,268	13	12	19	0.98	-0.13	69.27	46.12	MWD	Payzone
9/17/2014	1,303	0.70	74.64	1,298	13	12	20	0.56	-0.30	-36.47	46.51	MWD	Payzone
9/17/2014	1,333	0.69	77.11	1,328	13	13	20	0.11	-0.03	8.23	46.87	MWD	Payzone
9/17/2014	1,363	0.40	80.62	1,358	13	13	20	0.97	-0.97	11.70	47.16	MWD	Payzone
9/17/2014	1,393	0.66	86.11	1,388	13	13	21	0.88	0.87	18.30	47.44	MWD	Payzone
9/17/2014	1,423	0.70	73.67	1,418	13	13	21	0.51	0.13	-41.47	47.79	MWD	Payzone
9/17/2014	1,453	0.79	99.12	1,448	13	13	21	1.13	0.30	84.83	48.17	MWD	Payzone
9/17/2014	1,483	0.53	102.02	1,478	13	13	22	0.87	-0.87	9.67	48.52	MWD	Payzone

NEWFIELD

Directional Survey



Legal Well Name Powwitch 15-13-12-3-2WB				Wellbore Name Original Hole					
API/UWI 43013519420000		Surface Legal Location NWNE 75FNL 2332FEL SEC24 T3S R2W MERU		Field Name UINTA CB - BAR F HORZ		Well Type Development		Well Configuration Type Horizontal	
Well RC 500358785		County Duchesne	State/Province Utah		Spud Date 9/21/2014 06:00		Final Rig Release Date 10/28/2014 00:00		

Survey Data

Date	MD (ftKB)	Incl (°)	Azm (°)	TVD (ftKB)	VS (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Build (°/100ft)	Turn (°/100ft)	Unwrap Displace (ft)	Method	Survey Company
9/17/2014	1,513	1.05	104.08	1,508	13	13	22	1.74	1.73	6.87	48.93	MWD	Payzone
9/17/2014	1,543	1.23	99.42	1,538	13	12	23	0.67	0.60	-15.53	49.52	MWD	Payzone
9/17/2014	1,573	1.36	97.53	1,568	13	12	23	0.46	0.43	-6.30	50.20	MWD	Payzone
9/17/2014	1,586	1.23	90.99	1,581	13	12	24	1.51	-1.00	-50.31	50.50	MWD	Payzone
9/27/2014	1,707	1.72	96.88	1,702	13	12	27	0.42	0.40	4.87	53.61	MWD	Weatherford
9/27/2014	1,770	1.98	91.26	1,765	13	12	29	0.50	0.41	-8.92	55.64	MWD	Weatherford
9/27/2014	1,864	2.05	96.50	1,859	13	12	32	0.21	0.07	5.57	58.94	MWD	Weatherford
9/27/2014	1,959	2.22	92.93	1,954	13	11	36	0.23	0.18	-3.76	62.48	MWD	Weatherford
9/27/2014	2,053	2.14	98.87	2,048	12	11	39	0.25	-0.09	6.32	66.05	MWD	Weatherford
9/27/2014	2,147	2.22	100.16	2,142	12	11	43	0.10	0.09	1.37	69.62	MWD	Weatherford
9/27/2014	2,242	2.07	96.11	2,237	12	10	46	0.22	-0.16	-4.26	73.18	MWD	Weatherford
9/27/2014	2,336	2.01	96.81	2,331	11	10	49	0.07	-0.06	0.74	76.52	MWD	Weatherford
9/27/2014	2,431	1.94	92.75	2,426	11	9	53	0.16	-0.07	-4.27	79.80	MWD	Weatherford
9/27/2014	2,525	2.03	92.66	2,520	11	9	56	0.10	0.10	-0.10	83.05	MWD	Weatherford
9/27/2014	2,619	1.96	92.81	2,614	11	9	59	0.07	-0.07	0.16	86.32	MWD	Weatherford
9/28/2014	2,714	2.01	87.52	2,709	11	9	63	0.20	0.05	-5.57	89.61	MWD	Weatherford
9/28/2014	2,808	2.06	90.68	2,803	11	9	66	0.13	0.05	3.36	92.95	MWD	Weatherford
9/28/2014	2,903	2.02	92.14	2,897	11	9	69	0.07	-0.04	1.54	96.33	MWD	Weatherford
9/28/2014	2,998	1.79	92.33	2,992	11	9	72	0.24	-0.24	0.20	99.49	MWD	Weatherford
9/28/2014	3,092	1.74	91.46	3,086	11	9	75	0.06	-0.05	-0.93	102.38	MWD	Weatherford
9/28/2014	3,187	1.12	94.91	3,181	11	9	78	0.66	-0.65	3.63	104.75	MWD	Weatherford
9/28/2014	3,281	0.74	105.65	3,275	11	8	79	0.44	-0.40	11.43	106.27	MWD	Weatherford
9/28/2014	3,376	0.62	67.43	3,370	11	8	80	0.48	-0.13	-40.23	107.34	MWD	Weatherford
9/28/2014	3,469	0.39	103.38	3,463	11	9	81	0.41	-0.25	38.66	108.12	MWD	Weatherford
9/28/2014	3,564	0.78	92.55	3,558	11	8	82	0.42	0.41	-11.40	109.08	MWD	Weatherford
9/28/2014	3,658	0.46	134.15	3,652	11	8	83	0.57	-0.34	44.26	110.04	MWD	Weatherford
9/28/2014	3,753	0.68	163.45	3,747	10	7	83	0.38	0.23	30.84	110.96	MWD	Weatherford
9/28/2014	3,847	0.79	165.59	3,841	9	6	84	0.12	0.12	2.28	112.16	MWD	Weatherford
9/28/2014	3,941	1.23	177.92	3,935	8	5	84	0.52	0.47	13.12	113.81	MWD	Weatherford
9/28/2014	4,036	1.49	175.79	4,030	5	2	84	0.28	0.27	-2.24	116.06	MWD	Weatherford
9/28/2014	4,130	1.62	186.02	4,124	3	0	84	0.33	0.14	10.88	118.60	MWD	Weatherford
9/28/2014	4,225	1.96	186.60	4,219	0	-3	84	0.36	0.36	0.61	121.57	MWD	Weatherford
9/28/2014	4,319	1.92	188.86	4,313	-3	-6	83	0.09	-0.04	2.40	124.75	MWD	Weatherford
9/28/2014	4,414	2.17	182.73	4,408	-7	-10	83	0.35	0.26	-6.45	128.14	MWD	Weatherford
9/28/2014	4,508	2.36	186.23	4,502	-10	-13	83	0.25	0.20	3.72	131.85	MWD	Weatherford
9/28/2014	4,602	2.54	190.49	4,596	-14	-17	82	0.27	0.19	4.53	135.87	MWD	Weatherford
9/29/2014	4,697	2.88	186.57	4,691	-19	-22	81	0.41	0.36	-4.13	140.36	MWD	Weatherford
9/28/2014	4,789	3.55	186.54	4,783	-24	-27	81	0.73	0.73	-0.03	145.52	MWD	Weatherford
9/28/2014	4,883	3.89	173.60	4,876	-30	-33	81	0.96	0.36	-13.77	151.58	MWD	Weatherford
9/28/2014	4,978	4.31	148.44	4,971	-36	-39	83	1.93	0.44	-26.48	158.21	MWD	Weatherford
9/30/2014	5,072	4.45	130.11	5,065	-41	-45	88	1.49	0.15	-19.50	165.29	MWD	Weatherford
9/30/2014	5,167	4.29	106.30	5,160	-45	-48	94	1.90	-0.17	-25.06	172.38	MWD	Weatherford
9/30/2014	5,261	4.07	102.68	5,253	-46	-50	100	0.37	-0.23	-3.85	179.23	MWD	Weatherford
9/30/2014	5,355	4.76	95.21	5,347	-47	-51	108	0.95	0.73	-7.95	186.45	MWD	Weatherford
9/30/2014	5,450	5.28	92.29	5,442	-47	-51	116	0.61	0.55	-3.07	194.76	MWD	Weatherford
9/30/2014	5,544	5.65	87.90	5,535	-47	-51	125	0.59	0.39	-4.67	203.70	MWD	Weatherford
10/1/2014	5,639	6.20	84.61	5,630	-46	-51	135	0.68	0.58	-3.46	213.50	MWD	Weatherford
10/1/2014	5,733	5.63	84.55	5,723	-45	-50	144	0.61	-0.61	-0.06	223.19	MWD	Weatherford
10/1/2014	5,828	6.52	89.48	5,818	-44	-49	154	1.09	0.94	5.19	233.24	MWD	Weatherford
10/1/2014	6,017	5.17	88.81	6,006	-43	-49	174	0.72	-0.71	-0.35	252.48	MWD	Weatherford
10/1/2014	6,110	5.15	96.16	6,098	-43	-49	182	0.71	-0.02	7.90	260.83	MWD	Weatherford
10/2/2014	6,204	5.54	95.82	6,192	-43	-50	191	0.42	0.41	-0.36	269.59	MWD	Weatherford
10/2/2014	6,298	6.13	96.47	6,286	-44	-51	200	0.63	0.63	0.69	279.14	MWD	Weatherford

NEWFIELD**Directional Survey**

Legal Well Name Powitch 15-13-12-3-2WB				Wellbore Name Original Hole					
API/UWI 43013519420000		Surface Legal Location NWNE 75FNL 2332FEL SEC24 T3S R2W MERU		Field Name UINTA CB - BAR F HORZ		Well Type Development		Well Configuration Type Horizontal	
Well RC 500358785		County Duchesne		State/Province Utah		Spud Date 9/21/2014 06:00		Final Rig Release Date 10/28/2014 00:00	

Survey Data

Date	MD (ftKB)	Incl (°)	Azm (°)	TVD (ftKB)	VS (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Build (°/100ft)	Turn (°/100ft)	Unwrap Displace (ft)	Method	Survey Company
10/2/2014	6,392	6.98	93.71	6,379	-45	-52	211	0.96	0.90	-2.94	289.87	MWD	Weatherford
10/3/2014	6,479	6.56	97.57	6,465	-45	-53	221	0.71	-0.48	4.44	300.12	MWD	Weatherford
10/3/2014	6,572	6.20	99.86	6,558	-47	-55	231	0.47	-0.39	2.46	310.45	MWD	Weatherford
10/3/2014	6,667	5.61	102.59	6,652	-48	-57	241	0.69	-0.62	2.87	320.22	MWD	Weatherford
10/3/2014	6,761	4.88	100.65	6,746	-50	-58	249	0.80	-0.78	-2.06	328.81	MWD	Weatherford
10/3/2014	6,856	5.90	95.83	6,840	-50	-60	258	1.17	1.07	-5.07	337.73	MWD	Weatherford
10/4/2014	6,950	6.80	94.47	6,934	-51	-61	268	0.97	0.96	-1.45	348.13	MWD	Weatherford
10/4/2014	7,045	7.66	77.78	7,028	-50	-60	280	2.38	0.91	-17.57	359.96	MWD	Weatherford
10/4/2014	7,071	8.48	70.14	7,054	-49	-59	284	5.19	3.15	-29.38	363.60	MWD	Weatherford
10/4/2014	7,107	9.36	66.32	7,089	-46	-57	289	2.95	2.44	-10.61	369.18	MWD	Weatherford
10/4/2014	7,138	10.57	62.52	7,120	-44	-54	294	4.44	3.90	-12.26	374.54	MWD	Weatherford
10/4/2014	7,170	11.77	59.48	7,151	-41	-51	299	4.18	3.75	-9.50	380.74	MWD	Weatherford
10/4/2014	7,202	12.93	54.27	7,183	-37	-47	305	5.02	3.63	-16.28	387.57	MWD	Weatherford
10/4/2014	7,233	14.08	51.17	7,213	-32	-43	311	4.38	3.71	-10.00	394.81	MWD	Weatherford
10/4/2014	7,265	15.48	47.46	7,244	-26	-38	317	5.28	4.38	-11.59	402.97	MWD	Weatherford
10/4/2014	7,296	16.89	42.86	7,273	-20	-32	323	6.14	4.55	-14.84	411.60	MWD	Weatherford
10/4/2014	7,327	17.70	38.25	7,303	-13	-25	329	5.13	2.61	-14.87	420.81	MWD	Weatherford
10/5/2014	7,359	18.42	33.93	7,333	-5	-17	335	4.75	2.25	-13.50	430.73	MWD	Weatherford
10/5/2014	7,390	19.32	31.72	7,363	4	-8	340	3.71	2.90	-7.13	440.75	MWD	Weatherford
10/5/2014	7,422	20.08	28.78	7,393	13	1	345	3.90	2.38	-9.19	451.53	MWD	Weatherford
10/5/2014	7,453	20.97	25.84	7,422	23	11	350	4.39	2.87	-9.48	462.40	MWD	Weatherford
10/5/2014	7,485	22.09	23.80	7,452	34	21	355	4.21	3.50	-6.38	474.14	MWD	Weatherford
10/5/2014	7,516	23.46	22.15	7,480	45	32	360	4.88	4.42	-5.32	486.14	MWD	Weatherford
10/5/2014	7,547	25.27	20.81	7,509	57	44	365	6.10	5.84	-4.32	498.93	MWD	Weatherford
10/5/2014	7,579	27.08	20.09	7,537	71	58	370	5.74	5.66	-2.25	513.04	MWD	Weatherford
10/5/2014	7,610	28.82	18.98	7,565	85	71	375	5.86	5.61	-3.58	527.57	MWD	Weatherford
10/5/2014	7,642	29.88	17.38	7,593	100	86	379	4.12	3.31	-5.00	543.26	MWD	Weatherford
10/5/2014	7,673	30.85	16.65	7,619	115	101	384	3.35	3.13	-2.35	558.93	MWD	Weatherford
10/6/2014	7,705	31.43	15.93	7,647	131	117	389	2.15	1.81	-2.25	575.47	MWD	Weatherford
10/6/2014	7,736	32.41	14.83	7,673	147	133	393	3.68	3.16	-3.55	591.86	MWD	Weatherford
10/6/2014	7,768	33.22	14.62	7,700	164	150	397	2.56	2.53	-0.66	609.20	MWD	Weatherford
10/6/2014	7,799	34.57	14.26	7,726	181	166	402	4.40	4.35	-1.16	626.49	MWD	Weatherford
10/6/2014	7,831	36.17	14.11	7,752	199	184	406	5.01	5.00	-0.47	645.02	MWD	Weatherford
10/6/2014	7,854	37.99	14.21	7,770	212	198	410	7.92	7.91	0.43	658.88	MWD	Weatherford
10/6/2014	7,893	39.49	14.62	7,801	236	221	416	3.90	3.85	1.05	683.29	MWD	Weatherford
10/6/2014	7,925	41.70	14.95	7,825	256	242	421	6.94	6.91	1.03	704.11	MWD	Weatherford
10/6/2014	7,962	43.22	15.26	7,852	281	266	428	4.15	4.11	0.84	729.08	MWD	Weatherford
10/11/2014	8,060	47.68	18.11	7,921	348	333	448	5.00	4.55	2.91	798.89	MWD	Weatherford
10/11/2014	8,091	48.00	18.75	7,942	370	354	455	1.85	1.03	2.06	821.87	MWD	Weatherford
10/11/2014	8,122	48.87	18.70	7,962	392	376	462	2.81	2.81	-0.16	845.06	MWD	Weatherford
10/11/2014	8,154	52.55	17.16	7,982	416	400	470	12.09	11.50	-4.81	869.83	MWD	Weatherford
10/11/2014	8,185	55.40	15.66	8,001	441	424	477	9.99	9.19	-4.84	894.89	MWD	Weatherford
10/11/2014	8,217	57.39	14.08	8,018	467	450	484	7.46	6.22	-4.94	921.54	MWD	Weatherford
10/11/2014	8,248	59.89	11.55	8,035	493	475	490	10.66	8.06	-8.16	948.01	MWD	Weatherford
10/11/2014	8,280	62.57	9.26	8,050	520	503	495	10.46	8.38	-7.16	976.05	MWD	Weatherford
10/11/2014	8,311	64.97	7.00	8,064	548	531	499	10.13	7.74	-7.29	1,003.86	MWD	Weatherford

NEWFIELD**Directional Survey**

Legal Well Name Powwitch 15-13-12-3-2WB				Wellbore Name Original Hole					
API/UWI 43013519420000		Surface Legal Location NWNE 75FNL 2332FEL SEC24 T3S R2W MERU		Field Name UINTA CB - BAR F HORZ		Well Type Development		Well Configuration Type Horizontal	
Well RC 500358785		County Duchesne		State/Province Utah		Spud Date 9/21/2014 06:00		Final Rig Release Date 10/28/2014 00:00	

Survey Data

Date	MD (ftKB)	Incl (°)	Azm (°)	TVD (ftKB)	VS (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Build (°/100ft)	Turn (°/100ft)	Unwrap Displace (ft)	Method	Survey Company
10/11/2014	8,343	67.00	3.47	8,077	577	560	501	11.91	6.34	-11.03	1,033.08	MWD	Weatherford
10/11/2014	8,374	68.14	0.21	8,089	606	588	502	10.39	3.68	-10.52	1,061.73	MWD	Weatherford
10/11/2014	8,406	69.41	359.32	8,100	636	618	502	4.74	3.97	1122.22	1,091.56	MWD	Weatherford
10/11/2014	8,437	71.31	358.90	8,111	665	647	502	6.26	6.13	-1.35	1,120.75	MWD	Weatherford
10/11/2014	8,469	73.57	358.94	8,120	695	678	501	7.06	7.06	0.13	1,151.26	MWD	Weatherford
10/11/2014	8,500	75.04	358.74	8,129	725	708	501	4.78	4.74	-0.65	1,181.10	MWD	Weatherford
10/11/2014	8,532	76.70	358.83	8,136	756	739	500	5.19	5.19	0.28	1,212.13	MWD	Weatherford
10/11/2014	8,563	78.71	358.34	8,143	786	769	499	6.67	6.48	-1.58	1,242.42	MWD	Weatherford
10/11/2014	8,595	80.65	357.58	8,149	818	800	498	6.50	6.06	-2.37	1,273.90	MWD	Weatherford
10/11/2014	8,626	82.39	357.19	8,153	848	831	497	5.75	5.61	-1.26	1,304.56	MWD	Weatherford
10/11/2014	8,657	84.07	357.31	8,157	879	862	495	5.43	5.42	0.39	1,335.34	MWD	Weatherford
10/11/2014	8,689	85.80	356.60	8,160	911	894	493	5.84	5.41	-2.22	1,367.22	MWD	Weatherford
10/11/2014	8,720	86.98	356.02	8,162	941	924	491	4.24	3.81	-1.87	1,398.15	MWD	Weatherford
10/11/2014	8,783	86.85	355.35	8,165	1,004	987	487	1.08	-0.21	-1.06	1,461.06	MWD	Weatherford
10/11/2014	8,873	87.16	354.43	8,170	1,093	1,077	479	1.08	0.34	-1.02	1,550.94	MWD	Weatherford
10/13/2014	8,917	87.53	354.26	8,172	1,137	1,120	474	0.93	0.84	-0.39	1,594.89	MWD	Weatherford
10/13/2014	9,011	87.47	354.60	8,176	1,230	1,214	465	0.37	-0.06	0.36	1,688.80	MWD	Weatherford
10/13/2014	9,106	86.05	354.22	8,181	1,324	1,308	456	1.55	-1.49	-0.40	1,783.65	MWD	Weatherford
10/13/2014	9,200	86.17	356.54	8,188	1,417	1,402	448	2.47	0.13	2.47	1,877.42	MWD	Weatherford
10/13/2014	9,295	87.72	358.97	8,193	1,511	1,497	445	3.03	1.63	2.56	1,972.28	MWD	Weatherford
10/13/2014	9,389	88.58	359.23	8,196	1,605	1,591	443	0.96	0.91	0.28	2,066.23	MWD	Weatherford
10/13/2014	9,484	89.32	356.85	8,198	1,700	1,685	440	2.62	0.78	-2.51	2,161.21	MWD	Weatherford
10/13/2014	9,578	88.83	354.61	8,199	1,793	1,779	433	2.44	-0.52	-2.38	2,255.19	MWD	Weatherford
10/14/2014	9,673	89.08	352.70	8,201	1,887	1,874	423	2.03	0.26	-2.01	2,350.17	MWD	Weatherford
10/14/2014	9,767	89.14	355.18	8,202	1,980	1,967	413	2.64	0.06	2.64	2,444.15	MWD	Weatherford
10/14/2014	9,861	88.52	354.43	8,204	2,074	2,061	404	1.04	-0.66	-0.80	2,538.13	MWD	Weatherford
10/14/2014	9,956	87.60	353.15	8,207	2,168	2,155	394	1.66	-0.97	-1.35	2,633.07	MWD	Weatherford
10/14/2014	10,050	87.36	349.36	8,211	2,260	2,248	380	4.04	-0.26	-4.03	2,726.96	MWD	Weatherford
10/14/2014	10,144	87.47	349.42	8,216	2,351	2,340	362	0.13	0.12	0.06	2,820.87	MWD	Weatherford

NEWFIELD

Directional Survey



Legal Well Name Powitch 15-13-12-3-2WB				Wellbore Name Original Hole					
API/UWI 43013519420000		Surface Legal Location NWNE 75FNL 2332FEL SEC24 T3S R2W MERU		Field Name UINTA CB - BAR F HORZ		Well Type Development		Well Configuration Type Horizontal	
Well RC 500358785		County Duchesne		State/Province Utah		Spud Date 9/21/2014 06:00		Final Rig Release Date 10/28/2014 00:00	

Survey Data

Date	MD (ftKB)	Incl (°)	Azm (°)	TVD (ftKB)	VS (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Build (°/100ft)	Turn (°/100ft)	Unwrap Displace (ft)	Method	Survey Company
10/14/2014	10,239	87.66	353.39	8,220	2,445	2,434	348	4.18	0.20	4.18	2,915.76	MWD	Weatherford
10/14/2014	10,333	87.66	354.22	8,224	2,538	2,527	338	0.88	0.00	0.88	3,009.68	MWD	Weatherford
10/14/2014	10,428	87.72	354.37	8,227	2,632	2,622	329	0.17	0.06	0.16	3,104.61	MWD	Weatherford
10/14/2014	10,522	88.95	357.63	8,230	2,725	2,715	322	3.71	1.31	3.47	3,198.55	MWD	Weatherford
10/14/2014	10,616	89.26	359.73	8,232	2,819	2,809	320	2.26	0.33	2.23	3,292.53	MWD	Weatherford
10/14/2014	10,711	89.38	359.01	8,233	2,914	2,904	319	0.77	0.13	-0.76	3,387.53	MWD	Weatherford
10/14/2014	10,805	88.95	359.37	8,234	3,008	2,998	317	0.60	-0.46	0.38	3,481.52	MWD	Weatherford
10/15/2014	10,900	87.41	359.88	8,237	3,103	3,093	317	1.71	-1.62	0.54	3,576.47	MWD	Weatherford
10/15/2014	10,994	88.83	2.76	8,240	3,197	3,187	319	3.41	1.51	-379.91	3,670.40	MWD	Weatherford
10/15/2014	11,088	88.64	2.09	8,242	3,291	3,281	323	0.74	-0.20	-0.71	3,764.38	MWD	Weatherford
10/15/2014	11,183	88.52	0.46	8,245	3,386	3,376	325	1.72	-0.13	-1.72	3,859.35	MWD	Weatherford
10/15/2014	11,277	87.78	0.96	8,248	3,479	3,470	326	0.95	-0.79	0.53	3,953.30	MWD	Weatherford
10/15/2014	11,371	87.84	359.09	8,251	3,573	3,564	326	1.99	0.06	380.99	4,047.22	MWD	Weatherford
10/15/2014	11,466	88.46	6.93	8,254	3,668	3,659	331	8.27	0.65	-370.69	4,142.10	MWD	Weatherford
10/15/2014	11,561	88.09	5.75	8,257	3,763	3,753	342	1.30	-0.39	-1.24	4,237.05	MWD	Weatherford
10/16/2014	11,655	89.01	5.11	8,260	3,857	3,847	351	1.19	0.98	-0.68	4,331.02	MWD	Weatherford
10/16/2014	11,749	87.41	2.62	8,263	3,951	3,940	357	3.15	-1.70	-2.65	4,424.97	MWD	Weatherford
10/16/2014	11,844	86.98	4.67	8,267	4,045	4,035	363	2.20	-0.45	2.16	4,519.85	MWD	Weatherford
10/16/2014	11,938	86.85	1.79	8,272	4,139	4,129	368	3.06	-0.14	-3.06	4,613.70	MWD	Weatherford
10/16/2014	12,033	87.16	2.49	8,277	4,234	4,224	372	0.80	0.33	0.74	4,708.57	MWD	Weatherford
10/16/2014	12,127	86.73	0.68	8,282	4,328	4,317	374	1.98	-0.46	-1.93	4,802.43	MWD	Weatherford
10/16/2014	12,221	88.89	0.57	8,286	4,422	4,411	375	2.30	2.30	-0.12	4,896.36	MWD	Weatherford
10/16/2014	12,316	89.38	3.55	8,287	4,517	4,506	379	3.18	0.52	3.14	4,991.34	MWD	Weatherford
10/16/2014	12,410	87.66	357.99	8,290	4,611	4,600	380	6.19	-1.83	377.06	5,085.27	MWD	Weatherford
10/16/2014	12,505	87.60	355.63	8,294	4,705	4,695	375	2.48	-0.06	-2.48	5,180.18	MWD	Weatherford
10/16/2014	12,599	88.21	355.15	8,297	4,799	4,789	367	0.83	0.65	-0.51	5,274.11	MWD	Weatherford
10/16/2014	12,693	87.47	354.23	8,301	4,892	4,882	359	1.26	-0.79	-0.98	5,368.05	MWD	Weatherford
10/16/2014	12,788	86.73	356.40	8,305	4,986	4,977	351	2.41	-0.78	2.28	5,462.92	MWD	Weatherford
10/17/2014	12,882	85.31	356.27	8,312	5,079	5,070	345	1.52	-1.51	-0.14	5,556.69	MWD	Weatherford

NEWFIELD

Directional Survey



Legal Well Name Powitch 15-13-12-3-2WB				Wellbore Name Original Hole					
API/UWI 43013519420000		Surface Legal Location NWNE 75FNL 2332FEL SEC24 T3S R2W MERU		Field Name UINTA CB - BAR F HORZ		Well Type Development		Well Configuration Type Horizontal	
Well RC 500358785		County Duchesne	State/Province Utah		Spud Date 9/21/2014 06:00		Final Rig Release Date 10/28/2014 00:00		

Survey Data

Date	MD (ftKB)	Incl (°)	Azm (°)	TVD (ftKB)	VS (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Build (°/100ft)	Turn (°/100ft)	Unwrap Displace (ft)	Method	Survey Company
10/17/2014	12,977	86.67	356.97	8,319	5,174	5,165	339	1.61	1.43	0.74	5,651.45	MWD	Weatherford
10/17/2014	13,071	87.35	357.55	8,323	5,267	5,259	335	0.95	0.72	0.62	5,745.32	MWD	Weatherford
10/17/2014	13,166	87.59	357.74	8,328	5,362	5,353	331	0.32	0.25	0.20	5,840.23	MWD	Weatherford
10/17/2014	13,260	88.15	357.50	8,331	5,455	5,447	327	0.65	0.60	-0.26	5,934.17	MWD	Weatherford
10/17/2014	13,355	88.52	356.83	8,334	5,550	5,542	322	0.81	0.39	-0.71	6,029.12	MWD	Weatherford
10/17/2014	13,544	88.24	2.58	8,339	5,739	5,731	321	3.04	-0.15	-187.43	6,217.97	MWD	Weatherford
10/17/2014	13,638	87.90	2.37	8,342	5,833	5,825	325	0.43	-0.36	-0.22	6,311.92	MWD	Weatherford
10/18/2014	13,732	87.84	2.50	8,346	5,927	5,919	329	0.15	-0.06	0.14	6,405.85	MWD	Weatherford
10/18/2014	13,826	87.47	1.38	8,350	6,021	6,013	333	1.25	-0.39	-1.19	6,499.77	MWD	Weatherford
10/18/2014	13,921	88.52	0.65	8,353	6,115	6,107	334	1.35	1.11	-0.77	6,594.71	MWD	Weatherford
10/18/2014	14,015	88.58	0.59	8,355	6,209	6,201	335	0.09	0.06	-0.06	6,688.68	MWD	Weatherford
10/18/2014	14,109	87.53	1.17	8,359	6,303	6,295	337	1.28	-1.12	0.62	6,782.62	MWD	Weatherford
10/18/2014	14,204	87.53	1.65	8,363	6,398	6,390	339	0.50	0.00	0.51	6,877.54	MWD	Weatherford
10/18/2014	14,298	86.55	0.59	8,368	6,492	6,484	341	1.53	-1.04	-1.13	6,971.41	MWD	Weatherford
10/18/2014	14,393	87.23	0.43	8,373	6,587	6,579	342	0.74	0.72	-0.17	7,066.27	MWD	Weatherford
10/18/2014	14,487	87.66	0.29	8,377	6,681	6,673	342	0.48	0.46	-0.15	7,160.17	MWD	Weatherford
10/18/2014	14,582	88.06	1.17	8,381	6,776	6,768	344	1.02	0.42	0.93	7,255.11	MWD	Weatherford
10/18/2014	14,676	87.96	1.17	8,384	6,870	6,862	345	0.11	-0.11	0.00	7,349.05	MWD	Weatherford
10/18/2014	14,771	87.90	0.95	8,387	6,965	6,957	347	0.24	-0.06	-0.23	7,443.99	MWD	Weatherford
10/18/2014	14,866	87.90	0.15	8,391	7,059	7,052	348	0.84	0.00	-0.84	7,538.92	MWD	Weatherford
10/18/2014	14,960	87.96	359.87	8,394	7,153	7,145	348	0.30	0.06	382.68	7,632.86	MWD	Weatherford
10/18/2014	15,054	88.09	0.23	8,397	7,247	7,239	348	0.41	0.14	-382.60	7,726.81	MWD	Weatherford
10/19/2014	15,149	87.90	0.59	8,401	7,342	7,334	349	0.43	-0.20	0.38	7,821.75	MWD	Weatherford
10/19/2014	15,243	87.84	0.38	8,404	7,436	7,428	350	0.23	-0.06	-0.22	7,915.68	MWD	Weatherford
10/19/2014	15,338	87.90	0.44	8,408	7,531	7,523	350	0.09	0.06	0.06	8,010.62	MWD	Weatherford
10/19/2014	15,432	87.96	358.88	8,411	7,625	7,617	350	1.66	0.06	381.32	8,104.55	MWD	Weatherford
10/19/2014	15,527	88.24	358.17	8,414	7,720	7,712	347	0.80	0.29	-0.75	8,199.50	MWD	Weatherford
10/19/2014	15,622	88.64	358.79	8,417	7,814	7,807	345	0.78	0.42	0.65	8,294.46	MWD	Weatherford
10/19/2014	15,716	89.01	0.52	8,419	7,908	7,901	344	1.88	0.39	-381.14	8,388.44	MWD	Weatherford

NEWFIELD**Directional Survey**

Legal Well Name Powvitch 15-13-12-3-2WB				Wellbore Name Original Hole					
API/UWI 43013519420000		Surface Legal Location NWNE 75FNL 2332FEL SEC24 T3S R2W MERU		Field Name UINTA CB - BAR F HORZ		Well Type Development		Well Configuration Type Horizontal	
Well RC 500358785		County Duchesne		State/Province Utah		Spud Date 9/21/2014 06:00		Final Rig Release Date 10/28/2014 00:00	

Survey Data

Date	MD (ftKB)	Incl (°)	Azm (°)	TVD (ftKB)	VS (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Build (°/100ft)	Turn (°/100ft)	Unwrap Displace (ft)	Method	Survey Company
10/19/2014	15,811	87.59	359.48	8,422	8,003	7,996	344	1.85	-1.49	377.85	8,483.39	MWD	Weatherford
10/20/2014	15,905	86.23	359.21	8,427	8,097	8,090	343	1.47	-1.45	-0.29	8,577.26	MWD	Weatherford
10/20/2014	16,000	85.31	0.93	8,434	8,192	8,185	343	2.05	-0.97	-377.14	8,671.99	MWD	Weatherford
10/20/2014	16,094	86.48	4.10	8,440	8,285	8,278	347	3.59	1.24	3.37	8,765.74	MWD	Weatherford
10/20/2014	16,188	85.99	6.15	8,447	8,379	8,372	356	2.24	-0.52	2.18	8,859.53	MWD	Weatherford
10/20/2014	16,283	85.68	4.26	8,453	8,474	8,466	364	2.01	-0.33	-1.99	8,954.27	MWD	Weatherford
10/20/2014	16,377	85.38	1.37	8,461	8,567	8,560	369	3.08	-0.32	-3.07	9,047.98	MWD	Weatherford
10/20/2014	16,471	85.62	1.09	8,468	8,661	8,653	371	0.39	0.26	-0.30	9,141.69	MWD	Weatherford
10/20/2014	16,566	85.43	1.61	8,476	8,756	8,748	373	0.58	-0.20	0.55	9,236.40	MWD	Weatherford
10/20/2014	16,660	85.55	359.36	8,483	8,849	8,842	374	2.39	0.13	380.59	9,330.10	MWD	Weatherford
10/21/2014	16,755	85.24	359.40	8,491	8,944	8,936	373	0.33	-0.33	0.04	9,424.79	MWD	Weatherford
10/21/2014	16,849	85.24	359.76	8,498	9,037	9,030	372	0.38	0.00	0.38	9,518.47	MWD	Weatherford
10/21/2014	16,943	87.96	1.23	8,504	9,131	9,124	373	3.29	2.89	-381.41	9,612.29	MWD	Weatherford
10/21/2014	17,037	84.13	358.82	8,510	9,225	9,218	373	4.81	-4.07	380.41	9,706.04	MWD	Weatherford
10/21/2014	17,132	84.26	0.81	8,520	9,319	9,312	373	2.09	0.14	-376.85	9,800.55	MWD	Weatherford
10/21/2014	17,226	85.99	3.32	8,528	9,413	9,406	376	3.23	1.84	2.67	9,894.20	MWD	Weatherford
10/21/2014	17,321	86.30	1.13	8,534	9,508	9,500	380	2.32	0.33	-2.31	9,988.98	MWD	Weatherford
10/21/2014	17,415	87.10	0.23	8,540	9,602	9,594	381	1.28	0.85	-0.96	10,082.82	MWD	Weatherford
10/21/2014	17,509	86.73	360.00	8,545	9,695	9,688	381	0.46	-0.39	382.73	10,176.69	MWD	Weatherford
10/21/2014	17,604	86.11	359.18	8,551	9,790	9,783	381	1.08	-0.65	-0.86	10,271.50	MWD	Weatherford
10/22/2014	17,698	85.55	356.02	8,558	9,884	9,877	377	3.41	-0.60	-3.36	10,365.24	MWD	Weatherford
10/22/2014	17,793	85.56	353.51	8,565	9,978	9,971	368	2.63	0.01	-2.64	10,459.95	MWD	Weatherford
10/22/2014	17,888	85.33	353.76	8,573	10,071	10,065	357	0.36	-0.24	0.26	10,554.65	MWD	Weatherford

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Job Category	Job Start Date	Job End Date

Daily Operations

Report Start Date 11/4/2014	Report End Date 11/5/2014	24hr Activity Summary We are attempting to open RSI toe sleeve. Pinned to 7565psi walked pressure to 9000psi on several attempts to open RSI to no avail. Currently holding 9500psi as per NFX engineer .
Start Time 10:00	End Time 12:30	Comment 10:00 Spot in Halliburton and 11:30 rig up Halliburton
Start Time 12:30	End Time 13:30	Comment Pressure test pumps and lines to 6000 PSI 12:47 Pressure test pump and line Start pumping - pressure up to 720 psi Shut down, reboot computer on Acid pump 12:59 Open HCR Valve and pressure dropped to 0 psi 13:00 Start pumping in with 2 bpm pressure began climbing immediately reduced rate to 1.5 bpm at 4500 psi then reduced rate to 1 bpm at 5500 psi 13:05 Pressured up to 6040 psi and stopped pumping Found a leak on the pump in line and shut in line at 2" manifold and monitor pressure for 30 minutes 13:35 Pressure bleed to 5967 so the total pressure lost was 173 psi 13:37 Bleed pressure of HALLIBURTON line and fix leak on iron then pressure test line to 6000 and open to well. 13:39 Bleed pressure off well back to acid truck 13:44 Close in bleed off
Start Time 13:30	End Time 17:00	Comment Pump in to open RSI / discuss plan to pump in with frac pump at 7.5 bpm 13:45 Start pumping at 7.5 with kicks set at 9000 psi 13:48 Pumps kicked out at 8770 with 10.56 bbls pumped pressure holding at 8750 psi 13:51 Bleed pressure back to truck to 5100 psi 13:54 Start boost and begin pumping (pump in again at same pump settings but rate was not reading) pressure up to 8970 pumps kicked out. Help pressure for 5 minutes 14:00 Bleed pressure to zero 14:06 Close in bleed off start boost and begin pumping at 4.7 bpm pump in 9.5 bbls to pressure up to 9040 psi 14:10 Pressure holding at 9000 psi 14:30 Close in frac iron and open up to B&C test truck 15:38 Pump in at 1/8 bpm bring pressure up to 9500 psi! 15:06 Bumped pressure up to 9800 psi at 1/8 bpm 15:20 Bleed down to 9000 psi washed bleeder valve on test truck, shut in well and bleed off then change bleeder valve and open well up 15:30 Pressure up to 10000 psi 15:58 Bleed pressure off of well 16:04 Start pumping in at 7 bpm with frac pump pressure up to 9130 and stop pumping 16:07 Close in Halliburton iron 16:08 Bump in with B&C test truck at 1/8 bpm from 9130 to 9900 psi 16:12 Hold 9900 psi 16:35 Bumped pressure up to 10,100 Psi with B&C test truck 17:05 bleed pressure off to 0 hold Pressure while decisions are made weather or not to shut down for the night Trouble Shoot Frack Pump (Kicking out before set Kickout pressure)

Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	17:00	End Time	18:30	Comment
				Pickle up pumps and lines with Brine and Rig down Frac pump
				17:10 Rig down DFIT gauges /Trouble shoot frac pump / Drain up and rig down frac pump
				Prime up acid pump with brine water to pickle up pump and lines
				18:03 Begin pumping with Acid pump at 3.8 bpm set kicks at 9000 psi
				18:05 Drop rate to 2.5 bpm
				18:06 Pressured up to 9100 stop pumps
				18:07 Begin pumping at 1/8 bpm with B&C quick test pump to 9500 psi with brine to pickle well head and valves.
				Shut in HCR and bottom frac valve for double barrier then shut inside wing valves and break off HALLIBURTON iron and B&C Quick Test truck
Start Time	18:30	End Time	00:00	Comment
Report Start Date	11/5/2014	Report End Date	11/6/2014	24hr Activity Summary
				Shut down for night / 9500 PSI on well.
Start Time	00:00	End Time	08:00	Comment
				Wait on Daylight
Start Time	08:00	End Time	09:00	Comment
				B&C Quick Test arrived at 08:00 and held PJSM with Location supervisors and then checked pressure on the well (9400 PSI)
				Halliburton called to let us know that they were Delayed by road-side UDOT inspection. (Frac truck Passed DOT Inspection perfectly)
Start Time	09:00	End Time	12:00	Comment
				Rig up Halliburton and Pressure test pump and lines to 9000 then open well to halliburton and Bleed pressure off of well.
				Communicate with Leadership team to make a plan forward.
Start Time	12:00	End Time	14:00	Comment
				Weltech and JW Wireline arrived on location at 12:00
				Hold PJSM with B&C Quick test and JW wireline
				Nippled down 7 1/16 flange on top frac head and remove "Night cap" then Nipple up Wireline lubricator adapter (Wireline crane Broke down and it took JW approxamatly 15 minutes to get a new crane on location so no Downtime was recorded) Rig up crane and begin rigging up Wireline.
Start Time	14:00	End Time	18:00	Comment
				Rig up Wire line and lubricator
				Rig up 5 1/2" 10K lubricator, test 10k with B&C quick test, Pick up Tractor tool with perf gun string
				Tractor string: 22.38
				Gun String:21.96
				Total length:44.34
				Total weight: 755.5 lbs
Start Time	18:00	End Time	00:00	Comment
				RIH with WL tractor and perf guns. Correlate to csg tally at 7719'. RIH and set down at 8575'. Dn wt 870, up wt 1500, static 1340. Pressure csg to 3000 psi. Tractor guns IH at 38 fpm and 940 LTEN. Unable to locate marker jt at 10,495'. Correlate to csg tally at 12,753' and 15,261'.

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Daily Operations

Report Start Date	Report End Date	24hr Activity Summary
11/6/2014	11/7/2014	Tractor perf gun IH.
Start Time	End Time	Comment
00:00	01:00	Tractor perf gun IH. Tag at 17,422'. HES holding 3890 psi on csg. POH and perforate 9 holes at 17,375' to 17378'.
Start Time	End Time	Comment
01:00	04:30	POH running CCL to surf. Correlate to csg tally. All shots fired. All tools recovered. Install night cap on WL BOP. SICP 2800 psi.
Start Time	End Time	Comment
04:30	06:00	Install data traps. Equalize pressure on frac tree and open middle master valve. SICP 2,697 psi. Pump DFIT at 7 bpm. With 12 bbl pumped got a break at 7,648 psi. With 17 bbl pumped got a second break at 8,220 psi. With 23 bbl pumped got a break at 8,605 psi. Pumped 35 bbl with final pressure of 7,838 psi. Last 14 bbl pumped were brine water. ISIP 7,324 psi
Start Time	End Time	Comment
06:00	08:00	Continue DFIT Final Shut in Pressure after 1 Hour is 3084 PSI. / Rig down Wireline, install Night cap and nipple up, Rig down and move out Halliburton, Weltech and JW wireline.
Start Time	End Time	Comment
08:00	17:00	Continue DFIT 09:00 Pressure Gauge 7 = 2930.96 / Pressure gauge 8 = 2930.96 11:00 Pressure Gauge 7 = 2859.12 / Pressure gauge 8 = 2859.12 13:00 Pressure Gauge 7 = 2808.24 / Pressure gauge 8 = 2808.09 15:00 Pressure Gauge 7 = 2757.44 / Pressure gauge 8 = 2757.05 17:00 Pressure Gauge 7 = 2733.92 / Pressure gauge 8 = 2733.64 Select rental delivered Air heater Cardwell Petroleum Delivered fuel Ute Tribal UTERO commission Came to inspect location Weatherford Rigged up Tarp around well head Started Air heater at 16:30
Start Time	End Time	Comment
17:00	00:00	19:00 Pressure Gauge #7 - 2700.79 / Pressure Gauge #8 - 2700.38 21:00 Pressure Gauge #7 - 2672.5 / Pressure Gauge #8 - 2672.14 23:00 Pressure Gauge #7 - 2647.98 / Pressure Gauge #8 - 2647.62
Report Start Date	Report End Date	24hr Activity Summary
11/7/2014	11/8/2014	DFIT
Start Time	End Time	Comment
00:00	00:00	01:00 Pressure Gauge #7 - 2627.11 / Pressure Gauge #8 - 2626.8 03:00 Pressure Gauge #7 - 2608.14 / Pressure Gauge #8 - 2607.73 05:00 Pressure Gauge #7 - 2590.69 / Pressure Gauge #8 - 2590.37 07:00 Pressure Gauge #7 - 2574.46 / Pressure Gauge #8 - 2574.19 15:00 Pressure Gauge #7 - 2522.72 / Pressure Gauge #8 - 2522.32 23:00 Pressure Gauge #7 - 2485.58 / Pressure Gauge #8 - 2485.17
Report Start Date	Report End Date	24hr Activity Summary
11/8/2014	11/9/2014	DFIT
Start Time	End Time	Comment
00:00	00:00	07:00 Current Pressure Gauge 7= 2485.58 / Gauge 8= 2485.17. 15:00 pressure readings Gauge 7= 2429.71 / Gauge 8= 2429.27. 23:00 Gauge 7- 2409.28 / Gauge 8- 2408.88.

Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Daily Operations

Report Start Date	Report End Date	24hr Activity Summary
11/9/2014	11/10/2014	DFIT
Start Time	00:00	End Time 00:00
Comment 7:00 Current Pressure Gauge 7- 2390.51 / Gauge 8- 2390.30. 23:00 Gauge 7- 2362.11 / Gauge 8- 2361.69.		
Report Start Date	Report End Date	24hr Activity Summary
11/10/2014	11/11/2014	DFIT
Start Time	00:00	End Time 00:00
Comment Monitor Pressure and record every 8 Hours / Current Pressure at 07:00 Gauge 7- 2349.94 / Gauge 8- 2349.66 Monitor Pressure and record every 8 Hours / Current Pressure at 15:00 Gauge 7- 2339.87 / Gauge 8- 2338.64 23:00 DFIT pressure-- Gauge 7- 2328.68 / Gauge 8- 2328.33.		
Report Start Date	Report End Date	24hr Activity Summary
11/11/2014	11/12/2014	DFIT
Start Time	00:00	End Time 00:00
Comment Monitor Pressure and record every 8 Hours / Current pressure at 07:00 Gauge 7- 2320.27 / Gauge 8- 2320.33 / Current Pressure at 15:00 Gauge 7- 2312.29 , Gauge 8- 2311.96 23:00--Gauge 7-2304.10/Gauge 8-2303.96		
Report Start Date	Report End Date	24hr Activity Summary
11/12/2014	11/13/2014	DFIT
Start Time	00:00	End Time 00:00
Comment Monitor Pressure and record every 8 Hours / Current pressure at 06:00 Gauge 7-2297.31/Gauge 8-2297.22 / Current Pressure at 15:00 Gauge 7- 2290.89, Gauge 8- 2290.66 23:00 Gauge 7-2280.20/Gauge 8-2280.31		
Report Start Date	Report End Date	24hr Activity Summary
11/13/2014	11/14/2014	DFIT
Start Time	00:00	End Time 00:00
Comment Monitor Pressure and record every 8 Hours / Current pressure at 07:00 Gauge 7- 2278.30, Gauge 8- 2278.44 / Current Pressure at 15:00 Gauge 7- 2273.38, Gauge 8- 2273.18 23:00 Gauge 7-2268.17/gauge 8-2268.15		
Report Start Date	Report End Date	24hr Activity Summary
11/14/2014	11/15/2014	DFIT
Start Time	00:00	End Time 00:00
Comment 7 AM - Monitor Pressure and record every 8 Hours / Current Pressure Gauge 7- 2262.77, Gauge 8- 2262.52 3 PM - Monitor Pressure and record every 8 Hours / Current Pressure Gauge 7- 2258.88, Gauge 8- 2258.51\ 23:00 Gauge 7-2253.62/gauge 8-2253.25		
Report Start Date	Report End Date	24hr Activity Summary
11/15/2014	11/16/2014	DFIT
Start Time	00:00	End Time 00:00
Comment 7 AM - Monitor Pressure and record every 8 Hours / Current Pressure Gauge 7- 2249.33, Gauge 8- 2249.25 3 PM - Monitor Pressure and record every 8 Hours / Current Pressure Gauge 7- 2244.81, Gauge 8- 2244.50 23:00 -- Gauge 7-2241.81/Gauge 8-2241.72		
Report Start Date	Report End Date	24hr Activity Summary
11/16/2014	11/17/2014	DFIT
Start Time	00:00	End Time 00:00
Comment 7 AM - Monitor Pressure and record every 8 Hours / Current Pressure Gauge 7- 2237.71, Gauge 8- 2238.13 3 PM - Monitor Pressure and record every 8 Hours / Current Pressure Gauge 7- 2235.33, Gauge 8- 2234.84 23:00--Gauge 7-2231.12/Gauge 8-2230.82		

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB****Daily Operations**

Report Start Date	Report End Date	24hr Activity Summary
11/17/2014	11/18/2014	DFIT
Start Time	End Time	Comment
00:00	09:00	7 AM - Monitor Pressure and record every 8 Hours / Current Pressure Gauge 7- 2227.59, Gauge 8- 2227.40
Start Time	End Time	Comment
09:00	18:00	Halliburton & crane showed up on location getting everything spotted in & ready to wireline. RD DFIT gauges & night cap. RU Halliburton wireline & pressure test lube to 9,000 psi RIH W/ gauge ring. RIH pump down to 17,700'. POOH W/gauge ring.
Start Time	End Time	Comment
18:00	00:00	LD gauge ring & PU CAST-M logging tools & pressure test lubricator per Newfield standards. Refill water tanks. Pump down CAST-M tool at 5 bpm, LTEN 60, 10 fpm, 5050 psi to 1500'. Tool started falling at that depth.
Report Start Date	Report End Date	24hr Activity Summary
11/18/2014	11/19/2014	RU WL truck. Run Gauge ring.
Start Time	End Time	Comment
00:00	02:00	RIH with CAST-M logging tool to 8200'. Tool not working when rotating the head. POH to reset the telemetry on the head.
Start Time	End Time	Comment
02:00	07:00	POH. LD and repair logging tool. PU tool and lubricator. Check tool before starting IH, found CBL not working, work on CBL.
Start Time	End Time	Comment
07:00	11:00	Halliburton had picked up tools & tested lube & RIH a couple hundred foot & tested tool it didn't respond so came back out repair logging tool. PU tool and lubricator. Check tool before starting IH.
Start Time	End Time	Comment
11:00	15:00	Checking connection on drum to make sure that it is hooked up correctly. Waiting on a new communication box for wireline truck. Got all new stuff put on Halliburton truck & still not working 100% of the time. POOH W/wireline & tools. Re-head wireline & check all things out on surface.
Start Time	End Time	Comment
15:00	20:00	Wait on another WL truck from Rock Springs.
Start Time	End Time	Comment
20:00	00:00	Change out HES WL trucks. PU and check logging tools. Test lubricator per Newfield's guidelines. GIH to 30', PU to work logging tool in as centralizers were dragging. Started losing hole as we worked the tool up and down, working down to only 5'.
Report Start Date	Report End Date	24hr Activity Summary
11/19/2014	11/20/2014	CAST-M log
Start Time	End Time	Comment
00:00	02:00	LD tool logging tool. Found problem with lubricator pack off rubbers and repaired. PU tool and test lubricator to Newfield's standards.
Start Time	End Time	Comment
02:00	04:00	RIH with CAST-M log to 7900' then pump down tools. Pump pressure 6320 psi at 11.8 bpm. Line speed 210 fpm with 750 LTEN. Max pressure 7100 psi. Pumped 590 bbl. Max depth 17,320'.
Start Time	End Time	Comment
04:00	12:00	Run CAST-M log from 17,320' to 1,800'. POOH LD tools & RD Halliburton wireline. Had Halliburtons pump truck brine wellhead. RD Halliburton pump trucks & MO.
Start Time	End Time	Comment
12:00	00:00	Clean up location & finish poly transfer line from the Earl pad.
Report Start Date	Report End Date	24hr Activity Summary
11/20/2014	11/21/2014	CAST-M log
Start Time	End Time	Comment
00:00	00:00	SDFN - Rock Water is on location finishing up poly tranfer line testing & dry pigging.

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

--

Daily Operations

Report Start Date 11/21/2014	Report End Date 11/22/2014	24hr Activity Summary Finish poly transfer line from the Earl pad.	
Start Time 00:00	End Time 06:00	Comment SDFN	
Start Time 06:00	End Time 18:00	Comment Well is shut in . Rockwater is pumping frac water back to Earl pad to avoid freezing in tanks . Haul approx: 1800 bbls	
Start Time 18:00	End Time 00:00	Comment SDFN	
Report Start Date 11/22/2014	Report End Date 11/23/2014	24hr Activity Summary Finish poly transfer line from the Earl pad.	
Start Time 00:00	End Time 00:00	Comment Shut Down, Wait on Frac	
Report Start Date 11/23/2014	Report End Date 11/24/2014	24hr Activity Summary Wait on Frac	
Start Time 00:00	End Time 00:00	Comment Shut Down, Wait on Frac	
Report Start Date 11/24/2014	Report End Date 11/25/2014	24hr Activity Summary Wait on Frac	
Start Time 00:00	End Time 00:00	Comment Shut down, Wait on Frac	
Report Start Date 11/25/2014	Report End Date 11/26/2014	24hr Activity Summary Wait on Frac	
Start Time 00:00	End Time 06:00	Comment SDFN	
Start Time 06:00	End Time 10:00	Comment Rig up Pro's Flowback Lines & Manifold	
Start Time 10:00	End Time 17:00	Comment Pressure Test Flowback Lines & Manifold to Newfield Guidelines, Construction widen road at entrance to location, Spot in & set 500 bbl. Acid tank, Move in Halliburton Mountain Movers, Nipple Down Blanking Flange, Nipple Up 7 1/16"X 10K JW Wireline Flange, Pressure Test Wireline Flange to Newfields Guidelines	
Start Time 17:00	End Time 00:00	Comment Wait on Frac to start, SDFN	
Report Start Date 11/26/2014	Report End Date 11/27/2014	24hr Activity Summary Wait on Frac	
Start Time 00:00	End Time 06:00	Comment SDFN	
Start Time 06:00	End Time 11:00	Comment Goff Trucking loading frac sand into Halliburton Mountain Movers	
Start Time 11:00	End Time 00:00	Comment Wait on Frac to start, SDFN	
Report Start Date 11/27/2014	Report End Date 11/28/2014	24hr Activity Summary Wait on Frac	
Start Time 00:00	End Time 00:00	Comment Waiting for frac	
Report Start Date 11/28/2014	Report End Date 11/29/2014	24hr Activity Summary Wait on Frac	
Start Time 00:00	End Time 06:00	Comment SDFN	

Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time 06:00		End Time 18:00	Comment Move in Halliburton Frac Equip. RU and test frac lines. Move in & Rig up JW Wireline, Heating Water on Earl pad for Frac.
Report Start Date 11/29/2014	Report End Date 11/30/2014	24hr Activity Summary MIRU Halliburton equipment & transfer water for frac.	
Start Time 00:00		End Time 07:00	Comment Transferring water for Frac.
Start Time 07:00		End Time 16:00	Comment Hold JSA, Bucket Test, Halliburton working on Blender Computer, Pressure test frac lines to 10,000psi, Pump lateral volume, Start Frac Stage #1. Global Kick Outs set at 9500 psi. Pressure tested to 10400 psi. Job pumped Produced Water with 1.0% KCl .2. Calculated 8 holes open, 1813 psi perf friction, 997 psi NWB as per FracPro. Developed a leak after coming back on from FET. Shut down to fix. Made some minor design changes as per NF engineering. Started back into job and established XL and pumped 100 Mesh Displaced 100 Mesh with linear gel. Pressure started coming up with XL fluid on formation. Rate dropped to 14 bpm @ 9,100 psi. Decision made to swap back to FR. and flush the well. Placed approx. 6,900 lbs. of 100 Mesh in formation. Good job by crew with all the changes, move on to stage 2. Had multiple problems at the start of the job with data communication between IFS and Fracpro. WG-36-2.3% (15.5), BC-200-8.6% (2), FR-76-9.5% (2.3), BA-20-53.3% (5.7), CL-31-44.8% (1.5), BE-9-24.9% (5), MO-67-73.7% (4.2), MC S-2510T-6.1% (2.3) Vicon NF-4.4% (4.3), Losurf 300D-6.1% (4.6) Cat 3/4-168.4% (10.7),
Start Time 16:00		End Time 18:30	Comment P&P stage 2. RIH with guns and Plug to KOP. pumped down guns at 13.2 bpm @ 6785 Psi, @208 fpm, 724 LT, pumped guns to 17,345', Pulled up and got line tension and set plug @ 17,316'. Line tension prior to setting plug 2009, line tension after plug set 1748, plug set time 1 min. perf'd at (17,275' - 17,278') (17,210' - 17,213'). POOH with tools, max pressure for pump down: 7768. Max rate for pump down- 13.2 bpm. Total BBIs pumped-547.71. POOH w/tools all shots fired. Drop ball & turn over to Frac.
Start Time 18:30		End Time 21:00	Comment Start Frac Stage #2. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10400 psi. Job pumped Produced Water with 1.0% KCl . 2. Calculated 15 holes open, 1095 psi perf friction, 262 psi NWB as per FracPro. 3. Ran a little heavy on 100 Mesh sand and 30/50 prop. 4. Stage went well. All proppant placed. WG-36-2.9% (63.6), BC-200-4.3% (6.1), MO-67-4.1% (1.5), MC S-2510T-2.3% (1.7) Vicon NF-2.9% (6.7), Losurf 300D-5% (7.3) FE-2A-5.3% (1.7),
Start Time 21:00		End Time 00:00	Comment P&P stage 3. RIH with guns and Plug to KOP. Pumped down guns at 13.2 bpm @ 4,518 Psi, @220 fpm, 860 LT, pumped guns to 17,140', Pulled up and got line tension and set plug @ 17,110'. LT prior to setting plug 2,122, LT after plug set 1,772, plug set time 50 sec. perforated at (17,100' - 17,103') (17,050' - 17,053') (17,000-17,003). Max pressure for pump down was 4,518 psi. Max rate for pump down- 13.2 bpm. Total Bbls pumped - 522.2. POOH w/tools all shots fired. Drop ball & turn over to Frac.
Report Start Date 11/30/2014	Report End Date 12/1/2014	24hr Activity Summary Pressure test lines & start frac. Frac stage 1 & 2. P&P stages 1, 2 & 3.	
Start Time 00:00		End Time 02:00	Comment Start Frac on Stage #3. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water with 1.0% KCl . 2. Calculated 17 holes open, 778 psi perf friction, 663 psi NWB as per FracPro. 3. T-Belt sanded off during 3.0# sand stage. Sand fell off completely. 10,000 gallons after losing sand, operators were able to clean up and get going again. Redesigned and worked back up to 3.5# to resume stage. 4. Started losing tub on flush. Had to drop 4 bpm down to 56 bpm. 5. Good effort in recovering by crew. WG-36-4.9% (166.2), BC-200-2.8% (6.1), FR-76-39.7% (12.8), BA-20-9.6% (5.2), CL-31-4.5% (1.5) MO-67-2.5% (1.5), Losurf 300D-4.6% (9.1) FE-2A-22.7% (9.4), Cat 3/4-9.3% (2.7), BE-9-3.4% (1)



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	02:00	End Time	04:30	Comment
				P&P stage 4. RIH with guns and Plug to KOP. Pumped down guns at 13.1 bpm @ 4,611 Psi, @240 fpm, 850 LT, pumped guns to 16,990', Pulled up and got line tension and set plug @ 16,945'. LT prior to setting plug 1,886, LT after plug set 1,665, plug set time 53 sec. perforated at (16,950' - 16,953') (16,900' - 16,903') (16,823-16,826). Max pressure for pump down was 4,611 psi. Max rate for pump down- 13.1 bpm. Total Bbls pumped – 525. POOH w/tools all shots fired. Drop ball & turn over to Frac.
Start Time	04:30	End Time	06:30	Comment
				Start Frac stage #4. 1. Global Kick Outs set at 9400 psi. Pressure tested to 9400 psi. Job pumped Produced Water with 1.0% KCl. 2. Calculated 14 holes open, 1125 psi perf friction, 536 psi NWB as per FracPro.3. 30/50 Ran long. Operator overestimated how much was in hopper and T-Belt at end of stage. Ran approx. 10,000 lbs heavy. ball Seat Stage Pressures and Rate: 4575 psi @ 14.7 bpm, 4575 psi Pressure before Seating, 4575 psi Pressure after Seating. WG-36-4.7% (122.7), BC-200-3.5% (7.3), BA-20-15.6% (6.5), MO-67-6.1% (6.4), Vicon NF-5% (13.4), FE-2A-16% (6.3), BE-9-17% (8.2)
Start Time	06:30	End Time	10:00	Comment
				JW wireline Jumped Sheave kinked wireline and will have to replace Sheave and cut 400' of wireline and re-head. before RIH w/ stage #5 P&P.
Start Time	10:00	End Time	12:30	Comment
				Plug and Perf: Stage #5 RIH with guns and Plug to KOP. pumped down guns at 13.3 bpm @ 4703 Psi, @250 fpm, 880 LT, pumped guns to 16,800, Pulled up and got line tension and set plug. Line tension prior to setting plug 1869, line tension after plug set 1630, plug set time 1min30secs. POH and perf'd at (16,725' - 16,728') (16,660' - 16,663') (16,600' - 16,603'). POOH with tools, max pressure for pump down: 4703 Max rate for pump down- 13.3bpm. Total BBlS pumped-415.8. POOH W/Wireline all shots fired, Turn well over to Frac
Start Time	12:30	End Time	15:30	Comment
				Start Frac stage #5 Global Kick Outs set at 9730 psi. Pressure tested to 10490 psi. Job pumped Produced Water.2. Calculated 21 holes open, 1085 psi perf friction, 600 psi NWB as per FracPro.3. Able to get to 60 bpm with no problems.4. Good job execution by the crew, all proppant placed. Ball Seat Stage Pressures and Rate: 5252 psi @ 14.7 bpm, 4773 psi Pressure before Seating, 5247 psi Pressure after Seating WG-36-13.8% (323.2), BC-200-2.2% (3.4), CL-31-12.3% (2.8) MO-67-2.9% (2.2), MC S-2510T-4.5% (3.9) Vicon NF -11.4% (32.3), Losurf 300D-5% (8.9) Cat 3/4-22.4% (6.6), BE-9-7.9% (4.2)
Start Time	15:30	End Time	17:30	Comment
				Plug and Perf: Stage #6. RIH with guns and Plug to KOP. pumped down guns at 13.1 bpm @ 4418 Psi, @245 fpm, 870 LT, pumped guns to 16,572', Pulled up and got line tension and set plug. Line tension prior to setting plug 1907, line tension after plug set 1705, plug set time 1min40secs. POH and perf'd at (16,505'-16508') (16,421'-16,424'). POOH with tools, max pressure for pump down: 4492 Max rate for pump down- 13.2 bpm. Total BBlS pumped-411. POOH W/Wireline all shots fired.
Start Time	17:30	End Time	18:30	Comment
				Weatherford Grease all valves on Frac Stack
Start Time	18:30	End Time	20:30	Comment
				Drop ball & Start Frac stage #6, Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. Calculated 17 holes open, 1700 psi perf friction, 248 psi NWB as per FracPro. CFT 1200 - 13 cups Protechnics tracer. Ball Seat Stage Pressures and Rate: 5169 psi @ 14.5 bpm, 4528 psi Pressure before Seating, psi Pressure after Seating, WG-36-4.9% (80.1), BC-200-3.6% (3.8), FR-76-3.3% (1.2), BA-20-4.7% (1.2), MC S-2510T-4.2% (3) Losurf 300D-4.2% (5.9), FE-2A-6.6% (2.9), BE-9-4.8% (2)

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	20:30	End Time
		23:00
Comment		
Plug and Perf: Stage #7, RIH with guns and Plug to KOP. Pumped down guns at 12.1 bpm @ 4,209 Psi, @220 fpm, 830 LT, pumped guns to 16,380', Pulled up and got line tension and set plug @16,340'. Line tension prior to setting plug 1,870, line tension after plug set 1,640, plug set time 50secs. POOH and perforated at (16,282'-16,285') (16,200'-16,203'). POOH with tools, max pressure for pump down: 4,209 Max rate for pump down- 12.2 bpm. Total BBIs pumped-434. POOH W/Wireline all shots fired, Turn well over to Frac		
Start Time	23:00	End Time
		00:00
Comment		
Start Frac stage #7		
Report Start Date	Report End Date	24hr Activity Summary
12/1/2014	12/2/2014	Frac stages 3,4,5,& 6. P&P stages 4,5,6, &7.
Start Time	00:00	End Time
		00:30
Comment		
Start Frac stage #7, Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. Calculated 17 holes open, 766 psi perf friction, 1207 psi NWB as per FracPro.CFT 1300 - 15 cups Protechnics tracer. WG-36-4.9% (80.4), FR-76-2.9% (1), MC S-2510T-4.4% (3) Vicon NF-4% (8.1), Losurf 300D-4.4% (6), BE-9-2.9% (1.2)		
Start Time	00:30	End Time
		02:30
Comment		
Plug and Perf: Stage #8, RIH with guns and Plug to KOP. Pumped down guns at 14 bpm @ 4,449 Psi, @250 fpm, 900 LT, pumped guns to 16,195', Pulled up and got line tension and set plug @16,168'. Line tension prior to setting plug 1,870, line tension after plug set 1,650, plug set time 68 secs. POOH and perforated at (16,104'-16,107') (16,040'-16,043'). POOH with tools, max pressure for pump down: 4,449 Max rate for pump down- 14 bpm. Total BBIs pumped- 432. POOH W/Wireline all shots fired, Turn well over to Frac		
Start Time	02:30	End Time
		04:30
Comment		
Start Frac stage #8 Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. Calculated 15 holes open, 1087 psi perf friction, 671 psi NWB as per FracPro. 14.5 cups 1300 CFT Protechnics. BC-200-2.8% (3), FR-76-4.6% (1.6), CL-31-7.4% (1.2), MC S-2510T-4.8% (3.3) Vicon NF-4% (8), Losurf 300D-4.1% (5.6)FE-2A-8.1% (3.3), BE-9-3.4% (1.4)		
Start Time	04:30	End Time
		06:30
Comment		
Plug and Perf: Stage #9, RIH with guns and Plug to KOP. pumped down guns at 13.9 bpm @ 4340 Psi, @250 fpm, 900 LT, pumped guns to 15,996', Pulled up and got line tension and set plug. Line tension prior to setting plug 1960, line tension after plug set 1600, plug set time 1min30secs. POH and perf'd at (15,940'-15,943') (15,880'-15,883') (15,820'-15,823'). POOH with tools, max pressure for pump down:4340 Max rate for pump down- 14bpm. Total BBIs pumped-438.5. POOH W/Wireline all shots fired, Turn well over to Frac		
Start Time	06:30	End Time
		08:30
Comment		
Start Frac stage #9, 1. Global Kick Outs set at 9500 psi. Pressure tested to 10450 psi. Job pumped Produced Water. 2. Calculated 22 holes open, 988 psi perf friction, 885 psi NWB as per FracPro. 3. Good job execution by the crew, all sand placed in formation. Ball Seat Stage Pressures and Rate: 5575 psi @ 15.2 bpm , 4723 psi Pressure before Seating , 5590 psi Pressure after Seating BC-200-2.9% (4.7), MO-67-2.3% (1.9), MC S-2510T-4.7% (4) Vicon NF-4.3% (11.8), Losurf 300D-4.7% (8), FE-2A-6.7% (3.1), BE-9-4.7% (2.4)		
Start Time	08:30	End Time
		10:30
Comment		
Plug and Perf: Stage #10 RIH with guns and Plug to KOP. pumped down guns at 13.2 bpm @ 4206 Psi, @250 fpm, 915 LT, pumped guns to 15,670', Pulled up and got line tension and set plug. Line tension prior to setting plug 1820, line tension after plug set 1545, plug set time 1min15secs. POH and perf'd at (15,620'-15,623') (15,550'-15,553') (15,480'-15,483'), POOH with tools, max pressure for pump down: 4206, Max rate for pump down- 13.2bpm. Total BBIs pumped-386.8. . POOH W/Wireline all shots fired, Turn well over to Frac		

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	10:30	End Time	13:00	Comment
				Start Frac stage #10, 1. Global Kick Outs set at 9500 psi. Pressure tested to 10533 psi. Job pumped Produced Water. 2. Calculated 20 holes open, 1188 psi perf friction, 693 psi NWB as per FracPro. 3. Did not see a 200 psi loss across the 15 minute shutdown. 4. Good job execution by the crew, all sand placed. 5. Minor rate fluctuation during middle of job, rate loss 1 bpm or less. Lined out for remainder of job. Ball Seat Stage Pressures and Rate: 4900 psi @ 15.1 bpm, 4300 psi Pressure before Seating, 4910 psi Pressure after Seating. FR-76-5.2% (2), CL-31-4.3% (1), MC S-2510T-3.7% (3.2), Losurf 300D-3.1% (5.3), FE-2A-5% (2.2), BE-9-4.1% (2.1)
Start Time	13:00	End Time	15:30	Comment
				Plug and Perf: Stage #11 RIH with guns and Plug to KOP. pumped down guns at 13.6 bpm @ 4109 Psi, @246 fpm, 915 LT, pumped guns to 15,436', Pulled up and got line tension and set plug. Line tension prior to setting plug 1730, line tension after plug set 1458, plug set time 31secs. POH and perfed at (15,411'-15,414') (15,341'-15,344') (15,281'-15,284'), POOH with tools, max pressure for pump down: 4109, Max rate for pump down-13.6bpm. Total BBIs pumped-385.5. POOH W/Wireline all shots fired, Turn well over to Frac
Start Time	15:30	End Time	16:00	Comment
				Weatherford Greasing 7 1/16" Frac stack
Start Time	16:00	End Time	17:30	Comment
				Start Frac stage #11 (Chemical pump down 45 mins, resume frac with no other issues. Fracing stage #11 at present.) 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 21 holes open, 1186 psi perf friction, 350 psi NWB as per FracPro. 3. Lost the mixing bowl on the Growler at the end of 1.5 ppa sand, staged and dropped rate to see if it could recover. Gel was essentially gone, cut prop and flushed the well. Down 45 minutes.
Start Time	17:30	End Time	18:15	Comment
				Chemical blending pump down, repaired and continue with frac of stage #11 with no other issues.
Start Time	18:15	End Time	19:30	Comment
				Finisht Frac stage #11 Continue frac of stage #11 (Chemical pump down 45 mins, resume frac with no other issues. Fracing stage #11 at present.) 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 21 holes open, 1186 psi perf friction, 350 psi NWB as per FracPro. 3. Lost the mixing bowl on the Growler at the end of 1.5 ppa sand, staged and dropped rate to see if it could recover. Gel was essentially gone, cut prop and flushed the well. Down 45 minutes. Continue frac stage #11 4. Had a dip in prop con on 1.5 ppa stage, able to recover. Hopper dropped too low. 5. Remainder of the job went well with all proppant placed. Ball Seat Stage Pressures and Rate: 4770 psi @ 15.2 bpm, 4200 psi Pressure before Seating, 4775 psi Pressure after Seating WG-36-4.6% (143.5), BC-200-3.6% (8), FR-76-2.7% (1.3), BA-20-3.2% (1.6), CL-31-3.7% (1.3), MO-67-3.1% (3.5), Losurf 300D-4.4% (9.6), BE-9-3.3% (2.2)
Start Time	19:30	End Time	22:00	Comment
				Plug and Perf: Stage #12 RIH with guns and Plug to KOP. pumped down guns at 14.1 bpm @ 4131 Psi, @238 fpm, 958 LT, pumped guns to 15,236', Pulled up and got line tension and set plug. Line tension prior to setting plug 1764, line tension after plug set 1526, plug set time 55 secs. POH and perfed at (15,216'-15,219') (15,141'-15,144') (15,065'-15,068'), POOH with tools, max pressure for pump down: 4131, Max rate for pump down- 14.1 bpm. Total BBIs pumped-386.02. POOH W/Wireline all shots fired, Turn well over to Frac.

Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	22:00	End Time	00:00	Comment
				Start Frac stage #12 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 20 holes open, 1055 psi perf friction, 335 psi NWB as per FracPro. 3. 100 Mesh bin emptied late resulting in longer 1 ppg 100 Mesh stage. 4. Stage went well with all proppant placed. Ball Seat Stage Pressures and Rate: 4842 psi @ 14.9 bpm , 4441 psi Pressure before Seating , 4842 psi Pressure after Seating WG-36-3.7% (83.6) , BC-200-2.5% (4) , FR-76-4.2% (1.8) , BA-20-4.1% (1.5) , Losurf 300D-3.6% (6.5) , FE-2A-3.1% (1.5) , BE-9-2.1% (1.1)
Report Start Date	Report End Date	24hr Activity Summary		
12/2/2014	12/3/2014	Frac stages 13,14,15,16,17,18,19 P&P stages 13,14,15,16,17,18,19		
Start Time	00:00	End Time	00:30	Comment
				Finish stage #12 frac.
Start Time	00:30	End Time	02:45	Comment
				Plug and Perf: Stage #13 RIH with guns and Plug to KOP. pumped down guns at 12.1 bpm @ 4,161 Psi, @234 fpm, 890 LT, pumped guns to 15,021', Pulled up and got line tension and set plug. Line tension prior to setting plug 1722, line tension after plug set 1,460, plug set time 46 secs. POH and perfed at (14,985'-14,988') (14,910'-14,913') (14,834'-1,837'), POOH with tools, max pressure for pump down: 4,161, Max rate for pump down 12.1 bpm. Total BBIs pumped 331.40, POOH W/Wireline all shots fired, Turn well over to Frac.
Start Time	02:45	End Time	05:00	Comment
				Start Frac stage #13. Global Kick outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water.2. Calculated 24 holes open, 28 psi perf friction, 697 psi NWB as per FracPro.3. Stage went well with all proppant placed.4. Protechnics pumped 19.5 cups of FTP 1600.Ball Seat Stage Pressures and Rate: 4218 psi @ 15 bpm , 4115 psi Pressure before Seating , 4218 psi Pressure after Seating, FR-76-4.6% (1.7) , MC S-2510T-3.9% (3.2) Vicon NF-4.4% (11.1) , Losurf 300D-4% (6.6) , FE-2A-4.2% (1.8) , BE-9-3.4% (1.7) .
Start Time	05:00	End Time	07:00	Comment
				Plug and Perf: Stage #14 RIH with guns and Plug to KOP. pumped down guns at 12 bpm @ 4,043 Psi, @240 fpm, 900 LT, pumped guns to 14,794' Pulled up and got line tension and set plug. Line tension prior to setting plug 1642, line tension after plug set 1,390, plug set time 1min. POH and perfed at (14,754'-14,757') (14,679'-14,682') (14,603'-14,606'), POOH with tools, max pressure for pump down: 4,050, Max rate for pump down 12.1 bpm. Total BBIs pumped 316, POOH W/Wireline all shots fired, Turn well over to Frac.
Start Time	07:00	End Time	09:30	Comment
				Start Frac Stage #14. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 23 holes open, 765 psi perf friction, 145 psi NWB as per FracPro. 3. Good job execution by the crew, all sand pumped. Ball Seat Stage Pressures and Rate: 4212 psi @ 15.8 bpm , 4053 psi Pressure before Seating , 4220 psi Pressure after Seating WG-36-3.1% (69.4) , CL-31-6.3% (1.5) MO-67-2% (1.6) , Losurf 300D-2.6% (4.2) BE-9-3.7% (1.8)
Start Time	09:30	End Time	11:30	Comment
				Plug and Perf: Stage #15 RIH with guns and Plug to KOP. pumped down guns at 14.1 bpm @ 3,921 Psi, @256 fpm, 950 LT, pumped guns to 14,537' Pulled up and got line tension and set plug @14,551'. Line tension prior to setting plug 1,819, line tension after plug set 1,540, plug set time 1min 25 sec. POH and perfed at (14,523'-14,526') (14,448'-14,451') (14,372'-14,375'), POOH with tools, max pressure for pump down: 3,921, Max rate for pump down 14.1 bpm. Total BBIs pumped 303, POOH W/Wireline all shots fired, Turn well over to Frac.

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time 11:30	End Time 13:30	Comment Start Frac Stage #15. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10480 psi. Job pumped Produced Water. 2. Calculated 24 holes open, 751 psi perf friction, 310 psi NWB as per FracPro. 3. Good job execution by the crew, all proppant placed. Ball Seat Stage Pressures and Rate: 4225 psi @ 15.5 bpm , 4080 psi Pressure before Seating , 4228 psi Pressure after Seating WG-36-5.9% (129.7) , BC-200-5.2% (8.2) , FR-76-5.1% (1.8) ,BA-20-6.7% (2.4) , CL-31-6.3% (1.5) MO-67-2% (1.6) , MC S-2510T-5.6% (4.4) Vicon NF-7.5% (19.5) , Losurf 300D-5.1% (8.1) FE-2A-4.4% (1.8) , BE-9-4.9% (2.3)
Start Time 13:30	End Time 15:30	Comment Plug and Perf: Stage #16 RIH with guns and Plug to KOP. pumped down guns at 13 bpm @ 3,930 Psi, @250 fpm, 900 LT, pumped guns to 14,340' Pulled up and got line tension and set plug @14,330'. Line tension prior to setting plug 1,830, line tension after plug set 1,560, plug set time 1min. POH and perf'd at (14,292'-14,295') (14,217'-14,220') (14,141'-14,144'), POOH with tools, max pressure for pump down: 3,930, Max rate for pump down 13.1 bpm. Total BBls pumped 315.
Start Time 15:30	End Time 16:30	Comment Grease Frac Tree.
Start Time 16:30	End Time 18:30	Comment Drop Ball & turn over to frac. Start Frac Stage #16. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 21 holes open, 909 psi perf friction, 128 psi NWB as per FracPro. 3. Gel ran about 200 lbs low, early time visc was running 1-2 cp light. 4. Good job execution by the crew, all sand placed. Ball Seat Stage Pressures and Rate: 4376 psi @ 15.8 bpm , 4163 psi Pressure before Seating , 4380 psi Pressure after Seating WG-36-10.5% (221.8) , BC-200-4% (6.2) , FR-76-3.1% (1) , MO-67-3.8% (2.9) , Vicon NF-6.1% (15.3) , Losurf 300D-4.9% (7.5) , FE-2A-3.4% (1.3) , BE-9-4.9% (2.2)
Start Time 18:30	End Time 20:30	Comment Plug and Perf: Stage #17 RIH with guns and Plug to KOP. pumped down guns at 12.1 bpm @ 3,869 Psi, @208 fpm, 857 LT, pumped guns to 14,094', Pulled up and got line tension and set plug. Line tension prior to setting plug 1,634, line tension after plug set 1,383, plug set time 39 secs. POH and perf'd at (14,061'-14,064') (13,986'-13,989') (13,910'-13,913'), POOH with tools, max pressure for pump down: 9,936, Max rate for pump down 12.1 bpm. Total BBls pumped 317.73, POOH W/Wireline all shots fired, Turn well over to Frac.
Start Time 23:00	End Time 01:00	Comment frac 17
Start Time 20:30	End Time 23:00	Comment Start Frac Stage #17. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 27 holes open, 586 psi perf friction, 76 psi NWB as per FracPro. 3. Stage went well with all proppant placed. 4. ProTechnics pumped 18 Cups of CFT 1900. BC-200-4% (6.4) , FR-76-3.5% (1.2) , MO-67-3.5% (2.8) , MC S-2510T-2.6% (2) Vicon NF-3.9% (9.5) , Losurf 300D-4.5% (7) FE-2A-4.2% (1.6) , BE-9-4.7% (2.2)
Start Time 02:00	End Time 02:00	Comment P&P 18
Start Time 01:00	End Time 02:00	Comment RIH to P&P Stage # 18.
Report Start Date 12/3/2014	Report End Date 12/4/2014	24hr Activity Summary Frac stages 13,14,15,16,17,18,19 P&P stages 13,14,15,16,17,18,19
Start Time 00:00	End Time 01:00	Comment Plug and Perf: Stage #18 RIH with guns and Plug to KOP. pumped down guns at 12.1 bpm @ 4,037 Psi, @247 fpm, 880 LT, pumped guns to 13,853', Pulled up and got line tension and set plug. Line tension prior to setting plug 1,564, line tension after plug set 1,333, plug set time 64 secs. POH and perf'd at (13,830'-13,833') (13,755'-13,758') (13,679'-13,682'), POOH with tools, max pressure for pump down: 4,037, Max rate for pump down 12.1 bpm. Total BBls pumped 278.27, POOH W/Wireline all shots fired, Turn well over to Frac.

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	01:00	End Time	03:00	Comment
				Start Frac Stage # 18. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 24 holes open, 714 psi perf friction, 37 psi NWB as per FracPro. 3. Stage went well with all proppant placed. 4. ProTechnics pumped 17 cups of CFT 2000 during the stage. Ball Seat Stage Pressures and Rate: 4286 psi @ 14.9 bpm , 4102 psi Pressure before Seating , 4286 psi Pressure after Seating. BC-200-4.3% (6.8) , FR-76-3.8% (1.3) , MO-67-2.7% (2.1) , MC S-2510T-4.2% (3.3) Vicon NF-3.8% (9.4) , Losurf 300D-4.2% (6.5) BE-9-2.2% (1)
Start Time	03:00	End Time	05:00	Comment
				Plug and Perf: Stage #19 RIH with guns and Plug to KOP. pumped down guns at 12.1 bpm @ 4,139 Psi, @236 fpm, 913 LT, pumped guns to 13,630', Pulled up and got line tension and set plug. Line tension prior to setting plug 1,485, line tension after plug set 1,201, plug set time 90 secs. POH and perfed at (13,599'-13,602') (13,524'-13,527') (13,448'-13,451'), POOH with tools, max pressure for pump down: 4,139, Max rate for pump down 12.1 bpm. Total BBIs pumped 265.12, POOH W/Wireline. All shots fired. Drop ball & turn over to Frac.
Start Time	05:00	End Time	07:00	Comment
				Start Frac Stage #19. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 25 holes open, 713 psi perf friction, 58 psi NWB as per FracPro. 3. Observed a pressure build with 1 ppg 100 mesh on formation and again with 1.5 ppg 30/50 on formation. 4. Stage went well with all proppant placed. Ball Seat Stage Pressures and Rate: 4262 psi @ 15.4 bpm , 4135 psi Pressure before Seating , 4262 psi Pressure after Seating. WG-36-11.8% (260.5) , BC-200-5% (7.8) , FR-76-3.1% (1) , BA-20-4.1% (1.5) , MO-67-3.9% (3.1) , MC S-2510T-4.2% (3.3) Vicon NF-4.2% (10.2) , Losurf 300D-4.7% (7.4) Cat 3/4-5.3% (1.2) , BE-9-4.3% (2)
Start Time	07:00	End Time	09:00	Comment
				Plug and Perf: Stage #20 RIH with guns and Plug to KOP. pumped down guns at 12.1 bpm @ 3,844 Psi, @245 fpm, 905 LT, pumped guns to 13,395' Pulled up and got line tension and set plug @13,396'. Line tension prior to setting plug 1,593, line tension after plug set 1,370, plug set time 47 sec. POH and perfed at (13,368'-13,371') (13,293'-13,296') (13,217'-13,220'), POOH with tools, max pressure for pump down: 3,844, Max rate for pump down 13.1 bpm. Total BBIs pumped 269. All shots fired. Drop ball & turn over to Frac.
Start Time	09:00	End Time	11:00	Comment
				Start Frac Stage #20. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 26 holes open, 705 psi perf friction, 298 psi NWB as per FracPro. 3. Good job execution by the crew, all sand placed. Ball Seat Stage Pressures and Rate: 4300 psi @ 15.8 bpm , 4015 psi Pressure before Seating , 4311 psi Pressure after Seating. WG-36-5% (104.6) , BC-200-4.9% (7.4) , FR-76-25.8% (7.2) , MO-67-3.7% (2.8) , MC S-2510T-5% (3.8) Vicon NF-9.8% (24.5) , Losurf 300D-4.4% (6.7) FE-2A-6.7% (2.4) , Cat 3/4-7.4% (1.7) ,
Start Time	11:00	End Time	12:30	Comment
				: Plug and Perf: Stage #21 RIH with guns and Plug to KOP. pumped down guns at 13 bpm @ 3,921 Psi, @260 fpm, 905 LT, pumped guns to 13,195' Pulled up and got line tension and set plug @13,165'. Line tension prior to setting plug 1,638, line tension after plug set 1,408, plug set time 50 sec. POH and perfed at (13,137'-13,140') (13,062'-13,065') (12,986'-12,989'), POOH with tools, max pressure for pump down: 3,921, Max rate for pump down 13 bpm. Total BBIs pumped 259. All shots fired. Shut HCR valve.
Start Time	12:30	End Time	13:30	Comment
				Grease Frac Tree.
Start Time	13:30	End Time	15:30	Comment
				Start Frac Stage #21. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 23 holes open, 969 psi perf friction, 405 psi NWB as per FracPro. 3. Gel coming during job a 1-2 points light. XL samples looked good throughout. 4. Good job execution by the crew, all sand placed. Ball Seat Stage Pressures and Rate: 4472 psi @ 15.5 bpm , 4126 psi Pressure before Seating , 4475 psi Pressure after Seating BC-200-2.1% (3.3) , FR-76-13.7% (3.6) , BA-20-14.4% (5.3) , MC S-2510T-4.3% (3.3) Vicon NF-8.4% (23) , Losurf 300D-3.6% (5.7) FE-2A-17.1% (5.5) , Cat 3/4-30.7% (8) , BE-9-4.3% (2)

Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	15:30	End Time	17:00	Comment
				Plug and Perf: Stage #22 RIH with guns and Plug to KOP. pumped down guns at 13.1 bpm @ 4,033 Psi, @254 fpm, 900 LT, pumped guns to 12,950' Pulled up and got line tension and set plug @12,934'. Line tension prior to setting plug 1,850, line tension after plug set 1,600, plug set time 19 sec. POH and perfed at (12,906'-12,909') (12,831'-12,834') (12,755'-12,758'), POOH with tools, max pressure for pump down: 4,033, Max rate for pump down 13.1 bpm. Total BBIs pumped 254. POOH W/tools & check guns. Drop ball & turn over to Frac
Start Time	17:00	End Time	19:00	Comment
				Frac Stage #22, 1. Global Kick Outs set at 9500 psi. Pressure tested to 10400 psi. Job pumped Produced Water. 2. Calculated 25 holes open, 853 psi perf friction, 663 psi NWB as per FracPro. 3. Lost a pump due to power end problem, made up rate with remaining 9 pumps. 4. Stage treated well with all proppant placed. Ball Seat Stage Pressures and Rate: 4742 psi @ 15.2 bpm, 4343 psi Pressure before Seating, 4744 psi Pressure after Seating, WG-36-2.5% (43.4), BC-200-4.7% (7.1), FR-76-3.8% (1.2), BA-20-3.6% (1.3), MO-67-4.7% (3.6), MC S-2510T-3% (2.3) Vicon NF-4.5% (10.8), Losurf 300D-4.3% (6.6), FE-2A-2.7% (1), BE-9-3.9% (1.8)
Start Time	19:00	End Time	21:00	Comment
				Plug and Perf: Stage #23 RIH with guns and Plug to KOP. pumped down guns at 11.0 bpm @ 3,938 Psi, @231 fpm, 820 LT, pumped guns to 12,717', Pulled up and got line tension and set plug. Line tension prior to setting plug 1,620, line tension after plug set 1,440, plug set time 30 secs. POH and perfed at (12,675'-12,678') (12,600'-12,603') (12,495'-12,498'), POOH with tools, max pressure for pump down: 3,938, Max rate for pump down 11.0 bpm. Total BBIs pumped 246.28, POOH W/Wireline all shots fired, Turn well over to Frac.
Start Time	21:00	End Time	23:30	Comment
				Start Frac Stage #23, 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 24 holes open, 422 psi perf friction, 613 psi NWB as per FracPro. 3. Stage went well with all proppant placed. Ball Seat Stage Pressures and Rate: 4716 psi @ 14.6 bpm, 4300 psi Pressure before Seating, 4716 psi Pressure after Seating, WG-36-2.6% (45.3), BC-200-4.2% (6.5), BA-20-3.9% (1.3), MO-67-3.5% (2.7), Vicon NF-3.5% (7.9), Losurf 300D-4.6% (6.8)
Start Time	23:30	End Time	00:00	Comment
Report Start Date	Report End Date	24hr Activity Summary		Start in hole to P&P stage #24 at report time.
12/4/2014	12/5/2014	Frac stages 24,25,26,27,28 & 29 P&P stages 24,25,26,27,28,29 & 30		
Start Time	00:00	End Time	01:30	Comment
				Plug and Perf: Stage #24 RIH with guns and Plug to KOP. pumped down guns at 12.0 bpm @ 3,980 Psi, @235 fpm, 829 LT, pumped guns to 12,462', Pulled up and got line tension and set plug. Line tension prior to setting plug 1,540, line tension after plug set 1,278, plug set time 54 secs. POH and perfed at (12,444'-12,447') (12,369'-12,372'), POOH with tools, max pressure for pump down: 3,980, Max rate for pump down 12.0 bpm. Total BBIs pumped 215.10, POOH W/Wireline all shots fired, Turn well over to Frac.
Start Time	01:30	End Time	03:30	Comment
				Start Frac Stage #24, 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 17 holes open, 1216 psi perf friction, 370 psi NWB as per FracPro. 3. Hopper dropped off during 0.5 ppg 100 mesh resulting in a dip in proppant concentration. WG-36-4.8% (70.5), BC-200-4.7% (5.2), FR-76-4.1% (1.2), MO-67-3.8% (2.1), MC S-2510T-4.2% (2.6) Vicon NF-4.8% (8.9), Losurf 300D-4% (4.9), BE -9-4.8% (1.7).

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	03:30	End Time	05:00	Comment
				Plug and Perf: Stage #25 RIH with guns and Plug to KOP. pumped down guns at 12.0 bpm @ 4,293 Psi, @230 fpm, 820 LT, pumped guns to 12,248'. Pulled up and got line tension and set plug. Line tension prior to setting plug 1,570, line tension after plug set 1,270, plug set time 53 secs. POH and perf'd at (12,293'-12,296') (12,196'-12,199') (12,062'-12,065'), POOH with tools, max pressure for pump down: 4,293, Max rate for pump down 12.0 bpm. Total BBIs pumped 196.55, POOH W/Wireline all shots fired, Turn well over to Frac.
Start Time	05:00	End Time	07:00	Comment
				Start Frac Stage #25. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 24 holes open, 576 psi perf friction, 352 psi NWB as per FracPro. 3. Stage went well with all proppant placed. Ball Seat Stage Pressures and Rate: 4521 psi @ 14.9 bpm, 4249 psi Pressure before Seating, 4521 psi Pressure after Seating WG-36-20.1% (332.9), BC-200-4.5% (7.2), BA-20-3.6% (1.2), MO-67-3.9% (3.1), MC S-2510T-4.1% (3.1) Vicon NF-4.4% (10.2), Losurf 300D-3.5% (5.2) FE-2A-4.1% (1.4), BE-9-2.4% (1.1)
Start Time	07:00	End Time	08:30	Comment
				P&P Stage #26. RIH with guns and Plug to KOP. pumped down guns at 13.1 bpm @ 4,046 Psi, @250 fpm, 910 LT, pumped guns to 12,020' Pulled up and got line tension and set plug @12,010'. Line tension prior to setting plug 1,414, line tension after plug set 1,270, plug set time 56 sec. POH and perf'd at (11,984'-11,987') (11,924'-11,927') (11,868'-11,871'), POOH with tools, max pressure for pump down: 4,046, Max rate for pump down 13.1 bpm. Total BBIs pumped 201. POOH W/tools. All shots fired. Drop ball & turn over to Frac.
Start Time	08:30	End Time	10:30	Comment
				Start Frac Stage #26. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10450 psi. Job pumped Produced Water. 2. Calculated 26 holes open, 683 psi perf friction, 747 psi NWB as per FracPro. 3. A few minor pump problems up front with the rate, was able to line out at 60 bpm for job. 4. Had a quick sand spike on 1.5 ppa stage, fat fingered number in the van. 5. Overall good job execution by the crew, all sand placed. Ball Seat Stage Pressures and Rate: 5170 psi @ 16.2 bpm, 4558 psi Pressure before Seating, 5179 psi Pressure after Seating. WG-36-9.8% (170.9), BC-200-4% (6.2), BA-20-3% (1), MO-67-4% (3.1), MC S-2510T-5.1% (3.8) Vicon NF-4.5% (10.8), Losurf 300D-4.3% (6.4) BE-9-4.7% (2.1)
Start Time	10:30	End Time	12:00	Comment
				Plug and Perf: Stage #27 RIH with guns and Plug to KOP. pumped down guns at 12.6 bpm @ 4,165 Psi, @257 fpm, 892 LT, pumped guns to 11,850' Pulled up and got line tension and set plug @11,835'. Line tension prior to setting plug 1,595, line tension after plug set 1,396, plug set time 44 sec. POH and perf'd at (11,804'-11,807') (11,744'-11,747') (11,684'-11,687'), POOH with tools, max pressure for pump down: 4,165, Max rate for pump down 12.6 bpm. Total BBIs pumped 184. POOH w/ tools. All shots fired. Shut HCR.
Start Time	12:00	End Time	13:00	Comment
				Grease Frac Tree.
Start Time	13:00	End Time	15:00	Comment
				Start Frac Stage # 27. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10460 psi. Job pumped Produced Water. 2. Calculated 27 holes open, 450 psi perf friction, 1092 psi NWB as per FracPro. 3. Good job execution, all sand placed. 4. Gel continues to run heavy, visc is still running 16-17 cp at 75F. WG-36-17.9% (305.8), BC-200-5.3% (8.1), FR-76-4.2% (1.3), BA-20-3.6% (1.2), MO-67-4.6% (3.5), MC S-2510T-3.3% (2.5) Vicon NF-5.3% (12.5), Losurf 300D-4.7% (7.1) FE-2A-3.4% (1.2), BE-9-5.2% (2.3)
Start Time	15:00	End Time	16:30	Comment
				Plug and Perf: Stage #28 RIH with guns and Plug to KOP. pumped down guns at 12.8 bpm @ 4,160 Psi, @264 fpm, 928 LT, pumped guns to 11,650' Pulled up and got line tension and set plug @11,630'. Line tension prior to setting plug 1,301, line tension after plug set 1,158, plug set time 67 sec. POH and perf'd at (11,605'-11,608') (11,550'-11,553') (11,475'-11,478'), POOH with tools, max pressure for pump down: 4,160, Max rate for pump down 12.8 bpm. Total BBIs pumped 169. POOH w/ tools. All shots fired. Drop ball & turn over to frac.

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	16:30	End Time
		18:30
Comment		
Start Frac Stage #28. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 25 holes open, 808 psi perf friction, 647 psi NWB as per FracPro. 3. Good job execution, all sand placed. Ball Seat Stage Pressures and Rate: 4675 psi @ 15 bpm , 4300 psi Pressure before Seating , 4690 psi Pressure after Seating. WG-36-4.6% (80.8) , BC-200-2.7% (4.3) , FR-76-4.2% (1.2) , BA-20-4.5% (1.5) , CL-31-4.6% (1.1) MO-67-5% (4) , MC S-2510T-4.7% (3.4) Vicon NF-4.8% (11) , Losurf 300D-4.7% (6.7) FE-2A-3.7% (1.2) , BE-9-4.7% (2)		
Start Time	18:30	End Time
		20:00
Comment		
Plug and Perf: Stage #29 RIH with guns and Plug to KOP. pumped down guns at 12.9 bpm @ 4,100 Psi. @ 288 fpm, 870 LT, pumped guns to 11,450' Pulled up and got line tension and set plug @11,410'. Line tension prior to setting plug 1,290, line tension after plug set 1,120, plug set time 69 sec. POOH and perf'd at (11,400'-403') (11,325'-328') (11,250'-253'), POOH with tools, max pressure for pump down: 4,100, Max rate for pump down 12.9 bpm. Total BBIs pumped 150. POOH w/ tools. All shots fired . Drop ball & turn over to frac. To Frac Stage #29.		
Start Time	20:00	End Time
		22:00
Comment		
Frac stage #29 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 23 holes open, 724 psi perf friction, 357 psi NWB as per FracPro. 3. Stage treated well with all proppant placed. 4. Had rate fluctuate shortly after going to flush. WG-36-3.9% (68) , BC-200-4.2% (6.5) , FR-76-4.5% (1.3) , BA-20-3.5% (1.1) , MO-67-4.9% (3.8) , MC S-2510T-4.5% (3.1) Losurf 300D-4.5% (6.3) FE-2A-4.1% (1.3) , BE-9-4.1% (1.7)		
Start Time	22:00	End Time
		23:30
Comment		
Plug and Perf: Stage #30 RIH with guns and Plug to KOP. pumped down guns at 12.7 bpm @ 4,128 Psi. @ 302 fpm, 834 LT, pumped guns to 11,190' Pulled up and got line tension and set plug @11,170'. Line tension prior to setting plug 1,320, line tension after plug set 1,160, plug set time 65 sec. POOH and perf'd at (11,175'-178') (11,100'-103') (11,025'-028'), POOH with tools, max pressure for pump down: 4,128, Max rate for pump down 12.7 bpm. Total BBIs pumped 130. POOH w/ tools. All shots fired . Drop ball & turn over to frac. To Frac Stage #30.		
Start Time	23:30	End Time
		00:00
Comment		
Frac stg #30		
Report Start Date	Report End Date	24hr Activity Summary
12/5/2014	12/6/2014	Frac stgs 30,31,32,33 & 34. Perf'd stgs 31,32,33,34 & 35
Start Time	00:00	End Time
		01:30
Comment		
Frac stg #30 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 21 holes open, 861 psi perf friction, 347 psi NWB as per FracPro. 3. Had rate fluctuating from the middle of 1.5 ppg to 2.5 ppg and again during flush. 4. Cat 3/4 had trouble lining out until 2.5 ppg and gel ran heavy throughout the stage. 5. Stage treated well with all proppant placed. Ball Seat Stage Pressures and Rate: 4591 psi @ 14.9 bpm , 4319 psi Pressure before Seating , 4591 psi Pressure after Seating. WG-36-16.7% (281.8) , BC-200-4.8% (7.5) , FR-76-4.6% (1.3) , BA-20-5% (1.7) , MO-67-4.2% (3.2) , MC S-2510T-4.6% (3.2) Vicon NF-5.4% (12.2) , Losurf 300D-5.3% (Cat 3/4-28.8% (6.1) , BE-9-5% (2.1)		
Start Time	01:30	End Time
		03:30
Comment		
Plug and Perf: Stage #31 RIH with guns and Plug to KOP. pumped down guns at 13.1 bpm @ 3,950 Psi. @ 287 fpm, 880 LT, pumped guns to 10,955' Pulled up and got line tension and set plug @10,945'. Line tension prior to setting plug 1,280, line tension after plug set 1,115, plug set time 74 sec. POOH and perf'd at (10,950'-953') (10,875'-878') (10,800'-803'), POOH with tools, max pressure for pump down: 3,950, Max rate for pump down 13.1 bpm. Total BBIs pumped 82. POOH w/ tools. To Frac Stage #31.		

Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time 03:30	End Time 06:00	Comment Had to wait on stg #31 frac due to Halliburton working on horsepower. Start Frac Stage #31. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 25 holes open, 645 psi perf friction, 352 psi NWB as per FracPro. 3. Stage treated well with all proppant placed. 4. Pump operator unintentionally dropped rate just after staging to flush. Rate was completely recovered. 5. Gel ran heavy to get the correct visc. Ball Seat Stage Pressures and Rate: 4456 psi @ 14.8 bpm, 4183 psi Pressure before Seating, 4456 psi Pressure after Seating. WG-36-17.7% (292.5), BC-200-4.8% (7.6), CL-31-4.6% (1.1) MO-67-4.6% (3.7), MC S-2510T-3.7% (2.6) Vicon NF-5.2% (11.7), Losurf 300D-5.2% (7.3) FE-2A-4.8% (1.5), BE-9-4.2% (1.8)
Start Time 06:00	End Time 07:00	Comment Plug and Perf: Stage #32 RIH with guns and Plug to KOP. pumped down guns at 13.1 bpm @ 4,180 Psi, @ 258 fpm, 920 LT, pumped guns to 10,790' Pulled up and got line tension and set plug @10,756'. Line tension prior to setting plug 1,242, line tension after plug set 1,093, plug set time 40 sec. POOH and perfed at (10,725'-728') (10,675'-678') (10,578'-581'), POOH with tools, max pressure for pump down: 4,180, Max rate for pump down 13.1 bpm. Total BBIs pumped 131. POOH w/ tools. All shot fired. Shut in HCR.
Start Time 07:00	End Time 08:00	Comment Grease Frac Tree.
Start Time 08:00	End Time 10:00	Comment Start Frac Stage #32. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 25 holes open, 728 psi perf friction, 736 psi NWB as per FracPro. 3. MO-67 tote was swapped before job start. Had XL confirmed and went to sand. Lost XL towards end of 1.5 ppa stage. Increased set point and regained XL. Will check tote after job. 4. Good job execution by the crew, all sand placed. Ball Seat Stage Pressures and Rate: 4890 psi @ 15.2 bpm, 4483 psi Pressure before Seating, 4895 psi Pressure after Seating WG-36-17% (284.2), FR-76-5.7% (1.6), BA-20-4.4% (1.5), CL-31-6.4% (1.5) MO-67-9.8% (10.7), MC S-2510T-5.4% (3.7) Vicon NF-5.8% (12.8), Losurf 300D-6.1% (8.5) BE-9-3.5% (1.4)
Start Time 10:00	End Time 14:00	Comment Ran in hole W/wireline & pumped down to 10,500' and lost communication W/CCL tried a few things to get it to work with no luck. Pooh W/tools & cut off 1000' of wireline. Fixed some wiring in truck. Checked everything on surface everything working like designed.
Start Time 14:00	End Time 16:00	Comment Plug and Perf: Stage #33 RIH with guns and Plug to KOP. pumped down guns at 12.9 bpm @ 4,439 Psi, @ 256 fpm, 899 LT, pumped guns to 10,565' Pulled up and got line tension and set plug @10,550'. Line tension prior to setting plug 1,246, line tension after plug set 1,063, plug set time 50 sec. POOH and perfed at (10,525'-528') (10,455'-458') (10,385'-388'), POOH with tools, max pressure for pump down: 4,439, Max rate for pump down 12.9 bpm. Total BBIs pumped 131. POOH w/ tools. All shot fired. Drop ball & turn over to Frac.
Start Time 16:00	End Time 18:00	Comment Start Frac Stage #34. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 24 holes open, 751 psi perf friction, 740 psi NWB as per FracPro. 3. Had problems starting MO-67, dropped rate to trouble shoot. The tote was closed, re-prime the line and got going. Once good XL was established, proceeded with sand. The XL pad ran long before starting the 30/50. 4. Started to MO-67 at 1.5 gpt, pH started creeping higher during job. Backed off to a 1 gpt for the remainder of the job. 5. Overall good job execution by the crew, all sand placed. Ball Seat Stage Pressures and Rate: 4860 psi @ 14.9 bpm, 4610 psi Pressure before Seating, 4865 psi Pressure after Seating. WG-36-9.8% (183.4), BC-200-4.9% (8.5), FR-76-4.7% (1.3), BA-20-4.1% (1.5), MO-67-3.5% (3.8), MC S-2510T-4.7% (3.5) Vicon NF-4.3% (10.3), Losurf 300D-4.7% (7) FE-2A-3.6% (1.1), BE-9-2.9% (1.3)

NEWFIELD



Summary Rig Activity

Well Name: Powitch 15-13-12-3-2WB

Start Time	18:00	End Time
		19:30
Comment		
Plug and Perf: Stage #34 RIH with guns and Plug to KOP. pumped down guns at 12.8 bpm @ 4,200 Psi, @ 286 fpm, 882 LT, pumped guns to 10,355' Pulled up and got line tension and set plug @10,310'. Line tension prior to setting plug 1,250 line tension after plug set 1,110, plug set time 75 sec. POOH and perfed at (10,315'-318') (10,245'-248') (10,175'-178'), POOH with tools, max pressure for pump down: 4,200, Max rate for pump down 12.8 bpm. Total BBIs pumped 101. POOH w/ tools.		
Start Time	19:30	End Time
		21:30
Comment		
Frac stg #34 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 21 holes open, 892 psi perf friction, 28 psi NWB as per FracPro. 3. Stage went well with all proppant placed. Ball Seat Stage Pressures and Rate: 4802 psi @ 15.1 bpm , 4435 psi Pressure before Seating , 4802 psi Pressure after Seating. WG-36-17% (287.8) , BC-200-4.9% (8) , MO-67-4.4% (3.5) , MC S-2510T-4.1% (2.9) Vicon NF-4.7% (10.6) , Losurf 300D-4.4% BE-9-3.4% (1.5)		
Start Time	21:30	End Time
		23:00
Comment		
Plug and Perf: Stage #35 RIH with guns and Plug to KOP. pumped down guns at 12.8 bpm @ 4,200 Psi, @ 286 fpm, 882 LT, pumped guns to 10,355' Pulled up and got line tension and set plug @10,310'. Line tension prior to setting plug 1,250 line tension after plug set 1,110, plug set time 75 sec. POOH and perfed at (10,315'-318') (10,245'-248') (10,175'-178'), POOH with tools, max pressure for pump down: 4,200, Max rate for pump down 12.8 bpm. Total BBIs pumped 101. POOH w/ tools.		
Start Time	23:00	End Time
		00:00
Comment		
Frac stg #35		
Report Start Date	Report End Date	24hr Activity Summary
12/6/2014	12/7/2014	Frac Stgs 35,36,37,38,39,40 & 41. Perf Stgs 36,37,38,39,40 & 41. Set First kill plug.
Start Time	00:00	End Time
		01:00
Comment		
Frac Stg #35. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 22 holes open, 818 psi perf friction, 254 psi NWB as per FracPro. 3. Stage treated well with all proppant placed. 4. Had to drop a pump during flush to due to a broken pony rod. Ball Seat Stage Pressures and Rate: 4733 psi @ 15 bpm , 5380 psi Pressure before Seating , 4733 psi Pressure after Seating. WG-36-3.4% (68.2) , BC-200-5.1% (8) , MO-67-4.5% (3.5) , MC S-2510T-4.5% (3.1) Vicon NF-4.6% (10.2) , Losurf 300D-4.3% (5.9) . FE-2A-4.4% (1.3) , BE-9-2.9% (1.2)		
Start Time	01:00	End Time
		02:30
Comment		
Plug and Perf: Stage #36 RIH with guns and Plug to KOP. pumped down guns at 12.9 bpm @ 4,150 Psi, @ 308 fpm, 870 LT, pumped guns to 9,925' Pulled up and got line tension and set plug @9,910'. Line tension prior to setting plug 1,160 line tension after plug set 1,020, plug set time 56 sec. POOH and perfed at (9,858'-861') (9,797'-800') POOH with tools, max pressure for pump down: 4,150, Max rate for pump down 12.9 bpm. Total BBIs pumped 76. POOH w/ tools.		
Start Time	02:30	End Time
		05:00
Comment		
Frac stg #36. Halliburton had issues with crosslinker before going to 30/50 sand had to shut down until the issue was resolved. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 18 holes open, 1061 psi perf friction, 374 psi NWB as per FracPro. 3. Could not get crosslinker going and had issues with MO-67 during pad. Shutdown and resolved the issues prior to going to 30/50. 4. Issue was resolved in ~45 mins. 5. 30/50 ran ~10,000 lbs long out of the mover. 6. Stage treated well. Ball Seat Stage Pressures and Rate: 4540 psi @ 15.1 bpm , 4224 psi Pressure before Seating , 4540 psi Pressure after Seating WG-36-26.6% (494.9) , BC-200-5.1% (8.7) , BA-20-3.3% (1.1) , MO-67-5.1% (4.4) , MC S-2510T-4.3% (3) Losurf 300D-4.3% (6) BE-9-3.9% (1.6)		

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	05:00	End Time	07:00	Comment
				Plug and Perf: Stage #37 RIH with guns and Plug to KOP. pumped down guns at 12.3 bpm @ 4,335 Psi, @ 258 fpm, 878 LT, pumped guns to 9,690' Pulled up and got line tension and set plug @9,740'. Line tension prior to setting plug 1,178 line tension after plug set 1,050, plug set time 76 sec. POOH and perfed at (9,672'-675') (9,600'-603')(9,521'-524') POOH with tools, max pressure for pump down: 4,335, Max rate for pump down 12.3 bpm. Total BBIs pumped 77. POOH w/ tools. All shots fired. Drop ball & turn over to Frac.
Start Time	07:00	End Time	09:00	Comment
				Frac Stg #37. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 20 holes open, 867 psi perf friction, 136 psi NWB as per FracPro. 3. 20 cups 3700 CFT Protechnics tracer. WG-36-7.8% (140), BC-200-4.3% (6.8), BA-20-4.3% (1.4), MO-67-3.9% (3.1), MC S-2510T-4.2% (2.8) Vicon NF-4.2% (9.2), Losurf 300D-4.2% (5.6) BE-9-3.2% (1.3)
Start Time	09:00	End Time	10:30	Comment
				: Plug and Perf: Stage #38 RIH with guns and Plug to KOP. pumped down guns at 12.3 bpm @ 4,080 Psi, @ 252 fpm, 920 LT, pumped guns to 9,510' Pulled up and got line tension and set plug @9,490'. Line tension prior to setting plug 1,168 line tension after plug set 1,017, plug set time 46 sec. POOH and perfed at (9,441'-444') (9,366'-369')(9,290'-293') POOH with tools, max pressure for pump down: 4,080, Max rate for pump down 12.4 bpm. Total BBIs pumped 62. POOH w/ tools. All shots fired. Shut HCR.
Start Time	10:30	End Time	11:00	Comment
				Grease Frac Tree.
Start Time	11:00	End Time	12:30	Comment
				Frac stg #38. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 25 holes open, 767 psi perf friction, 556 psi NWB as per FracPro. 3. 20 cups 3900 CFT Protechnics tracer. WG-36-13.8% (232.8), BC-200-4% (6.3), FR-76-5.3% (1.4),BA-20-4.1% (1.4), CL-31-5.9% (1.4) MO-67-3.4% (2.7), MC S-2510T-4.9% (3.3) Vicon NF-3.8% (8.4), Losurf 300D-4.9% (6.7) FE-2A-13.1% (3.4), Cat 3/4-4.8% (1), BE-9-3.4% (1.4)
Start Time	12:30	End Time	14:00	Comment
				Plug and Perf: Stage #39 RIH with guns and Plug to KOP. pumped down guns at 11.8 bpm @ 4,041 Psi, @ 245 fpm, 929 LT, pumped guns to 9,250' Pulled up and got line tension and set plug @9,238'. Line tension prior to setting plug 1,222 line tension after plug set 1,042, plug set time 60 sec. POOH and perfed at (9,210'-213') (9,137'-140')(9,059'-062') POOH with tools, max pressure for pump down: 4,041, Max rate for pump down 11.8 bpm. Total BBIs pumped 48. POOH w/ tools. All shots fired. Drop ball & turn over to Frac.
Start Time	14:00	End Time	16:00	Comment
				Frac stg #39. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 27 holes open, 585 psi perf friction, 112 psi NWB as per FracPro. 3. 22 cups CFT 3900 Protechnics tracer. WG-36-7.9% (134.9), CL-31-6.5% (1.6) MO-67-2.9% (2.4), Vicon NF-4.3% (9.5), Losurf 300D-4.3% (5.8) Cat 3/4-6.7% (1.4), BE-9-4.7% (1.9)
Start Time	16:00	End Time	17:30	Comment
				Plug and Perf: Stage #40 RIH with guns and Plug to KOP. pumped down guns at 11 bpm @ 3,932 Psi, @ 248 fpm, 853 LT, pumped guns to 9,055' Pulled up and got line tension and set plug @9,020'. Line tension prior to setting plug 1,192 line tension after plug set 1,046, plug set time 24 sec. POOH and perfed at (8,979'-982') (8,904'-907')(8,828'-831') POOH with tools, max pressure for pump down: 3,932, Max rate for pump down 11 bpm. Total BBIs pumped 37. POOH w/ tools. All shots fired. Drop ball & turn over to Frac.

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time 17:30	End Time 19:30	Comment Frac stg #40. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 25 holes open, 776 psi perf friction, 279 psi NWB as per FracPro. 3. Stage went well with all proppant. WG-36-18.4% (316.2), BC-200-4.6% (7.4), BA-20-4.7% (1.6), MO-67-4.1% (3.3), MC S-2510T-4.2% (2.8) Vicon NF-4.3% (9.5), Losurf 300D-4.2% (5.6). BE-9-4.8% (1.9)
Start Time 19:30	End Time 21:00	Comment Plug and Perf: Stage #41 RIH with guns and Plug to KOP. pumped down guns at 12 bpm @ 3,660 Psi, @ 260 fpm, 960 LT, pumped guns to 8,753' Pulled up and got line tension and set plug @ 8,776'. Line tension prior to setting plug 1,190 line tension after plug set 1,040, plug set time 81 sec. POOH and perfed at (8,748'-751') (8,673'-676')(8,612'-615') POOH with tools, max pressure for pump down: 3,660, Max rate for pump down 12 bpm. Total BBIs pumped 34. POOH w/ tools.
Start Time 21:00	End Time 22:45	Comment Frac Stg #41. 1. Global Kick Outs set at 9500 psi. Pressure tested to 10500 psi. Job pumped Produced Water. 2. Calculated 23 holes open, 738 psi perf friction, 219 psi NWB as per FracPro. 3. 100 Mesh emptied out late. 4. Lost prime to the blender during flush. Reduced rate to alleviate issue and successfully flush the well. Ball Seat Stage Pressures and Rate: 4166 psi @ 15.3 bpm , 4013 psi Pressure before Seating , 4166 psi Pressure after Seating. WG-36-29.7% (485.4), BC-200-5% (7.9), FR-76-4.1% (1), BA-20-4.1% (1.3), MC S-2510T-4.3% (2.8) Vicon NF-4.3% (9.2), Losurf 300D-4.9% (6.4). FE-2A-4.6% (1.2), BE-9-3.7% (1.5)
Start Time 22:45	End Time 00:00	Comment First kill plug is set at 7,930'
Report Start Date 12/7/2014	Report End Date 12/8/2014	24hr Activity Summary Finished up the fracs. RD frac and W/L equipment and ND frac stack and NU BOP stack. Pressure test stack and flowback iron to NFX testing procedures.
Start Time 00:00	End Time 01:30	Comment Set Second Kill plug at 7,890'
Start Time 01:30	End Time 06:00	Comment RD W/L and Frac Equipment and MOL.
Start Time 06:00	End Time 11:00	Comment Clean up location & move off tanks that are not needed. Level out location.
Start Time 11:00	End Time 15:00	Comment ND frac tree & NU BOPS & night cap on top.
Start Time 15:00	End Time 17:00	Comment Testing BOPS & accumulator as per Newfield procedures 250 low 10K high.
Start Time 17:00	End Time 00:00	Comment Wait on daylight.
Report Start Date 12/8/2014	Report End Date 12/9/2014	24hr Activity Summary RU Snubbing unit and WOR and all the equipment on location to do the drillout.
Start Time 00:00	End Time 07:00	Comment Wait on daylight.
Start Time 07:00	End Time 10:00	Comment MIRU WOR
Start Time 10:00	End Time 14:00	Comment MIRU Snub unit
Start Time 14:00	End Time 18:00	Comment Pressure test snub unit as per Newfield's pressure testing Procedures. Test annular to 5K. Spot in Weatherford pump & lines.
Start Time 18:00	End Time 00:00	Comment Finish RU Snubbing unit and WOR equipment.
Report Start Date 12/9/2014	Report End Date 12/10/2014	24hr Activity Summary RIH with PH-6 Workstring and drill out the two kill plugs.

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	00:00	End Time 04:00
		Comment Finish RU Snubbing unit and WOR equipment.
Start Time	04:00	End Time 06:00
		Comment Snubbing unit has blown two hydraulic fitting.
Start Time	06:00	End Time 17:00
		Comment PU BHA. BHA is as follows from bottom to top: Concave Mill (4.625" OD x 1.79'), 2 7/8" ECTD Motor (2.875" OD x 12.00'), Circ Sub (2.875" OD x .750" ID x 0.69'), Dual Flapper (2.875" OD x 1.00" ID x 1.28'), Pup Jt. (2-3/8" x 9.82'), X-Over Sub (2.906" OD x 1.560" ID x 1.13') RN-Nipple (2.906" OD x 1.560" ID x 0.75'). For a total length of 27.64'. PU 256 jts 2-3/8" 5.96# P110 PH6 tbq. Fill tbq every 25 jts. Tag kill plug #2 at 7904' by tbq tally. 14' deeper than WL. Fill WS.
Start Time	17:00	End Time 20:00
		Comment RU power swivel. Power swivel is RU on jt 256 2-3/8" 5.96# P110 PH6 tbq. Tag kill plug #2 at 7904' by tbq tally. 14' deeper than WL. We will break circulation and start to drill up the first kill plug.
Start Time	20:00	End Time 00:00
		Comment 21:06-Tagged First kill plug at 7904' on jt #256, Up weight 53k, down weight 50k, neutral 52. 1750 free torque, 2100 drill torque. WOB: 5-6pts, RPM @ 60-75. 2 bbl in @ 1750psi, 1.5bbl out @ 0psi on full open " choke. 29 minutes to drill plug. Pumped 70bbbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. 22:06-Tagged Second kill plug at 7,944' on jt #258, Up weight 53k, down weight 50k, neutral 52. 1200 free torque, 2350 drill torque. WOB: 5-6pts, RPM @ 60-75. 2 bbl in @ 1200psi, 2.1bbl out @ 2500psi on 18/64 " choke. 54 minutes to drill plug. Pumped 110bbbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. 23:00- Pumping a bottoms up here 135bbbls.
Report Start Date	Report End Date	24hr Activity Summary
12/10/2014	12/11/2014	Drilled out Frac Plugs 41,40,39,38,37,36,35,34,33,32 & 31
Start Time	00:00	End Time 02:30
		Comment Had to PU 26 jts to get to the first flow through frac plug.
Start Time	02:30	End Time 03:30
		Comment 02:43-Tagged Frac plug #41 at 8,788' on jt #285 8' out, Up weight 43k, down weight 38k, neutral 41. 3400 free torque, 4100 drill torque. WOB: 5-6pts, RPM @ 60-75. 2 bbl in @ 3400psi, 2.3bbl out @ 2350psi on 22/64 " choke. 21 minutes to drill plug. Pumped 57bbbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	03:30	End Time 06:00
		Comment 04:28-Tagged Frac plug #40 at 9,032' on jt #293 9' out, Up weight 43k, down weight 38k, neutral 41. 3300 free torque, 3900 drill torque. WOB: 5-6pts, RPM @ 60-75. 2 bbl in @ 3300psi, 2.4bbl out @ 2400psi on 25/64 " choke. 20 minutes to drill plug. Pumped 55bbbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	06:00	End Time 08:00
		Comment 06:00-Tagged Frac plug #40 at 9,249' on jt #300 with 7' out, Up weight 46k, down weight 40k, neutral 43k. 3500 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500psi, 2. bbl out @ 2400 psi on 22/64 " choke. Well head pressure 2300 psi. 37 minutes to drill plug. Pumped 135 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. Circulated 20 minutes while thawing out torq gauge to driller's stand.
Start Time	08:00	End Time 10:00
		Comment 08:10-Tagged Frac plug #38 at 9,500' on jt #308 with 2' out, Up weight 46k, down weight 40k, neutral 43k. 3300 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3300 psi, 2. bbl out @ 2400 psi on 20/64 " choke. Well head pressure 2500 psi. 58 minutes to drill plug. Pumped 112 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	End Time	Comment
10:00	11:00	09:57-Tagged Frac plug #37 at 9,749' on jt #317 with 29' out, Up weight 46k, down weight 40k, neutral 43k. 3300 free torque, 3600 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3300 psi, 2. bbl out @ 2400 psi on 20/64 " choke. Well head pressure 2500 psi. 37 minutes to drill plug. Pumped 90 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
11:00	12:00	Circulate 165 bbl bottoms up.
Start Time	End Time	Comment
12:00	13:00	12:32-Tagged Frac plug #36 at 9,923' on jt #322 with 10' out, Up weight 45k, down weight 39k, neutral 42k. 3800 free torque, 4500 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3800 psi, 2. bbl out @ 2500 psi on 18/64 " choke. Well head pressure 2500 psi. 35 minutes to drill plug. Pumped 76 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
13:00	14:00	13:30-Tagged Frac plug #35 at 10,141' on jt #329 with 7' out, Up weight 45k, down weight 39k, neutral 42k. 3400 free torque, 3600 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3400 psi, 2. bbl out @ 2500 psi on 20/64 " choke. Well head pressure 2500 psi. 46 minutes to drill plug. Pumped 105 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
14:00	17:00	Wash 7 jts sand to plug circulating 20 bbl each jt. 16:34-Tagged Frac plug #34 at 10,352' on jt #336 with 11' out, Up weight 45k, down weight 40k, neutral 42k. 3500 free torque, 3600 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.5 bbl out @ 2400 psi on 27/64 " choke. Well head pressure 2500 psi. 25 minutes to drill plug. Pumped 62 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
17:00	19:00	Circulate 195 bbl bottoms up.
Start Time	End Time	Comment
19:00	20:30	19:41-Tagged Frac plug #33 at 10,559' on jt #343 20' out, Up weight 45k, down weight 40k, neutral 42. 3800 free torque, 4100 drill torque. WOB: 5-6pts, RPM @ 60-75. 2 bbl in @ 3800psi, 2.4bbl out @ 2350psi on 21/64 "choke 31 minutes to drill plug. Pumped 69bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
20:30	22:30	21:44-Tagged Frac plug #32 at 10,765' on jt #350 29' out, We washed 70' of sand to get to the plug. Up weight 45k, down weight 40k, neutral 42k. 3800 free torque, 4100 drill torque. WOB: 5-6pts, RPM @ 60-75. 2 bbl in @ 3800psi, 2.4bbl out @ 2400psi on 21/64 "choke 31 minutes to drill plug. Pumped 82bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
22:30	23:00	Circulate 70 bbl while Nabors has to fix the drill line so we are goking to pump a bottoms up while the y fix the drill line.
Start Time	End Time	Comment
23:00	00:00	Washed two joints of sand.
Report Start Date	Report End Date	24hr Activity Summary
12/11/2014	12/12/2014	Drilled up Frac plugs 30,29,28,27,26,25,24,23,22,21 & 20
Start Time	End Time	Comment
00:00	01:30	00:53-Tagged Frac plug #31 at 10,987' on jt #357 20' out, We washed 222' of sand to get to the plug. Up weight 45k, down weight 40k, neutral 42k. 3600 free torque, 4000 drill torque. WOB: 5-6pts, RPM @ 60-75. 2 bbl in @ 3600psi, 2.7bbl out @ 2400psi on 23/64 "choke 16 minutes to drill plug. Pumped 36bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. We are going to pump a bottoms up here.
Start Time	End Time	Comment
01:30	03:00	Pump a bootoms up at 210bbls.

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	03:00	End Time	04:30	Comment
				03:50-Tagged Frac plug #30 at 11,203' on jt #364 15' out, Up weight 45k, down weight 40k, neutral 42k. 3700 free torque, 4100 drill torque. WOB: 5-6pts, RPM @ 60-75. 2 bbl in @ 3700psi, 2.6bbl out @ 2450psi on 23/64 "choke 33 minutes to drill plug. Pumped 74bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	04:30	End Time	06:30	Comment
				Sand-circulate every jt down to plug. 05:56-Tagged Frac plug #29 at 11,449' on jt #372 with 11' out, Up weight 45k, down weight 39k, neutral 42k. 3600 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3600 psi, 2.4 bbl out @ 2400 psi on 19/64 " choke. Well head pressure 2500 psi. 18 minutes to drill plug. Pumped 40 bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	06:30	End Time	07:45	Comment
				0705-Tagged Frac plug #28 at 11,635' on jt #378 with 18' out, Up weight 45k, down weight 39k, neutral 42k. 3600 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3700 psi, 2.5 bbl out @ 2400 psi on 19/64 " choke. Well head pressure 2500 psi. 35 minutes to drill plug. Pumped 75 bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	07:45	End Time	09:15	Comment
				08:28-Tagged Frac plug #27 at 11,841' on jt #385 with 27' out, Up weight 45k, down weight 39k, neutral 42k. 3500 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.4 bbl out @ 2400 psi on 19/64 " choke. Well head pressure 2500 psi. 36 minutes to drill plug. Pumped 90 bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep
Start Time	09:15	End Time	10:30	Comment
				09:53-Tagged Frac plug #26 at 12,015' on jt #390 with 4' out, Up weight 45k, down weight 39k, neutral 42k. 3500 free torque, 4300 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.4 bbl out @ 2400 psi on 20/64 " choke. Well head pressure 2500 psi. 27 minutes to drill plug. Pumped 73 bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	10:30	End Time	12:30	Comment
				Circulate 240 bbl bottoms up.
Start Time	12:30	End Time	14:15	Comment
				14:15-Tagged Frac plug #25 at 12,337' on jt #401 with 20' out, Up weight 47k, down weight 40k, neutral 43k. 3600 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3600 psi, 2.3 bbl out @ 2300 psi on 20/64 " choke. Well head pressure 2400 psi. 13 minutes to drill plug. Pumped 52 bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	14:15	End Time	15:30	Comment
				15:30-Tagged Frac plug #24 at 12,477' on jt #405 with 3' out, Up weight 47k, down weight 40k, neutral 43k. 3700 free torque, 4100 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3700 psi, 2.3 bbl out @ 2300 psi on 22/64 " choke. Well head pressure 2400 psi. 19 minutes to drill plug. Pumped 56 bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	15:30	End Time	17:00	Comment
				17:05-Tagged Frac plug #23 at 12,716' on jt #413 with 10' out, Up weight 47k, down weight 40k, neutral 43k. 3500 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.4 bbl out @ 2400 psi on 21/64 " choke. Well head pressure 2500 psi. 15 minutes to drill plug. Pumped 38 bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	17:00	End Time	19:00	Comment
				18:25-Tagged Frac plug #22 at 12,944' on jt #421 with 28' out, Up weight 46k, down weight 38k, neutral 41k. 3600 free torque, 4200 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3600 psi, 2.3bbl out @ 2350 psi on 19/64 " choke 23 minutes to drill plug. Pumped 55 bbbs water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	19:00	End Time	20:30	Comment
				19:27-Tagged Frac plug #21 at 13,169' on jt #428 with 19' out, Up weight 46k, down weight 38k, neutral 41k. 3400 free torque, 4200 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3400 psi, 2.8bbl out @ 2300 psi on 17/64 " choke 32 minutes to drill plug. Pumped 69 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. We are going to pump a bottoms up here of 260bbls.
Start Time	20:30	End Time	22:30	Comment
				Pumped a bottoms up of 260bbls
Start Time	22:30	End Time	23:30	Comment
				22:40-Tagged Frac plug #20 at 13,403' on jt #435 with 3' out, Up weight 46k, down weight 38k, neutral 41k. 3700 free torque, 4000 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3700 psi, 2.3bbl out @ 2400 psi on 17/64 " choke 26 minutes to drill plug. Pumped 67 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	23:30	End Time	00:00	Comment
				PU tbg to get down to Frac plug #19.
Report Start Date	Report End Date	24hr Activity Summary		
12/12/2014	12/13/2014	Drilled out frac plugs 19,18,17,16,15,14,13,12,11,10,9,8,7 & 6		
Start Time	00:00	End Time	00:30	Comment
				22:40-Tagged Frac plug #20 at 13,403' on jt #435 with 3' out, Up weight 46k, down weight 38k, neutral 41k. 3700 free torque, 4000 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3700 psi, 2.3bbl out @ 2400 psi on 17/64 " choke 26 minutes to drill plug. Pumped 67 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	00:30	End Time	04:00	Comment
				01:05-Tagged Frac plug #18 at 13,880' on jt #451 with 15' out, Up weight 46k, down weight 38k, neutral 41k. 3400 free torque, 4000 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3400 psi, 2.3bbl out @ 2200 psi on 19/64"choke 30 minutes to drill plug. Pumped 75 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
				02:13-Tagged Frac plug #17 at 14,094' on jt #458 with 16' out, Up weight 46k, down weight 38k, neutral 41k. 3400 free torque, 4000 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3400 psi, 2.1bbl out @ 2325 psi on 17/64"choke 33 minutes to drill plug. Pumped 62 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	04:00	End Time	05:30	Comment
				04:10-Tagged Frac plug #16 at 14,334' on jt #466 with 22' out, Up weight 46k, down weight 38k, neutral 41k. 3400 free torque, 4000 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3400 psi, 2.3bbl out @ 2400 psi on 17/64"choke 28 minutes to drill plug. Pumped 64 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. We are going to pump a bottoms up here of 280bbls.
Start Time	05:30	End Time	07:00	Comment
				Circulate 280 bbl bottoms up.
Start Time	07:00	End Time	08:00	Comment
				07:38-Tagged Frac plug #15 at 4,555' on jt #473 with 16' out, Up weight 50k, down weight 38k, neutral 43k. 3500 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.1 bbl out @ 2400 psi on 22/64 " choke. Well head pressure 2500 psi. 36 minutes to drill plug. Pumped 83 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep
Start Time	08:00	End Time	10:00	Comment
				09:37-Tagged Frac plug #14 at 14,800' on jt #481 with 17' out, Up weight 50k, down weight 38k, neutral 43k. 3500 free torque, 4100 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.3 bbl out @ 2300 psi on 22/64 " choke. Well head pressure 2500 psi. 14 minutes to drill plug. Pumped 42 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	End Time	Comment
10:00	11:15	Pump 5 gal POP. 10:43-Tagged Frac plug #13 at 15,016' on jt #488 with 16' out, Up weight 50k, down weight 38k, neutral 43k. 3500 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.5 bbl out @ 2400 psi on 23/64 " choke. Well head pressure 2500 psi. 27 minutes to drill plug. Pumped 61 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep
Start Time	End Time	Comment
11:15	12:15	12:43-Tagged Frac plug #12 at 15,244' on jt #495 with 4' out, Up weight 50k, down weight 38k, neutral 43k. 4000 free torque, 4500 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 4000 psi, 2.4 bbl out @ 2200 psi on 23/64 " choke. Well head pressure 2400 psi. 19 minutes to drill plug. Pumped 47 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
12:15	13:15	13:40-Tagged Frac plug #11 at 15,437' on jt #502 with 26' out, Up weight 50k, down weight 38k, neutral 43k. 3500 free torque, 4100 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.5 bbl out @ 2200 psi on 23/64 " choke. Well head pressure 2400 psi. 31 minutes to drill plug. Pumped 62 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
13:15	15:15	Circulate 280 bbl bottoms up
Start Time	End Time	Comment
15:15	17:30	16:58-Tagged Frac plug #10 at 15,677' on jt #509 with 7' out, Up weight 50k, down weight 38k, neutral 43k. 3500 free torque, 4200 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.1 bbl out @ 2300 psi on 21/64 " choke. Well head pressure 2400 psi. 25 minutes to drill plug. Pumped 59 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
17:30	20:30	18:31-Tagged Frac plug #9 at 16,000' on jt #520 with 16' out, Up weight 50k, down weight 38k, neutral 43k. 3500 free torque, 4000 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3500 psi, 2.5 bbl out @ 2400 psi on 17/64 " choke. Well head pressure 2400 psi. 40 minutes to drill plug. Pumped 89 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. 20:12-Tagged Frac plug #8 at 16,173' on jt #526 with 27' out, Up weight 50k, down weight 38k, neutral 43k. 3500 free torque, 4000 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3500 psi, 2.3 bbl out @ 2400 psi on 16/64 " choke. Well head pressure 2400 psi. 18 minutes to drill plug. Pumped 47 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	End Time	Comment
20:30	23:00	21:03-Tagged Frac plug #7 at 16,343' on jt #5310 with 11' out, Up weight 50k, down weight 38k, neutral 43k. 3600 free torque, 4000 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3600 psi, 2.0 bbl out @ 2300 psi on 17/64 " choke. Well head pressure 2300 psi. 22 minutes to drill plug. Pumped 46 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. 22:03-Tagged Frac plug #6 at 16,553' on jt #538 with 16' out, Up weight 50k, down weight 38k, neutral 43k. 3900 free torque, 4600 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3900 psi, 2.30 bbl out @ 2300 psi on 17/64 " choke. Well head pressure 2300 psi. 34 minutes to drill plug. Pumped 76 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. We are pumping a bottoms up here 330bbls.
Start Time	End Time	Comment
23:00	00:00	We are pumping a bottoms up here 330bbls.
Report Start Date	Report End Date	24hr Activity Summary
12/13/2014	12/14/2014	
Start Time	End Time	Comment
00:00	01:30	We are done pumping a bottoms up here at 16,553' on jt #538 330bbls.

NEWFIELD



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time	01:30	End Time	03:30	Comment
				01:54-Tagged Frac plug #5 at 16,761' on jt #545 with 23' out, Up weight 50k, down weight 38k, neutral 43k. 3800 free torque, 4300 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3800 psi, 2.5 bbl out @ 2375 psi on 17/64 " choke. Well head pressure 2375 psi. 31 minutes to drill plug. Pumped 72 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
				02:58-Tagged Frac plug #4 at 16,973' on jt #552 with 26' out, Up weight 50k, down weight 38k, neutral 43k. 3700 free torque, 4300 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3700 psi, 2.4 bbl out @ 2300 psi on 18/64 " choke. Well head pressure 2300 psi. 47 minutes to drill plug. Pumped 100 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	03:30	End Time	05:00	Comment
				04:28-Tagged Frac plug #3 at 17,128' on jt #557 with 24' out, Up weight 50k, down weight 38k, neutral 43k. 3800 free torque, 4300 drill torque. WOB: 5-6 pts, RPM 90. 2 bbl in @ 3800 psi, 2.2 bbl out @ 2350 psi on 17/64 " choke. Well head pressure 2350 psi. 14 minutes to drill plug. Pumped 35 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep. Washed sand from frac plug #4 to frac plug #3 we will pump 60 extra bbls here to get the sand way up above us.
Start Time	05:00	End Time	07:00	Comment
				Circulate 300 bbl bottoms up.
Start Time	07:00	End Time	08:00	Comment
				07:36-Tagged Frac plug #2 at 17,319' on jt #563 with 17' out, Up weight 57k, down weight 38k, neutral 43k. 3500 free torque, 4100 drill torque. WOB: 4 pts, RPM 90. 2 bbl in @ 3500 psi, 2.5 bbl out @ 2400 psi on 18/64 " choke. Well head pressure 2500 psi. 35 minutes to drill plug. Pumped 87 bbls water with .5 gal of FR-76 to 1000gals. Pumped 10 bbl gel sweep.
Start Time	08:00	End Time	09:00	Comment
				Clean out to 17,473' on jt #576.
Start Time	09:00	End Time	14:15	Comment
				Pump 10 bbl sweep, 20 bbl spacer, then 10 bbl sweep. Circulate 750 bbl (2.5 times bottoms up).
Start Time	14:15	End Time	18:00	Comment
				SIP 2400 psi. Swivel 10 jts OH. Tie back swivel. LD 2-3/8" WS.
Start Time	18:00	End Time	23:00	Comment
				Con't LD 2 3/8" tbg. With 319 jts of 2 3/8" PH-6 tbg on the ground stop and get ready to circulate bottoms up. EOT @8366'
Start Time	23:00	End Time	00:00	Comment
				Get good jt count on tbg. RU power swivel to circulate bottoms up.
Report Start Date	Report End Date	24hr Activity Summary		
12/14/2014	12/15/2014	Continue the drill out to PBTD. POOH LD tbg.		
Start Time	00:00	End Time	02:00	Comment
				Circulated 180 bbls bottoms up with two 12 bbl sweeps 20 bbls apart. EOT @8366'.
Start Time	02:00	End Time	03:00	Comment
				RD power swivel & rack out. Pickle pumps & flowback iron.
Start Time	03:00	End Time	06:00	Comment
				Continue to LD 2 3/8" 5.95# PH-6 tbg. There is 460 jts out 130 jts in the hole putting EOT @4028'. Shut in & secure well.
Start Time	06:00	End Time	07:30	Comment
				Wait for day light to snub out.
Start Time	07:30	End Time	14:30	Comment
				Finish laying down WS with rig assist snubbing unit. LD BHA. Secure well.
Start Time	14:30	End Time	20:30	Comment
				Change out pipe rams.
Start Time	20:30	End Time	22:30	Comment
				Test BOP stack & snub unit to Newfields testing Procedures.



Summary Rig Activity

Well Name: Powvitch 15-13-12-3-2WB

Start Time			22:30	End Time		00:00	Comment		SDFN & wait on daylights.
Report Start Date		Report End Date		24hr Activity Summary					
12/15/2014		12/16/2014		Snub WS out of hole. PUMU production string & RIH.					
Start Time			00:00	End Time		07:00	Comment		
Start Time			07:00	End Time		08:30	SDFN & secure well. Wait on daylights.		
Start Time			08:30	End Time		16:30	Comment		
Start Time			16:30	End Time		20:00	PU 2-7/8" notched collar (3.688" OD x 3.00" ID x 0.44' L), 2-7/8" x 2.09' pup jt, 2-7/8" x 4.13' perf pup, 10K ceramic burst disc (3.688" OD x 2.441" ID x 0.78' L), 2-7/8" TUBAL gauge (3.600" OD x 2.200" ID x 3.61' L) 1 jt 2 -7/8" 6.5# EUE 8rd L-80 tbg, 2-7/8" x 2.313" ID x 1.20'L X-nipple. Equalize pressure in BOP stack and open blind/shears and HCR valve. Snub -7/8" 6.5# EUE 8rd L-80 tbg IH.		
Start Time			20:00	End Time		22:00	Comment		
Start Time			22:00	End Time		23:00	RIH on elevators W/111 jts of 2 7/8" 6.5# EUE tbg filling every 25 jts. To get 2-7/8" notched collar (3.688" OD x 3.00" ID x 0.44' L), 2-7/8" x 2.09' pup jt, 2-7/8" x 4.13' perf pup, 10K ceramic burst disc (3.688" OD x 2.441" ID x 0.78' L), 2-7/8" TUBAL gauge (3.600" OD x 2.200" ID x 3.61' L) 1 jt 2-7/8" 6.5# EUE 8rd L-80 tbg, 2-7/8" x 2.313" ID x 1.20'L X-nipple, 140 jts 2 7/8" L-80 6.5# tbg.		
Start Time			23:00	End Time		00:00	Comment		
Report Start Date		Report End Date		24hr Activity Summary					
12/16/2014		12/17/2014		PUMU production string & RIH.					
Start Time			00:00	End Time		04:00	Comment		
Start Time			04:00	End Time		05:00	RD snub unit & spools		
Start Time			05:00	End Time		06:00	Comment		
Start Time			06:00	End Time		07:30	ND BOP stack & HCR valve.		
Start Time			07:30	End Time		09:30	Comment		
Start Time			09:30	End Time		10:15	NU Production tree		
Start Time			10:15	End Time		18:00	Comment		
Start Time			18:00	End Time		00:00	Wait on daylight.		
Start Time			00:00	End Time		04:00	Comment		
Start Time			04:00	End Time		05:00	RDMO WOR,		
Start Time			05:00	End Time		06:00	Comment		
Start Time			06:00	End Time		07:30	POP well at 10:15 AM and turn over to production. Pumped 90 bbls water down tubing and rupture disc, (two tbg volumes), Disc ruptured at 3,000 psi,		
Start Time			07:30	End Time		09:30	Clean location and release equipment.		
Start Time			09:30	End Time		10:15	Comment		
Start Time			10:15	End Time		18:00	Shut down for night		
Start Time			18:00	End Time		00:00			

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9			
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-H62-6173			
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE			
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME:			
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: POWVITCH 15-13-12-3-2WB			
PHONE NUMBER: 435 646-4825 Ext		9. API NUMBER: 43013519420000			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0075 FNL 2332 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 24 Township: 03.0S Range: 02.0W Meridian: U		9. FIELD and POOL or WILDCAT: NORTH MYTON BENCH			
		COUNTY: DUCHESNE			
		STATE: UTAH			
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA					
TYPE OF SUBMISSION	TYPE OF ACTION				
<input checked="" type="checkbox"/> NOTICE OF INTENT Approximate date work will start: 11/23/2015 <input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <input type="checkbox"/> SPUD REPORT Date of Spud: <input type="checkbox"/> DRILLING REPORT Report Date:	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER </td> <td style="width: 33%; vertical-align: top;"> <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION </td> </tr> </table>		<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION
<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input checked="" type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> APD EXTENSION			
OTHER: <input style="width: 100px;" type="text" value="Well Lease Number"/>					
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. <div style="display: flex; justify-content: space-between;"> <div style="width: 60%;"> <p>It has been determined by the Bureau of Land Management that the correct lease number for the Powvitch 15-13-12-3-2WB is 14-20-H62-6173.</p> </div> <div style="width: 35%; text-align: center;"> <p>Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY December 01, 2015</p> </div> </div>					
NAME (PLEASE PRINT) Mandie Crozier	PHONE NUMBER 435 646-4825	TITLE Regulatory Tech			
SIGNATURE N/A	DATE 11/23/2015				

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: 14-20-H62-6173
1. TYPE OF WELL Oil Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: UTE
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME:
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: POWVITCH 15-13-12-3-2WB
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0075 FNL 2332 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWNE Section: 24 Township: 03.0S Range: 02.0W Meridian: U		9. API NUMBER: 43013519420000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: NORTH MYTON BENCH
COUNTY: DUCHESNE		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 10/28/2014	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input checked="" type="checkbox"/> OTHER	
	OTHER: Daily Drilling Reports	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. As per our conversation with Dustin Doucet, attached find the Daily Drilling Reports for the above mentioned well.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY January 22, 2016		
NAME (PLEASE PRINT) Mandie Crozier	PHONE NUMBER 435 646-4825	TITLE Regulatory Tech
SIGNATURE N/A	DATE 1/21/2016	

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Job Category	Job Start Date	Job End Date

Daily Operations

Report Start Date 9/14/2014	Report End Date 9/15/2014	24hr Activity Summary Set 60' of 20" conductor pipe.
Start Time 00:00	End Time 00:00	Comment Pete Martin Rig #16 spudded 26" hole on 09/14/2014 and drilled to 60' GL. Set 20", 52.78# (0.250" wall), SA53B conductor pipe at 60' GL and cemented to surface with Redi Mix. Kylan Cook notified UDOGM and BLM by e-mail @ 09:30 AM on 09/12/2014 to spud conductor hole on 09/13/2014. Spud date pushed back due to availability of bucket rig.
Report Start Date 9/15/2014	Report End Date 9/16/2014	24hr Activity Summary MIRU Pro Petro Rig #10. Pick up directional BHA. Trip in hole to 60' GL. Drill from 60' GL to 90' GL. Change packing in top drive.
Start Time 08:00	End Time 22:00	Comment MIRU Pro Petro Rig #10.
Start Time 22:00	End Time 23:00	Comment Start picking up directional BHA. Trip in hole to 60' GL.
Start Time 23:00	End Time 23:30	Comment Spud 17 1/2" hole @ 23:00 PM on 09/15/2014. Drill from 60' GL to 90' GL while picking up directional tools.
Start Time 23:30	End Time 00:00	Comment Change packing in top drive.
Report Start Date 9/16/2014	Report End Date 9/17/2014	24hr Activity Summary Change packing in top drive. Drill from 90' GL to 650' GL. Repair leak in hydraulic hard line. Drill from 650' GL to 1010' GL.
Start Time 00:00	End Time 02:00	Comment Change packing in top drive.
Start Time 02:00	End Time 03:00	Comment Pick up directional tools.
Start Time 03:00	End Time 04:00	Comment Drill from 90' GL to 150' GL while picking up directional BHA.
Start Time 04:00	End Time 04:30	Comment Install rotating head rubber.
Start Time 04:30	End Time 11:30	Comment Drill from 150' GL to 580' GL while picking up directional BHA.
Start Time 11:30	End Time 12:00	Comment Change rubber size in rotating head.
Start Time 12:00	End Time 13:30	Comment Drill from 580' GL to 650' GL.
Start Time 13:30	End Time 16:30	Comment Repair leak in hydraulic hard line.
Start Time 16:30	End Time 00:00	Comment Drill from 650' GL to 1010' GL.
Report Start Date 9/17/2014	Report End Date 9/18/2014	24hr Activity Summary Drill from 1010' GL to TD @ 1650' GL. Circulate. Trip out of hole to run surface casing.
Start Time 00:00	End Time 13:30	Comment Drill from 1010' GL to 1520' GL.
Start Time 13:30	End Time 14:00	Comment Change swab in mud pump.
Start Time 14:00	End Time 16:00	Comment Drill from 1520' GL to 1610' GL.

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	End Time	Comment
16:00	18:00	Repair table wrench.
Start Time	End Time	Comment
18:00	18:30	Drill from 1610' GL to TD @ 1650' GL. TD 17 1/2" hole @ 18:30 PM on 09/17/2014.
Start Time	End Time	Comment
18:30	20:00	Circulate to trip out of hole.
Start Time	End Time	Comment
20:00	00:00	Trip out of hole to run surface casing.
Report Start Date	Report End Date	24hr Activity Summary
9/18/2014	9/19/2014	Run surface casing. Circulate. Weld top cap. Cement surface casing. Wait on cement, clean pits, and rig down. Release rig.
Start Time	End Time	Comment
00:00	01:00	Rig up to run surface casing. No water flow.
Start Time	End Time	Comment
01:00	07:30	Run 39 joints (1637.19') of 13 3/8", 54.5#, J-55, BT&C casing with Top-Co guide shoe and float collar. 14 centralizers spaced 10' from the shoe, on top of joints #2 & #3 then every 3rd collar to surface. Landed @ 1637.19' GL, Float Collar @ 1593.97' GL. Had to wash through intermittent tight spots from 1250' GL.
Start Time	End Time	Comment
07:30	08:30	Circulate with casing on bottom.
Start Time	End Time	Comment
08:30	09:30	Weld top cap from casing to conductor pipe.
Start Time	End Time	Comment
09:30	10:00	Circulate casing with rig pump. Rig up Pro Petro Cementers.
Start Time	End Time	Comment
10:00	10:30	Start Cement: 60 bbls into lead cement lost hydraulic hose on pump truck.
Start Time	End Time	Comment
10:30	12:00	Shut down pump truck. Circulate cement out of hole with rig pump while waiting for another pump truck from Vernal.
Start Time	End Time	Comment
12:00	13:30	Cement Job: Pumped 20 bbls fresh water & 40 bbls gelled water flush ahead of cement. Lead: Mixed and pumped 416 sacks (212 bbls) of Type V Cement with 16% Gel, 10 #/sk Gilsonite, 2#/sk Gr3, 3% Salt, and 1/4 #/sk Flocele. Mixed cement @ 12.0 ppg with yield of 2.86 cf/sk. Tail: Mixed and pumped 675 sacks (138 bbls) of Premium Class G Cement with 2% CaCl ₂ , and 1/4 #/sk Flocele. Mixed cement @ 15.8 ppg with yield of 1.15 cf/sk. Displaced cement with 245 bbls fresh water. Bumped plug with 1000# @ 13:36 PM on 09/18/2014. Floats held. 40 bbls cement to surface. Shut in well after pumping stopped. Kylan Cook notified UDOGM and BLM of the surface casing & cement job via e-mail on 09/16/2014 @ 22:50 PM.
Start Time	End Time	Comment
13:30	21:30	Wait on cement, clean pits, and rig down. Release rig @ 21:30 PM on 09/18/2014.
Report Start Date	Report End Date	24hr Activity Summary
9/20/2014	9/21/2014	Finish preparation of location for drilling rig.

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time 00:00	End Time 00:00	Comment 09/19/2014 - Drill Mouse Hole. 09/20/2014 - Final blade location. 09/21/2014 - Weld on Wellhead. 09/22/2014 - Cement cellar floor up to the top of base plate on wellhead. SURFACE HOLE DIRECTIONAL SURVEY DEPTHS ARE GROUND LEVEL. Location is ready for drilling rig.
Report Start Date 9/21/2014	Report End Date 9/22/2014	24hr Activity Summary Lay down top drive, tds remove pipe wrangler, prepare rig for rig move
Start Time 06:00	End Time 00:00	Comment (Start) Cleared rig floor of tools & mats. R/D Service Loop and Kelly Hose. Removed Service Loop Cover. Hung Top Drive. Slipped Drilling Line on drum. L/D Mousehole. Disconnect Becket from Blocks. Lowered Top Drive to Rig Floor. Rig Down Standpipe & Manifold, Mud Tanks and hoses, Prep ST-80,VFD House, Pull service loops, Take Top Drive offset on racks, Top drive on Ground @ 16:30, Rig up trac cart, rig down pipe wrangler, rig down TDS trac. Two swampers, 2 bed trucks, 1 forklift, 1 truck pusher, 1 crane, 3 riggers, 1 operator. Arrived on location @ 15:30. J.D. Services shut down @19:00.
Report Start Date 9/22/2014	Report End Date 9/23/2014	24hr Activity Summary Rig down & move out
Start Time 00:00	End Time 06:00	Comment Operations suspended for the night. Crews working days only for rig move.
Start Time 06:00	End Time 18:00	Comment Blow down water lines & Hydro matic, R/D water system, Totco lines, Atuo driller, Electrical lines, Prep floor for laying down derrick. Remove ait tuggers & Floor plates, Hang kelly hose, Lay derrick over on stand @ 08:30, Chain blocks down, Unbridle, Unstring, Split compoundUn bolt drawworks and turn buckles, Take derrick off floor & Set on pipe racks, Load out mud pumps & Mud tanks, Parts house, Light plants, Change house, Koomey house, Satirs, Water tank, Fuel tank, Hopper house, Matting Boards, Gas buster, TDS Gen, Pre mix, Dog house, Rig down & move out. On new location set mud tanks, pump mats, and mud pumps #1, #2, #3 On location 2 cranes (1 = 1/2 day)4 riggers, 2 bed trucks, 1 pole truck, 3 swampers, 6 haul trucks, 2 forklifts. Total loads for today 25
Start Time 18:00	End Time 00:00	Comment Operations suspended for the night. Crews working days only for rig move.
Report Start Date 9/23/2014	Report End Date 9/24/2014	24hr Activity Summary Break down sub base and re-allembles on new locarion lay down and split derrick
Start Time 00:00	End Time 06:00	Comment Shut down wait on daylight to resume rig move
Start Time 06:00	End Time 18:00	Comment Resume rig move break down sub base, split derrick, transport loads to the Powvitch locarion re-assemble sub base, move camps Set off BOP, instsall tubing head, pressure tested. All electrical, fuel and ground rods pulled. rig up mats and stack pin subs and install bop, 90% off rig off old location, Back yard 90% rigged up, 2 cranes, 4 riggers, 2 Bed trucks, 1 pole truck, 3 swampers, 7 Haul trucks, 2 Forklift, 2 Pushers, 1 safety, 5 Pilot cars.
Start Time 18:00	End Time 00:00	Comment Shut down, wait on daylight to resume rig move
Report Start Date 9/24/2014	Report End Date 9/25/2014	24hr Activity Summary Move in and rig up clear old location and rig up on new location
Start Time 00:00	End Time 06:00	Comment Wait until daylight to resume rig move

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	06:00	End Time
		19:30
		Comment
		Continue clear old location, rig up on new location, set drawworks and motors, set all peak equipment, pinned derrick. set #1 # 2 floor motors chains in compound and fill with oil. get air and fuel to floor. set gas buster choke house, and flow line inspect crown set derrick board. put derrick on floor pin and raise A-Legs. set water tank, service loop and doghouse.set hopper house and barite uprights. hooked lines up from hopper to tanks. set all stairs in place.hooking up water lines and hooking up cords for doghouse, pumps and accumulators. rig up string up crew string up blocks. Raise Derrick. 2 cranes, 5 haul trucks, 1 bed truck 3 forklifts
Start Time	19:30	End Time
		00:00
		Comment
		Wait until daylight to resume rig move
Report Start Date	Report End Date	24hr Activity Summary
9/25/2014	9/26/2014	Rig up, pits, pumps and back yard. Install and rig up top drive, hang service loop and rig up rig floor. Nipple up and install rotating head and flow line then Tighten and function test Bop. Welder making necessary repairs to Flow line and Catwalk (Hot Work) Fill pits and receive Directional tools
Start Time	00:00	End Time
		06:00
		Comment
		Wait on daylight to resume rig move and rig up
Start Time	06:00	End Time
		18:00
		Comment
		R/U Air Tuggers. Install Floor Plates. R/D Bridle Lines and hang back in derrick. Install lines from Gas Buster to flow line and shakers. Set Catwalk and Beaver Slide. Installed Torque Tube in derrick. Picked up top drive. Plugged in cords on Top Drive and VFD House. Hung Service Loop. Installed sheath on service loop. M/U Kelly Hose to Top Drive.
Start Time	18:00	End Time
		00:00
		Comment
		(Start) Nipple up BOPE- Rig up Choke line, Kill line, Nipple up Bop, make up Flow line and rotating head, Torque bolts on Bop and choke line, install turn Buckles and preliminary center up Bop stack under floor. Hook up and test accumulator hydraulic hoses and Pressure up Accumulator. Function test BOP.
		Rig up work continued in back yard, hook up pits to tank farm, rig up premix tank, hook up flow lines from centrifuges to pits, Clean out Pump rooms and clean off pits prepare rig for spud and perform pre spud inspection.
		Clean up Mud storage area and pipe racking area and store all auxiliary equipment.
		Welder (Hot work Permit) Completed repairs to catwalk and flow line.
		Hauled in 260 bbl's 20%Kcl and 440 bbl's fresh water to fill pits, fill Premix tank with 200 bbl's of fresh water. fill storage tanks in front yard. with 450 bbl's fresh water, used 2 Iowa Tank lines trucks and 2 Gonzo Trucking trucks.
		Hauled in, unload and began prepping Weatherford Directional tools for 12 1/4" section.
Report Start Date	Report End Date	24hr Activity Summary
9/26/2014	9/27/2014	Service and lubricate all valves on BOP and choke. Perform full accumulator function test then Pressure test BOPE to 5M Specifications. Replaced element in Annular (failed to test). Nipple up Rotating head and Flow line, Begin handle BHA.
Start Time	00:00	End Time
		01:00
		Comment
		Service and Lubricate all Valves on BOPE with Eager beaver Testers.
		Pick up Joint of drill pipe and get Test Plug and test subs on Rig floor

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	01:00	End Time
		06:00
Comment (Start) Test BOP - Hold pre-job safety Meeting with Eager Beaver Testers and complete JSA Begin test with Accumulator function test then run test plug in on Drill pipe and set in well head, Fill BOP with water and Begin testing Test 1: (02:00) Test Annular preventer - Attempted Several times to test but Could not achieve low pressure test even after increasing accumulator hydraulic pressure to over 1500 psi, Drained Stack below Hydril and shut in again then Clearly noticed Hydril element leaking around pipe. Began trying to locate Replacement element and continue testing BOPE Test 2: (03:30) Upper Pipe rams, Hydraulic IBOP, Inside Kill line valve, Manuel Choke line valve to 250 Psi Low for 5 minutes then 5000 Psi High for 10 minutes *(At 04:00 Night Rig manager TJ Ramone located replacement parts for Hydril at Pioneer yard in Vernal Utah and got them in route to rig.) Test 3: (04:10) Lower Pipe Rams, Manual IBOP, Outside Kill line valve & HCR Choke line valve to 250 psi Low for 5 minutes then 5000 psi High for 10 Minutes. Test 4:(04:40) Lower pipe rams, Full open safety Valve(TIW), Dart Valve (IBOP), Coke manifold riser and inside manifold valves, Kill line check valve. Test 5; (05:25) Blind Rams, outside manifold valves to 250 Psi low for 5 minutes and 5000 psi High for 10 minutes Test 6: (06:00) Super Choke to 250 psi low for 5 minutes and 1500 psi high for 10 minutes		
Start Time	06:00	End Time
		08:00
Comment PJSM with Eager Beaver BOP Testers. Pulled Test Plug. Test 7: (06:35) Outside manifold Valves on choke to 250 psi low and 5000 psi high for 10 minutes. Test 8: (07:00) Test casing to 250 psi low for 5 minutes and 1500 Psi high for 30 minutes.		
Start Time	08:00	End Time
		15:00
Comment Closed Blind Rams. R/D Flowline and Rotating Head. M/U Potatomasher to Annular cap. Unbolt and removed cap on annular. Changed out Rubber Element. Installed cap on Annular.		
Start Time	15:00	End Time
		16:30
Start Time	16:30	End Time
		17:00
Start Time	17:00	End Time
		22:30
Comment Install and N/U Rotating Head, R/U Flow Line. Install turn Buckles and center up BOP Rig up plumbing from Choke house to Pits and Gas Buster		
Start Time	22:30	End Time
		23:00
Comment Lubricate Draw works, Blocks and top Drive. Service and inspect St-80 and catwalk (JSA, Personel lift permit and LOTO)		
Start Time	23:00	End Time
		00:00
Comment (Start) Line out and prepare to Pick up Directional tools Tally HWDP.		
Report Start Date	Report End Date	24hr Activity Summary
9/27/2014	9/28/2014	Pick up BHA and trip in hole tag cement and drill out shoe and float then 10 of new formation to 1687 then perform FIT to 13 ppg Emw, Drill 1040' of 12 1/4" hole from 1686' to 2716' Replace Main drive clutch on #2 Mud pump.
Start Time	00:00	End Time
		05:30
Comment Hold safety meeting with weatherford, Make up Ultera Bit (U616M with .557 TFA) to Weatherford Mud motor (QLE 7840 with 1.83 deg bent housing) then make up and Scribe (EM) MWD equipment. Pick up 21 - 5" HWDP then Pick up Smith super jar, and 6 - 5" HWDP.		
Start Time	05:30	End Time
		07:00
Comment Pick up 5" drill pipe and trip in hole from 970' to 1,574' tagged cement.		
Start Time	07:00	End Time
		07:30
Comment Installed Rotating Head Element.		

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	End Time	Comment
07:30	09:30	(Start) Drill shoe track/FIT... Drill cement f/ 1574' to 1676' (Float Collar @ 1620' Float Shoe @ 1663')
Start Time	End Time	Comment
09:30	10:00	Drill 10' of new formation for FIT. Drill 12.25" Vertical Hole Section F/ 1676' To 1686' (2 Pumps on the hole at 86 SPM Each, 403 GPM) Present Mwt 8.6 ppg
Start Time	End Time	Comment
10:00	11:00	Circulate Bottoms up and for mud wt checks. Spot Hi Vis Pill
Start Time	End Time	Comment
11:00	11:30	HPJSM & Rig up Eager Beaver Testers. Conduct FIT to 13 ppg EMW, 13 ppg-8.6 ppg=4.4 x .052 x 1686' = 386 psi
Start Time	End Time	Comment
11:30	12:30	Circulated High Vis Pill out of hole. Fluid blinding off shakers. Changed Shaker Screens to 70's.
Start Time	End Time	Comment
12:30	17:30	(Start) Drill 12.25" Vertical Hole Section F/ 1686' To 2197' (3 Pumps on the hole at 97 SPM Each, 656 GPM) Present Mwt 8.6 ppg
Start Time	End Time	Comment
17:30	18:00	Serviced Rig & Equipment.
Start Time	End Time	Comment
18:00	21:00	Drill 217' of 12.25" Vertical Hole Section From 2197' to 2414' at 72 fph avg. (2 Pumps on the hole at 120 SPM Each, 545 GPM) Present Mw 8.6 ppg Pumped 15 bbl High vis Sweep at 2400' plugged screens on Pump suctions Replacing Drive clutch on #2 Mud pump
Start Time	End Time	Comment
21:00	21:30	Clean suction screens on Both mud pumps.
Start Time	End Time	Comment
21:30	00:00	Drill 302' of 12.25" Vertical Hole Section From 2414' to 2716' at 120 fph avg. (2 Pumps on the hole at 120 SPM Each, 545 GPM) Present Mw 8.6 ppg Replacing Drive clutch on #2 Mud pump
Report Start Date	Report End Date	24hr Activity Summary
9/28/2014	9/29/2014	Drilled 2031' of 12 1/4" Hole from 2716' to 4747'
Start Time	End Time	Comment
00:00	05:30	Drill 521' of 12.25" Vertical Hole Section From 2716' to 3237' at 94.7 fph avg. (2 Pumps on the hole at 120 SPM Each, 545 GPM Until 3050' when repairs on pump #2 were completed and we began running 3 Pumps at 104 stk each= 700 GPM at 3050 PSI on bottom) Present Mw 8.6 ppg Pumped 15 bbl High vis sweep at 2963' Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion)
Start Time	End Time	Comment
05:30	06:00	Lubricate rig - Service Draw works, Blocks, Top Drive, St-80, Catwalk, and compound. JSA and Personel lift Permit.
Start Time	End Time	Comment
06:00	12:00	Drill 448' of 12.25" Vertical Hole Section From 3237' to 3685' at 74.6 fph avg. 3 Pumps at 104 stk each= 700 GPM at 3050 PSI on bottom) Present Mw 9.2 ppg Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion)
Start Time	End Time	Comment
12:00	15:30	Drill 401' of 12.25" Vertical Hole Section From 3685' to 4086' at 114.6 fph avg. (2 Pumps on the hole at 120 SPM Each, 545 GPM From 3777' - 4086' while making repairs on pump #1 and Shaker. Ran 3 Pumps at 104 stk each= 700 GPM at From 3685' - 3777') Present Mw 9.2 ppg Pumped 15 bbl High vis sweep at 3900' BGG 3000 - 4700 Units. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion)
Start Time	End Time	Comment
15:30	16:00	Serviced Rig and Equipment.

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time 16:00	End Time 00:00	Comment Drill 661' of 12.25" Vertical Hole Section From 4086' to 4747' at 82.6 fph avg. (2 Pumps on the hole at 120 SPM Each, 545 GPM From 4086' - 4143' while making repairs on pump #1 and Shaker. Ran 3 Pumps at 104 stk each= 700 GPM at From 4143' - 4747') Present Mw 9.3 ppg Pumped 15 bbl High vis sweep at 4685' BGG 400 - 1600 Units. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion)
Report Start Date 9/29/2014	Report End Date 9/30/2014	24hr Activity Summary Trouble shoot EM tool, Drill 31' from 4747' to 4778' Circulate high vis sweep around mix pill, Check flow and POOH, Replace EM tools and trip in hole, Drill 172' from 4778' to 4950'
Start Time 00:00	End Time 02:00	Comment (STOP) Trouble shoot Weatherford MWD tool, Weak signal at 4747' Pull up to 4650 Signal is strong and tool responding
Start Time 02:00	End Time 02:30	Comment Still trouble shooting MWD, Drill ahead with no data 31' from 4747' to 4778' to attempt to regain signal.
Start Time 02:30	End Time 03:00	Comment Continue to Trouble Shoot MWD, Back up EM tools are here on location but WSS ordered Weatherford to Send Pulse MWD subs and Kit Box at 02:30 Just in case EM Tool shows no signs of damage.
Start Time 03:00	End Time 05:00	Comment Circulate High vis sweeps around and Clean up hole while rotating and reciprocating Drill string from 4650' to 4778'.
Start Time 05:00	End Time 05:30	Comment Rig service - Lubricate Blocks and top Drive, Service and inspect Draw works, st-80, Catwalk.
Start Time 05:30	End Time 06:00	Comment (Start) Pull out of hole - Flow Check and Pump Slug to Dry Pipe, Pull out of hole from 4778' to 4100' while monitoring fill up on trip tank.
Start Time 06:00	End Time 07:30	Comment Pull out of hole from 4100' to 900' while monitoring fill up on trip tank.
Start Time 07:30	End Time 08:00	Comment Removed Rotating Head Rubber. Flow Check - No Flow.
Start Time 08:00	End Time 08:30	Comment Serviced Rig and Equipment.
Start Time 08:30	End Time 09:30	Comment Pull out of hole from 900' to BHA while monitoring fill up on trip tank. L/D Jars and NMDC. Removed EM Tool. L/D Emitter Sub. Drained Motor. Checked Motor and Bit.
Start Time 09:30	End Time 10:30	Comment M/U Bit, Motor, NM Pony Collar, XO, MWD Carrier Sub, and Emitter Sub. Installed EM MWD/ GR Probe Tool. M/U NMDC. Orient BHA. Test EM Tool.
Start Time 10:30	End Time 14:00	Comment Trip in hole with BHA to 4,753'. Filled pipe at 1,730' and 4,753'. Wash down to 4,778'.
Start Time 14:00	End Time 14:30	Comment (Start) Drill 8' of 12.25" Vertical Hole Section From 4778' to 4786'. Ran 3 Pumps at 104 stk each= 700 GPM at From 4778' - 4786') Present Mw 9.3 ppg Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slide From 4,780' to 4,786 (6' in .5 hr)
Start Time 14:30	End Time 15:30	Comment (STOP) Trouble shoot Weatherford MWD/GR tool, Reboot Computer to clear sporadic toolface readings. Signal is strong and tool responding.

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time 15:30	End Time 17:30	Comment Drill 62' of 12.25" Vertical Hole Section Sliding From 4786' to 4848'. Ran 2 Pumps at 120 stk each= 549 GPM Present Mw 9.3 ppg Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 4786 - 4803 (17' in 1 hr) Rotate: 45' in 1 Hr
Start Time 17:30	End Time 18:30	Comment (STOP) Trouble shoot Weatherford MWD/GR tool, Reboot Computer to clear sporadic toolface readings. Boost power to 6 Amp Signal is strong and tool responding. Reduce power to 3 Amp Nov called out to service wildcat
Start Time 18:30	End Time 00:00	Comment Drill 112' of 12.25" Vertical Hole Section rotating and Sliding From 4848' to 4960'. Ran 2 Pumps at 120 stk each= 549 GPM Present Mw 9.3 ppg / Pump #1 is down with welder needed to replace wear plate (welder coming at 06:00) Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 4848 - 4879 (31' in 2.5 hr) / 4942' - 4960' (18' in 2.5 hr) Rotate: 63' in .5 Hr MW at 9.2 ppg ITL water truck on location Sucking up Rain water and transferring to Fresh water cuttings pit. 650 bbl's transferred.
Report Start Date 9/30/2014	Report End Date 10/1/2014	24hr Activity Summary Drill 597' From 4950' to 5557'
Start Time 00:00	End Time 02:00	Comment Drill 77' of 12.25" Vertical Hole Section rotating and Sliding From 4960' to 5037. Ran 2 Pumps at 120 stk each= 549 GPM Present Mw 9.3 ppg / Pump #1 is down with welder needed to replace wear plate (welder coming at 06:00) Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 4960 - 4974 (14' in 1 hr) Rotate: 63' in 1 Hr MW at 9.2 ppg ITL water truck on location Sucking up Rain water and transferring to Fresh water cuttings pit. over 800 bbl's transferred.
Start Time 02:00	End Time 02:30	Comment Serviced Rig and Equipment.
Start Time 02:30	End Time 06:00	Comment Drill 94' of 12.25" Vertical Hole Section rotating and Sliding From 5037 to 5131. Ran 2 Pumps at 120 stk each= 549 GPM Present Mw 9.3 ppg / Pump #1 is down with welder needed to replace wear plate (welder coming at 06:00) Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 5037' - 5065 (28' in 2.5 hr) Rotate: 66' in 1 Hr MW at 9.2 ppg ITL water truck on location Sucking up Rain water and transferring to Fresh water cuttings pit. over 1000 bbl's transferred total .

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time 06:00	End Time 11:30	Comment Drill 189' of 12.25" Vertical Hole Section rotating and Sliding From 5131' to 5320. Ran 2 Pumps at 120 stk each= 549 GPM Present Mw 9.2 ppg / Pump #1 is down with welder needed to replace wear plate (welder coming at 06:00) Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 5131' - 5158' (27' in 2.5 hr) Rotate: 162' in 3.0 Hr MW at 9.2 ppg ITL water truck on location Sucking up Rain water and transferring to Fresh water cuttings pit. over 1100 bbl's transferred total .
Start Time 11:30	End Time 12:00	Comment Precautionary wash and reamed stand through top of Mahogany Bench (~5,247 MD) prior to making connection.
Start Time 12:00	End Time 17:00	Comment Drill 94' of 12.25" Vertical Hole Section rotating and Sliding From 5320' to 5414'. Ran 2 Pumps at 120 stk each= 549 GPM Present Mw 9.2 ppg / Pump #1 is down with welder working to replace wear plate Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 5320' - 5343' (23' in 3.5 hr) Rotate: 71' in 1.5 Hr MW at 9.2 ppg
Start Time 17:00	End Time 17:30	Comment Serviced Rig and Equipment. Greased Rig, Blocks, Crown, and Swivel Packing.
Start Time 17:30	End Time 00:00	Comment Drill 143' of 12.25" Vertical Hole Section rotating and Sliding From 5414' to 5557'. Ran 2 Pumps at 120 stk each= 549 GPM Present Mw 9.2 ppg / Pump #1 is repaired and fully operational (cont. run only 2 pumps while drilling Mahogany bench). Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 5414 - 5421' (7' in .5 hr) 5421-5440 (19' in 1.25 hr) 5509 - 5537 (28' in 2.25 hr) Total slide:54' in 4 hr Rotate: 89' in 2.5 Hr MW at 9.2 ppg
Report Start Date 10/1/2014	Report End Date 10/2/2014	24hr Activity Summary Drill 706' From 5557' to 6263'
Start Time 00:00	End Time 04:30	Comment Drill 141' of 12.25" Vertical Hole Section rotating and Sliding From 5557' to 5698'. Ran 2 Pumps at 120 stk each= 549 GPM Present Mw 9.2 ppg / Pump #1 is repaired and fully operational (cont. run only 2 pumps while drilling Mahogany bench). Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 5603 - 5635' (32' in 2 hr) Total slide:32' in 2 hr Rotate: 109' in 2.5 Hr MW at 9.2 ppg
Start Time 04:30	End Time 05:00	Comment Serviced Rig and Equipment. Greased Rig, Blocks, Crown, and Swivel Packing.

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time 05:00	End Time 06:00	Comment Drill 48' of 12.25" Vertical Hole Section rotating and Sliding From 5698' to 5746'. Ran 3 Pumps at 105 stk each= 700 GPM Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: Total slide 0' in 0 hr Rotate 48' in 1.0 Hr MW at 9.4 ppg
Start Time 06:00	End Time 12:00	Comment Drill 235' of 12.25" Vertical Hole Section rotating and Sliding From 5746' to 5981'. Ran 3 Pumps at 115 stk each= 750 GPM Present Mw 9.4 ppg. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 5792 - 5822' (30' in 2 hr) Total slide:30' in 2 hr Rotate: 205' in 4.0 Hr MW at 9.4 ppg
Start Time 12:00	End Time 14:00	Comment Drill 95' of 12.25" Vertical Hole Section Rotating From 5981' to 6076'. Ran 3 Pumps at 100 stk each= 700 GPM Present Mw 9.4 ppg. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 0 - 0' (0' in 0 hr) Total slide:0' in 0 hr Rotate: 95' in 2.0 Hr MW at 9.4 ppg
Start Time 14:00	End Time 14:30	Comment Lubricate Rig, Blocks, Top Drive, Crown and Swivel Packing.
Start Time 14:30	End Time 15:00	Comment Drill 4' of 12.25" Vertical Hole Section Sliding From 6076' to 6080'. Ran 3 Pumps at 100 stk each= 700 GPM Having pump pressure problems when sliding.Present Mw 9.4 ppg. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 6076' - 6080' (4' in 0.5 hr) Total slide:4' in 0.5 hr Rotate: 0' in 0.0 Hr MW at 9.4 ppg
Start Time 15:00	End Time 15:30	Comment Troubleshoot pumps changed out 2" Bleed-Off Valve on # 2 Mud Pump.
Start Time 15:30	End Time 00:00	Comment Drill 183' of 12.25" Vertical Hole Section Sliding From 6080' to 6263'. Ran 3 Pumps at 100 stk each= 700 GPM. Present Mw 9.4 ppg. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 6080' - 6108' (28' in 2.25 hr) 6169 - 6182 (13' in 1.5 hr) 6201 - 6232 (31' in 2 hr) Total slide:72' in 5.75 hr Rotate: 111' in 2.75 Hr MW at 9.4 ppg 260 bbl'sRig water Delivered By ITL
Report Start Date 10/2/2014	Report End Date 10/3/2014	24hr Activity Summary Drill 188' From 6263 to 6451'. Motor failure. Circulate High Vis Sweep, flow check and slug pipe. POH Break off Bit and L/D Motor.

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	00:00	End Time
		04:00
Comment		
Drill 94' of 12.25" Vertical Hole Section Sliding From 6263' to 6357'. Ran 3 Pumps at 100 stk each= 700 GPM. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion)		
Slides: 6273' - 6296' (23' in 2 hr)		
Total slide:23' in 2 hr		
Rotate: 71' in 2 Hr		
MW at 9.55 ppg		
Start Time	04:00	End Time
		04:30
Comment		
Lubricate Rig, Blocks, Top Drive, Crown and Swivel Packing.		
Start Time	04:30	End Time
		06:00
Comment		
Drill 94' of 12.25" Vertical Hole Section Sliding From 6357' to 6378'. Ran 3 Pumps at 100 stk each= 700 GPM. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion)		
Slides: 6367' - 6378' (11' in 1.50 hr)		
Total slide:11' in 1.5 hr		
Rotate: 0' in 0 Hr		
MW at 9.55 ppg		
Start Time	06:00	End Time
		10:30
Comment		
Drill 73' of 12.25" Vertical Hole Section Sliding From 6378' to 6451'. Ran 3 Pumps at 100 stk each= 700 GPM. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion)		
Slides: 6377' - 6387' (10' in 1.25 hr) 6397' - 6406' (9' in 1.0 hr)		
Total slide:19' in 2.25 hr		
Rotate: 54' in 2.25 Hr		
MW at 9.55 ppg		
Start Time	10:30	End Time
		11:00
Comment		
Motor stalling out and pressuring up. Troubleshoot motor and determined that motor failure had occurred.		
Start Time	11:00	End Time
		13:30
Comment		
Circulate High vis sweeps around and clean up hole while rotating and reciprocating drill string from 6380' to 6451'.		
Start Time	13:30	End Time
		17:00
Comment		
(Start) Pull out of hole - Flow Check and Pump Slug to Dry Pipe, Pull out of hole from 6451' to 2110' while monitoring fill up on trip tank.		
Start Time	17:00	End Time
		17:30
Comment		
Serviced and Lubricated Blocks, Top Drive and Crown.		
Start Time	17:30	End Time
		20:00
Comment		
Continue pooh to 103'		
Start Time	20:00	End Time
		21:30
Comment		
PJSM with DD and MWD lay down BHA X/O Sub, NMDC, Emitter Sub, TOL Carrier, double pin sub and NMDC, Broke bit and layed down motor		
Start Time	21:30	End Time
		00:00
Comment		
PJSM with DD, MWD, P/U Mud Motor, Muleshoe, Make up Bit, P/U NMDC, Tool Carrier, NMDC, X/O Sub		
Report Start Date	Report End Date	24hr Activity Summary
10/3/2014	10/4/2014	Trip in Hole, Wash and Ream to 6451' Rotate and Slide Drill F/ 6451 to 6996'
Start Time	00:00	End Time
		01:00
Comment		
Start TIH W/ HWDP P/U Jars, Install Rotating Head Rubber. Cont. in Hole to 1728'		
Start Time	01:00	End Time
		02:30
Comment		
Test MWD Tools, Getting Magnetic Interference From The casing Run a couple more stands in to 1940' Test MWD tools again, Good Test		
Start Time	02:30	End Time
		03:30
Comment		
Cont. TIH to 4729'		
Start Time	03:30	End Time
		04:00
Comment		
Rig Service Lubricate Rig, Top Drive & ST-80		

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	04:00	End Time
		07:30
Comment		
Cont. TIH F/ 4729' Wash and Ream Tight Spots F/4935' To 6,451'.		
Start Time	07:30	End Time
		15:00
Comment		
Drill 371' of 12.25" Vertical Hole Section Rotating From 6451' to 6822'. Ran 3 Pumps at 110 stk each= 740 GPM. Top Drive RPM 30, SPP 3775 psi Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Rotate: 371' in 7.50 Hr MW at 9.6 ppg		
Start Time	15:00	End Time
		15:30
Comment		
Serviced Rig and Equipment. Greased Rig, Blocks, Top Drive, Crown and Swivel Packing.		
Start Time	15:30	End Time
		20:00
Comment		
Drill 95' of 12.25" Vertical Hole Section Sliding From 6822' to 6917'. Ran 3 Pumps at 110 stk each= 740 GPM. Top Drive RPM 0-30, SPP 3,750 psi. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 6822' - 6947' (53' in 1.50 hr) Total slide:53' in 3.50 hr Rotate: 42' in 1.00 Hr MW at 9.6 ppg		
Start Time	20:00	End Time
		20:30
Comment		
Service rig and equipment Greased Rig, Blocks, Top Drive, Crown and Swivel Packing		
Start Time	20:30	End Time
		00:00
Comment		
Slide F/ 6947' to 6996' Slide 49' in 3.5 hrs. Running 2 Pumps @ 120 stks each 540 GPM SPP 1960 psi Replacing Drive Chain on # 1 Mud Pump		
Report Start Date	Report End Date	24hr Activity Summary
10/4/2014	10/5/2014	Drilled 12-1/4" Hole Sliding from 6,996' to 7418'
Start Time	00:00	End Time
		06:00
Comment		
Slide Drill F/ 6996 to 7074'. Running 2 Pumps @ 120 stks each 540 GPM SPP 1960 psi to 05:30 Hours Running 3 pumps 742 GPM SPP 3665 psi		
Start Time	06:00	End Time
		16:00
Comment		
Drill 220' of 12.25" Vertical Hole Section Sliding From 7074' to 7294'. Ran 3 Pumps at 110 stk each= 740 GPM. Top Drive RPM 0-30, SPP 3,690 psi. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 7074' - 7294' (220' in 10.00 hr) MW at 9.6 ppg		
Start Time	16:00	End Time
		16:30
Comment		
Serviced Rig and Equipment. Greased Rig, Blocks, Top Drive, Crown and Swivel Packing.		
Start Time	16:30	End Time
		00:00
Comment		
Drill 124' of 12.25" Vertical Hole Section Sliding From 7294' to 7418'. Ran 3 Pumps at 110 stk each= 740 GPM. Top Drive RPM 0-30, SPP 3,690 psi. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 7294' - 7418' 124' in 7.5 hr MW at 9.7 ppg		
Report Start Date	Report End Date	24hr Activity Summary
10/5/2014	10/6/2014	Slide Drill F/7418 To 7781' Building angle toward 45 degrees
Start Time	00:00	End Time
		03:00
Comment		
Drill f 12.25" Vertical Hole Section Sliding From 7418' to 7483'. Ran 3 Pumps at 110 stk each= 740 GPM. Top Drive RPM 0-30, SPP 3,690 psi. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 7418' - 7483' MW at 9.7 ppg		

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	03:00	End Time 03:30
Comment Service Rig Lubricate rig, top Drive and ST-80		
Start Time	03:30	End Time 06:00
Comment Drill 53 ft of 12.25" Vertical Hole Section Sliding From 7483' to 7536'. Ran 3 Pumps at 110 stk each= 740 GPM. Top Drive RPM 0-30, SPP 3,690 psi. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 7483' - 7536' MW at 9.7 ppg		
Start Time	06:00	End Time 13:00
Comment Drill 135 ft of 12.25" Vertical Hole Section Sliding From 7536' to 7671'. Ran 3 Pumps at 110 stk each= 740 GPM. Top Drive RPM 0-30, SPP 3,690 psi. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 7536' - 7671' MW at 9.9 ppg BGG 1500 - 3500 Units, 5 - 15 Ft Flare		
Start Time	13:00	End Time 13:30
Comment Changed out Rotating Head Rubber.		
Start Time	13:30	End Time 17:30
Comment Drill 64 ft of 12.25" Vertical Hole Section Sliding From 7671' to 7735'. Ran 3 Pumps at 110 stk each= 740 GPM. Top Drive RPM 0, SPP 3,990 psi. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 7671' - 7735' MW at 9.9 ppg		
Start Time	17:30	End Time 18:00
Comment Serviced Rig and Equipment. Greased Rig, Top Drive, Crown and Swivel packing.		
Start Time	18:00	End Time 18:30
Comment Drill 2 ft of 12.25" Vertical Hole Section Sliding From 7735' to 7737'. Ran 2 Pumps at 120 stk each= 540 GPM. Top Drive RPM 0, SPP 2,100 psi. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 7735' - 7737' MW at 9.9 ppg		
Start Time	18:30	End Time 19:30
Comment Replaced liner gasket on # 3 mud pump. Circulated and reciprocated string while making repairs.		
Start Time	19:30	End Time 00:00
Comment Drill 46 ft of 12.25" Vertical Hole Section Sliding From 7735' to 7781'. Ran 2 Pumps at 120 stk each= 540 GPM. (Replacing Fluid end Module on # 1 Pump) Top Drive RPM 0, SPP 2,150 psi. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 7735' -7781' MW at 9.9 ppg		
Report Start Date	Report End Date	24hr Activity Summary
10/6/2014	10/7/2014	Slide Drill From 7,803' to 8023'. (TD)
Start Time	00:00	End Time 05:30
Comment Drill 17 ft of 12.25" Vertical Hole Section Sliding From 7803' to 7820'. Ran 2 Pumps at 120 stk each= 540 GPM. (Replacing Fluid end Module on # 1 Pump) Top Drive RPM 0, SPP 2,150 psi. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 7803' -7820' MW at 9.9 ppg		

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	05:30	End Time 06:00
		Comment Serviced Rig and Equipment. Greased Rig, Top Drive and ST-80.
Start Time	06:00	End Time 13:00
		Comment Drill 79 ft of 12.25" Vertical Hole Section Sliding From 7820' to 7899'. Ran 2 Pumps at 120 stk each= 540 GPM. (Replaced Fluid end Module on # 1 Pump) (# 1 Mud Pump Online at 11:50 Hours) Ran 3 Pumps at 110 STK each = 740 GPM Top Drive RPM 0, SPP 2,250 - 3990 psi. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 7820' -7899' MW at 9.9 ppg "B" Limestone 7,788 Ft MD, 7,721 Ft TVD
Start Time	13:00	End Time 13:30
		Comment Serviced Rig and Equipment. Greased Rig, Top Drive, Crown and Swivel packing.
Start Time	13:30	End Time 17:30
		Comment Drill 87 ft of 12.25" Vertical Hole Section Sliding From 7899' to 7986'. Ran 3 Pumps at 110 STK each = 740 GPM Top Drive RPM 0, SPP 3900 psi. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 7899' -7986' MW at 9.9 ppg
Start Time	17:30	End Time 18:30
		Comment Circulated while discussing 9-5/8" Casing Point with Engineer, Directional and Geology.
Start Time	18:30	End Time 20:30
		Comment Drill 37 ft of 12.25" Vertical Hole Section Sliding From 7986 to 8023 (TD for 9-5/8" Casing Point). Ran 3 Pumps at 110 STK each = 740 GPM Top Drive RPM 0, SPP 3900 psi. Adding EZMud down the drill pipe on Connections (1 to 3 Qt at the drillers discretion) Slides: 7986' -8023' MW at 10.0 ppg
Start Time	20:30	End Time 23:00
		Comment Circulate @ 8023', Circulate 40 bbl Hi-Vis Sweep around, Shakers clean, Circ one more BTMS Up
Start Time	23:00	End Time 00:00
		Comment Flow Check and POOH F/ 8023' to 7271' for Short Trip
Report Start Date 10/7/2014	Report End Date 10/8/2014	24hr Activity Summary Wiper Trip Raise MW to 10.5 Strap out of hole Lay down Dir. Tools Rig up and run 9 5/8" Casing
Start Time	00:00	End Time 01:00
		Comment Finish Wiper Trip. Trip in Hole F/6934' To 8023'
Start Time	01:00	End Time 05:30
		Comment Circ and Pump 40 BBL HI-VIS Sweep, Start Circ. BTMS UP Gas increased to 5458 Units with a 5-15 FT. Flare. Circulate while raising MW to 10.5 ppg
Start Time	05:30	End Time 06:00
		Comment Lube Rig Top Drive and ST-80
Start Time	06:00	End Time 10:00
		Comment Circulate while raising MW to 10.5 ppg. Flow Check - No Flow. Pumped Dry Job.
Start Time	10:00	End Time 17:00
		Comment (Start) Strap out of hole from 8023' to 980' while monitoring fluid displacement on trip tank. L/D 27 Joints of 5" HWD and Jars.
Start Time	17:00	End Time 17:30
		Comment Held PJSM with Weatherford. L/D XO and NMDC.
Start Time	17:30	End Time 18:00
		Comment Serviced Rig & Equipment.
Start Time	18:00	End Time 19:00
		Comment (End) PJSM with DD, and MWD hands. Broke Bit, Layed Down Tool Carrier, Muleshoe, and Motor

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	End Time	Comment
19:00	20:00	Pull Wear Bushing
Start Time	End Time	Comment
20:00	20:30	Service Rig Lube Rig, Top Drive and service Catwalk
Start Time	End Time	Comment
20:30	21:00	Held Pre Job Safety Meeting With Rig Crew and Casing Crew
Start Time	End Time	Comment
21:00	22:30	Rig Up Franks Casing Equipment
Start Time	End Time	Comment
22:30	00:00	Pick up 2 jt shoe track and Run 9 5/8" 40 # BTC connection, F/ surface t/ 402'.
Report Start Date	Report End Date	24hr Activity Summary
10/8/2014	10/9/2014	Run 9 5/8" Casing, Land Casing, Rig up and Cement Casing.
Start Time	End Time	Comment
00:00	06:00	Run 9 5/8 Intermediate casing F/ 402' to 5818' Auto fill function failed @ + - 3400 Ft. Had to fill casing with CRT Tool.
Start Time	End Time	Comment
06:00	10:00	Run 9 5/8 Intermediate casing F/ 5818' to 7938'. M/U Casing Hanger and Landing Joint. Landed hanger in well head, shoe at 8,013'. Fill casing with CRT Tool.
Start Time	End Time	Comment
10:00	13:00	Circulate and conditioned mud for cement job. Held PJSM with Halliburton.
Start Time	End Time	Comment
13:00	13:30	Service Rig
Start Time	End Time	Comment
13:30	14:00	R/U Cement Head and Lines.
Start Time	End Time	Comment
14:00	19:00	Cement 9 5/8" Casing Pump 40 bbl tuned spacer 11.5 ppg 3.71 yield, 35 bbls 1st lead, 12.5 ppg, yield 1.96. pump 323 bbls 2nd lead 12.5 ppg 1.96 yield, pump 136 bbls tail cement 14.0 ppg 1.29 yield. Displaced W/ 600 bbls 10.5 ppg Bump Plug, Floats holding. Returned to Surface 35 BBLS Spacer.
Start Time	End Time	Comment
19:00	20:30	Wash Out Stack, Rig Down Halliburton, Rig Down Casing Elevators and Bails, Cleaning Pits
Start Time	End Time	Comment
20:30	00:00	Back Out Landing Jt. Attempt to Set Packoff With Cameron Hand. Cleaning Pits
Report Start Date	Report End Date	24hr Activity Summary
10/9/2014	10/10/2014	Set and Test 9-5/8" Packoff. Rig Service. Installed Wear Bushing. Cleaned mud tanks. Shipped OBM to mud tanks. M/U BHA Trip in hole to 4200'.
Start Time	End Time	Comment
00:00	02:30	Attempt to set Packoff, Applied Weight, Turned, Set weight on it, Wash Wellhead, P/U Running Tool and Try to Re-Set Casing. P/U 1 1/2' to insure casing could be cut, Pulled 300,000 lb.
Start Time	End Time	Comment
02:30	05:30	Holding Casing 1-1/2' up with 300,000 lb pull. Waiting on BOP Jacks. Land hanger in well head. Tried running undressed Packoff and to remove any debris in setting area. Packoff seated properly. P/U and run original Packoff. Packoff seated. Run in Anchor Ram Screws, Tested to 2400 psi. Red Mesa cleaning mud pits.
Start Time	End Time	Comment
05:30	06:00	Service Rig
Start Time	End Time	Comment
06:00	06:30	Installed Wear Bushing.
Start Time	End Time	Comment
06:30	09:00	Installed Catch Pans and Tarps. Red Mesa Super Suckers cleaning mud pits.
Start Time	End Time	Comment
09:00	12:00	Shipped 380 bbls of 14.8 ppg OBM to mud pits. Transferred slowly over shakers to keep OBM from running over shaker screens.

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	End Time	Comment
12:00	14:00	Unplugged hose's and suction lines to transfer pumps in Tank Farm.
Start Time	End Time	Comment
14:00	17:30	Shipped 14.8 ppg OBM to mud pits. Transferred slowly over shakers to keep OBM from running over shaker screens.
Start Time	End Time	Comment
17:30	18:00	Serviced Rig and Equipment.
Start Time	End Time	Comment
18:00	18:30	Cond Mud shaking out LCM, Reduce MW to 13.0 ppg
Start Time	End Time	Comment
18:30	22:00	PJSM with DD, MWD. P/U Tools M/U Bit R.S.S. Tool,NMDC,Tomax, 1 x HWDP, Drill-n-Ream
Start Time	End Time	Comment
22:00	23:00	Trip in Hole to 1700 Ft. Filled Drill Pipe with 30 bbl Diesel Spacer.
Start Time	End Time	Comment
23:00	00:00	Trip in Hole to 4200'. 10.5 ppg WBM displacing to Trip Tank. Vacuum Truck moving WBM from Trip Tank to Tank Farm.
Report Start Date	Report End Date	24hr Activity Summary
10/10/2014	10/11/2014	Tripped in Hole Displaced to OBM Test Casing to 1800psi for 30 min. Drilled out plus 10 Ft. of new hole Perform FIT test to 16.5 EMW. Drilled from 8,033' - 8,110'. Troubleshoot RSS. Circulated bottoms up. Pumped dry job. POH.
Start Time	End Time	Comment
00:00	02:00	Trip in Hole F/4200' to 7287'
Start Time	End Time	Comment
02:00	02:30	Service Rig.
Start Time	End Time	Comment
02:30	03:30	Trip in Hole F/7287' to 7924' Tagged Cement @ 7924'
Start Time	End Time	Comment
03:30	08:00	Displaced 10.5 ppg WBM with 13.1 ppg OBM into Trip Tank.
Start Time	End Time	Comment
08:00	09:00	Held PJSM with Eager Beaver. R/U Test Equipment. Test 9-5/8" Casing to 1800 psi for 30 min. R/D Test Equipment.
Start Time	End Time	Comment
09:00	12:30	Drilled cement from 7,924', Float Collar at 7,926', Shoe at 8,013'. Cleaned out Rathole to 8,023'. Drilled 10 ft of new 8-3/4" Hole from 8,023' to 8,033'.
Start Time	End Time	Comment
12:30	13:00	Circulated hole clean, spotted viscous pill in open hole.
Start Time	End Time	Comment
13:00	13:30	Performed F.I.T. to 16.5 EMW. OMW 13.1 ppg, 1395 psi.
Start Time	End Time	Comment
13:30	14:30	(Start) Drill 8.75"curve with RSS f/ 8033' to 8056', (2 Pumps on the hole at 110 a piece, 460 GPM) Present Mwt 13.1 ppg.
Start Time	End Time	Comment
14:30	15:00	Serviced Rig and Equipment. Greased Rig, Top Drive, Crown and Swivel packing.
Start Time	End Time	Comment
15:00	17:00	Drill 8.75"curve with RSS f/ 8056' to 8110', (2 Pumps on the hole at 110 a piece, 460 GPM) Present Mwt 13.1 ppg.
Start Time	End Time	Comment
17:00	18:00	Troubleshoot problems with RSS. Unable to hold toolface.
Start Time	End Time	Comment
18:00	19:00	Circulate BTMS UP while building Slug Flow Check (no flow) Pump Slug
Start Time	End Time	Comment
19:00	00:00	Trip Out of Hole F/ 8110 to 791'

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

--

Daily Operations			
Report Start Date 10/11/2014	Report End Date 10/12/2014	24hr Activity Summary POH L/D RSS. M/U BHA. Trip in hole to 7,716'. Cut & Slip Drilling Line. RIH to 8,110'. Drilled Curve from 8,110' to 8,686'.	
Start Time	End Time	Comment	
00:00	00:30	Continued to POH to 130'.	
Start Time	End Time	Comment	
00:30	02:00	Held PJSM with Weatherford Directional Crew. Stood Back in Derrick Drill-n-Ream, 1 X hwdp, Tomax, nmcd, Spiral String Stab., Broke Bit, Layed Down HEL/IDS, and RSS Tool.	
Start Time	End Time	Comment	
02:00	04:00	P/U RSS and HEL/IDS, M/U Bit. Program Directional Tools	
Start Time	End Time	Comment	
04:00	04:30	Service Rig Lube Rig, Top Drive, and ST-80	
Start Time	End Time	Comment	
04:30	08:00	Trip in Hole F/130' to 7716' with Curve BHA. Filled pipe at 2,950', and 6,169'.	
Start Time	End Time	Comment	
08:00	09:30	Slipped and cut off 120 ft of drilling line.	
Start Time	End Time	Comment	
09:30	10:00	Trip in hole from 7,716' to 8,055'. Filled Drill Pipe. Washed down from 8,055' to 8,110'.	
Start Time	End Time	Comment	
10:00	14:30	Drill 8.75"curve with RSS f/ 8110' to 8339', (2 Pumps on the hole at 115 a piece, 530 GPM) Present Mwt 13.1 ppg. Lower Black Shale at 8,145'MD / 7,981' TVD / 385' VS, The target is dropped by 59' to: 0' VS = 8,117' TVD = 86.98° 892' VS = 8,164' TVD = 86.98°	
Start Time	End Time	Comment	
14:30	15:00	Serviced Rig and Equipment.	
Start Time	End Time	Comment	
15:00	17:00	Drill 8.75"curve with RSS f/ 8339' to 8448', (2 Pumps on the hole at 115 a piece, 530 GPM) Present Mwt 13.1 ppg.	
Start Time	End Time	Comment	
17:00	17:30	Troubleshoot and repair Downlink Manifold.	
Start Time	End Time	Comment	
17:30	18:30	Drill 8.75"curve with RSS f/ 8448' to 8528', (2 Pumps on the hole at 115 a piece, 530 GPM) Present Mwt 13.1 ppg.	
Start Time	End Time	Comment	
18:30	19:00	Directional Work Re-Log Hole Section F/8504' To 8528'	
Start Time	End Time	Comment	
19:00	20:00	Change Rotating Head Rubber	
Start Time	End Time	Comment	
20:00	00:00	Drill 8.75"curve with RSS f/ 8528' to 8686', (2 Pumps on the hole at 115 a piece, 530 GPM) Present Mwt 13.1 ppg.	
Report Start Date 10/12/2014	Report End Date 10/13/2014	24hr Activity Summary Drill Curve, Landed curve @ 8717, Drilled 200 Ft of Lateral. Circulated and raised mud wt to 13.8 ppg. POOH For Lateral Assembly.	
Start Time	End Time	Comment	
00:00	02:30	Drill F/8686' Land Curve @ 8717' 87.31 degrees AZ 356 degrees TVD 8166' Cont. Drilling to 8811' while raising MW to 10.4 ppg	
Start Time	End Time	Comment	
02:30	03:00	Service Rig Lube Rig, Top Drive and ST-80	

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	03:00	End Time
	05:30	Comment
Start Time	05:30	End Time
	08:00	Comment
Start Time	08:00	End Time
	08:30	Comment
Start Time	08:30	End Time
	12:00	Comment
Start Time	12:00	End Time
	17:30	Comment
Start Time	17:30	End Time
	19:00	Comment
Start Time	19:00	End Time
	00:00	Comment
Report Start Date	Report End Date	24hr Activity Summary
10/13/2014	10/14/2014	Tripped in Hole With Lateral Assembly Drilled Lateral F/8917' To 9,736'
Start Time	00:00	End Time
	01:30	Comment
Start Time	01:30	End Time
	02:00	Comment
Start Time	02:00	End Time
	07:30	Comment
Start Time	07:30	End Time
	11:00	Comment
Start Time	11:00	End Time
	12:00	Comment
Start Time	12:00	End Time
	15:30	Comment
Start Time	15:30	End Time
	16:00	Comment
Start Time	16:00	End Time
	00:00	Comment
Report Start Date	Report End Date	24hr Activity Summary
10/14/2014	10/15/2014	Drilled Lateral Section F/9,736 to 10,774'
Start Time	00:00	End Time
	03:30	Comment
Start Time	03:30	End Time
	04:00	Comment
Start Time	04:00	End Time
	06:00	Comment

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	06:00	End Time 12:00
		Comment Drill Lateral Section F/ 10,019' To 10,329'. 06:00 to 07:00 Running 2 Pumps 115 SPM Each, SPP 4090 psi. 530 GPM, 07:00 - 12:00 Running 2 Pumps 105 SPM Each, SPP 3650 Psi, 490 GPM, Top Drive RPM 144, WOB 27-30K, MW 13.8 ppg
Start Time	12:00	End Time 16:30
		Comment Drill Lateral Section F/ 10,329' To 10,491'. Running 2 Pumps 105 SPM Each, SPP 3650 psi. 490 GPM, Top Drive RPM 144, WOB 27-30K, MW 13.8 ppg
Start Time	16:30	End Time 17:00
		Comment Rig Service Lube Crown, Drawworks, Top Drive and compound
Start Time	17:00	End Time 00:00
		Comment Drill Lateral Section F/ 10491' To 10,774'. Running 2 Pumps 105 SPM Each, SPP 3650 psi. 490 GPM, Top Drive RPM 144, WOB 27-30K, MW 13.8 ppg
Report Start Date 10/15/2014	Report End Date 10/16/2014	24hr Activity Summary Drill Lateral Section F/10,774 To 11,718'
Start Time	00:00	End Time 02:30
		Comment Drill Lateral F/10,774' to 10,868' Control Drill With 26K WOB held to 80 ROP Running 2 Pumps @ 105 STKS Each 481 GPM 3600 SPP. RPM140 Torq 9600
Start Time	02:30	End Time 03:00
		Comment Service Rig
Start Time	03:00	End Time 06:00
		Comment Drill Lateral F/10,868' to 10,963' Control Drill With 26K WOB held to 80 ROP Running 2 Pumps @ 105 STKS Each 481 GPM 3600 SPP. RPM140 Torq 9600
Start Time	06:00	End Time 14:30
		Comment Drill Lateral F/10,963' to 11,246' 28K WOB Running 2 Pumps @ 105 STKS Each 491 GPM 3800 SPP. RPM140 Torq 9600
Start Time	14:30	End Time 15:00
		Comment Serviced Rig and Equipment.
Start Time	15:00	End Time 00:00
		Comment Drill Lateral F/11,246' to 11,718' 28K WOB Running 2 Pumps @ 105 STKS Each 490 GPM 3800 SPP. RPM150 Torque 9600
Report Start Date 10/16/2014	Report End Date 10/17/2014	24hr Activity Summary Drilled F/11,718 To 12,865'
Start Time	00:00	End Time 02:00
		Comment Drill 8 3/4' Lateral Section f/11,718 to 11,812' 2 Pumps on the hole @ 105 Stks Each 482 GPM, 3800 SPP, Rotary Torque 13,500 Top Drive RPM 135
Start Time	02:00	End Time 02:30
		Comment Service Rig
Start Time	02:30	End Time 06:00
		Comment Drill 8 3/4' Lateral Section f/11,812 To 12,033' 2 Pumps on the hole @ 105 Stks Each 482 GPM, 3800 SPP, Rotary Torque 13,500 Top Drive RPM 135
Start Time	06:00	End Time 13:00
		Comment Drill 8 3/4' Lateral Section f/12,033' To 12,379' 2 Pumps on the hole @ 105 Stks Each 482 GPM, 3800 SPP, Rotary Torque 12,500 Top Drive RPM 135
Start Time	13:00	End Time 13:30
		Comment Serviced Rig and Equipment. Checked oil levels in Top Drive and Drawworks.
Start Time	13:30	End Time 18:00
		Comment Drill 8 3/4' Lateral Section f/12,379' To 12,631' 2 Pumps on the hole @ 105 Stks Each 482 GPM, 3800 SPP, Rotary Torque 12,500 Top Drive RPM 130-140
Start Time	18:00	End Time 20:00
		Comment Drill 8 3/4' Lateral Section f/12,631' To 12,742' 2 Pumps on the hole @ 105 Stks Each 482 GPM, 3800 SPP, Rotary Torque 12,500 Top Drive RPM 130-140

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	20:00	End Time
		21:00
Comment		
Repair and bypass Downlink Equipment		
Start Time	21:00	End Time
		00:00
Comment		
Drill 8 3/4' Lateral Section f/12,742' To 12,865' 2 Pumps on the hole @ 105 Stks Each 482 GPM, 3800 SPP, Rotary Torque 12,500 Top Drive RPM 130-140		
Report Start Date	Report End Date	24hr Activity Summary
10/17/2014	10/18/2014	Drill Lateral Section F/12,865' To 13,891'
Start Time	00:00	End Time
		02:00
Comment		
Drill 8 3/4' Lateral Section f/12,865' To 12,948' 2 Pumps on the hole @ 105 Stks Each 482 GPM, 3800 SPP, Rotary Torque 12,500 Top Drive RPM 130-140		
Start Time	02:00	End Time
		02:30
Comment		
Directional work, Change out Downlink Unit		
Start Time	02:30	End Time
		04:00
Comment		
Drill 8 3/4' Lateral Section f/12,948' To 13,040' 2 Pumps on the hole @ 105 Stks Each 482 GPM, 3800 SPP, Rotary Torque 12,500 Top Drive RPM 130-140		
Start Time	04:00	End Time
		04:30
Comment		
Rig Service		
Start Time	04:30	End Time
		06:00
Comment		
Drill 8 3/4' Lateral Section f/13,040' To 13,134' 2 Pumps on the hole @ 105 Stks Each 482 GPM, 3800 SPP, Rotary Torque 12,500 Top Drive RPM 130-140		
Start Time	06:00	End Time
		12:00
Comment		
Drill 8 3/4' Lateral Section f/13,134' To 13,436' 2 Pumps on the hole @ 105 Stks Each 482 GPM, SPP 4100 psi, Rotary Torque 12,500 Top Drive RPM 130-140		
Start Time	12:00	End Time
		15:30
Comment		
Drill 8 3/4' Lateral Section f/13,436' To 13,607' 2 Pumps on the hole @ 104 Stks Each 470 GPM, SPP 3950 psi, Rotary Torque 12,500 Top Drive RPM 130-140		
Start Time	15:30	End Time
		16:30
Comment		
Flow Checked - No Flow. Changed out leaking Rotating Head Rubber.		
Start Time	16:30	End Time
		17:00
Comment		
Service Rig Lube Rig, Blocks, Top Drive, Crown, Swivel Packing		
Start Time	17:00	End Time
		18:00
Comment		
Drill 8 3/4' Lateral Section f/13607' To 13,677' 2 Pumps on the hole @ 104 Stks Each 470 GPM, SPP 3950 psi, Rotary Torque 12,500 Top Drive RPM 130-140		
Start Time	18:00	End Time
		18:30
Comment		
Change out flow sensor Gasket		
Start Time	18:30	End Time
		00:00
Comment		
Drill 8 3/4' Lateral Section f/13677' To 13,13891' 2 Pumps on the hole @ 104 Stks Each 470 GPM, SPP 3950 psi, Rotary Torque 12,500 Top Drive RPM 130-140		
Report Start Date	Report End Date	24hr Activity Summary
10/18/2014	10/19/2014	Drill 8 3/4" Lateral F/13891 To 15,041'
Start Time	00:00	End Time
		02:00
Comment		
Drill 8 3/4' Lateral Section f/13891' To 13,978' 2 Pumps on the hole @ 104 Stks Each 470 GPM, SPP 3950 psi, Rotary Torque 12,500 Top Drive RPM 130-140		
Start Time	02:00	End Time
		03:30
Comment		
Trouble Shoot LWD Tools Re-Wipe in Data		
Start Time	03:30	End Time
		04:00
Comment		
Rig Service		
Start Time	04:00	End Time
		06:00
Comment		
Drill 8 3/4' Lateral Section f/13978' To 14,078' 2 Pumps on the hole @ 104 Stks Each 470 GPM, SPP 3950 psi, Rotary Torque 12,500 Top Drive RPM 130-140		

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	End Time	Comment
06:00	07:00	Relogged from 13,984' to 14,078' .
Start Time	End Time	Comment
07:00	08:00	Downlink to change to Frequency 2 for data acquisition.
Start Time	End Time	Comment
08:00	14:00	Drill 8 3/4' Lateral Section f/14,078' To 14,361' 2 Pumps on the hole @ 100 Stks Each 462 GPM, SPP 4000 psi, Rotary Torque 14,500 Top Drive RPM 130
Start Time	End Time	Comment
14:00	14:30	Serviced Rig and Equipment.
Start Time	End Time	Comment
14:30	18:00	Drill 8 3/4' Lateral Section f/14,361' To 14,676' 2 Pumps on the hole @ 100 Stks Each 460 GPM, SPP 4000 psi, Rotary Torque 13,800 Top Drive RPM 130
Start Time	End Time	Comment
18:00	00:00	Drill 8 3/4' Lateral Section f/14,676' To 15,041' 2 Pumps on the hole @ 100 Stks Each 452 GPM, SPP 4000 psi, Rotary Torque 13,800 Top Drive RPM 130
Report Start Date	Report End Date	24hr Activity Summary
10/19/2014	10/20/2014	Drill 8 3/4' Lateral F/15,041' To 15,914'
Start Time	End Time	Comment
00:00	02:30	Drill 8 3/4' Lateral Section f/15,041' To 15,212' 2 Pumps on the hole @ 100 Stks Each 452 GPM, SPP 4000 psi, Rotary Torque 13,800 Top Drive RPM 130
Start Time	End Time	Comment
02:30	03:00	Service Rig
Start Time	End Time	Comment
03:00	06:00	Drill 8 3/4' Lateral Section f/15,212' To 15,401' 2 Pumps on the hole @ 100 Stks Each 452 GPM, SPP 4000 psi, Rotary Torque 13,300 Top Drive RPM 130
Start Time	End Time	Comment
06:00	08:00	Drill 8 3/4' Lateral Section f/15,401' To 15,465' 2 Pumps on the hole @ 100 Stks Each 452 GPM, SPP 4000 psi, Rotary Torque 15,500 Top Drive RPM 150
Start Time	End Time	Comment
08:00	08:30	Downlink.
Start Time	End Time	Comment
08:30	09:00	Drill 8 3/4' Lateral Section f/15,465' To 15,496' 2 Pumps on the hole @ 100 Stks Each 452 GPM, SPP 4000 psi, Rotary Torque 15,500 Top Drive RPM 150
Start Time	End Time	Comment
09:00	09:30	Downlink.
Start Time	End Time	Comment
09:30	13:00	Drill 8 3/4' Lateral Section f/15,496' To 15,614' 2 Pumps on the hole @ 100 Stks Each 452 GPM, SPP 4000 psi, Rotary Torque 15,500 Top Drive RPM 150
Start Time	End Time	Comment
13:00	13:30	Downlink.
Start Time	End Time	Comment
13:30	14:00	Drill 8 3/4' Lateral Section f/15,614' To 15,646' 2 Pumps on the hole @ 100 Stks Each 452 GPM, SPP 4000 psi, Rotary Torque 15,500 Top Drive RPM 150
Start Time	End Time	Comment
14:00	15:00	Troubleshoot power failure on MD Totco System.
Start Time	End Time	Comment
15:00	15:30	Drill 8 3/4' Lateral Section f/15,646' To 15,685' 2 Pumps on the hole @ 100 Stks Each 452 GPM, SPP 4000 psi, Rotary Torque 15,500 Top Drive RPM 150
Start Time	End Time	Comment
15:30	16:00	Serviced Rig and Equipment.

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	End Time	Comment
16:00	18:00	Troubleshoot MD Totco System. Replaced Cable to Wireless Antenna.
Start Time	End Time	Comment
18:00	00:00	Drill 8 3/4' Lateral Section f/15,685' To 15,914' 2 Pumps on the hole @ 100 Stks Each 452 GPM, SPP 4000 psi, Rotary Torque 15,500 Top Drive RPM 150
Report Start Date	Report End Date	24hr Activity Summary
10/20/2014	10/21/2014	Drill 8 3/4' Lateral F/15,914' To 16,818'
Start Time	End Time	Comment
00:00	00:30	Downlink.
Start Time	End Time	Comment
00:30	03:30	Drill 8 3/4' Lateral Section f/15,914' To 16,063' 2 Pumps on the hole @ 100 Stks Each 452 GPM, SPP 4000 psi, Rotary Torque 15,500 Top Drive RPM 150
Start Time	End Time	Comment
03:30	04:00	Serviced Rig and Equipment.
Start Time	End Time	Comment
04:00	05:30	Drill 8 3/4' Lateral Section f/16,063' To 16,157' 2 Pumps on the hole @ 95 Stks Each 436 GPM, SPP 4150 psi, Rotary Torque 17,600 Top Drive RPM 150
Start Time	End Time	Comment
05:30	06:00	Downlink. Reboot LWD Computers.
Start Time	End Time	Comment
06:00	08:00	Drill 8 3/4' Lateral Section f/16,157' To 16,251' 2 Pumps on the hole @ 95 Stks Each 436 GPM, SPP 4290 psi, Rotary Torque 17,600 Top Drive RPM 140-150
Start Time	End Time	Comment
08:00	08:30	Downlink.
Start Time	End Time	Comment
08:30	12:00	Drill 8 3/4' Lateral Section f/16,251' To 16,409' 2 Pumps on the hole @ 95 Stks Each 436 GPM, SPP 4290 psi, Rotary Torque 17,600 Top Drive RPM 140-150
Start Time	End Time	Comment
12:00	15:30	Drill 8 3/4' Lateral Section f/16,409' To 16,534' 2 Pumps on the hole @ 95 Stks Each 436 GPM, SPP 4350 psi, Rotary Torque 16,600 Top Drive RPM 140-150
Start Time	End Time	Comment
15:30	16:00	Serviced Rig and Equipment.
Start Time	End Time	Comment
16:00	18:00	Drill 8 3/4' Lateral Section f/16,534' To 16,610' 2 Pumps on the hole @ 95 Stks Each 436 GPM, SPP 4350 psi, Rotary Torque 16,600 Top Drive RPM 140-150
Start Time	End Time	Comment
18:00	21:00	Drill 8 3/4' Lateral Section f/16,610' To 16,738' 2 Pumps on the hole @ 95 Stks Each 436 GPM, SPP 4150 psi, Rotary Torque 16,600 Top Drive RPM 140-150
Start Time	End Time	Comment
21:00	21:30	Service Rig
Start Time	End Time	Comment
21:30	00:00	Drill 8 3/4' Lateral Section f/16,738' To 16,818' 2 Pumps on the hole @ 95 Stks Each 436 GPM, SPP 4150 psi, Rotary Torque 16,600 Top Drive RPM 140-150
Report Start Date	Report End Date	24hr Activity Summary
10/21/2014	10/22/2014	Drill 8 3/4" Lateral Hole F16,818' To 17,245'
Start Time	End Time	Comment
00:00	02:00	Drill 8 3/4' Lateral Section f/16,818' To 16,863' 2 Pumps on the hole @ 95 Stks Each 436 GPM, SPP 4150 psi, Rotary Torque 16,600 Top Drive RPM 140-150
Start Time	End Time	Comment
02:00	03:30	Service and replace Swab in Mud Pump #1

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	03:30	End Time
	06:00	Comment
		Drill 8 3/4' Lateral Section f/16863' To 16918' 2 Pumps on the hole @ 95 Stks Each 436 GPM, SPP 4150 psi, Rotary Torque 16,600 Top Drive RPM 140-150
Start Time	06:00	End Time
	06:30	Comment
		Drill 8 3/4' Lateral Section f/16,918' To 16,925' 2 Pumps on the hole @ 91 Stks Each 420 GPM, SPP 4150 psi, Rotary Torque 16,600 Top Drive RPM 140-150
Start Time	06:30	End Time
	07:00	Comment
		Serviced Rig and Equipment.
Start Time	07:00	End Time
	08:00	Comment
		Drill 8 3/4' Lateral Section f/16,925' To 16,972' 2 Pumps on the hole @ 91 Stks Each 420 GPM, SPP 4150 psi, Rotary Torque 16,600 Top Drive RPM 140-150
Start Time	08:00	End Time
	08:30	Comment
		Downlink to RSS.
Start Time	08:30	End Time
	09:30	Comment
		Drill 8 3/4' Lateral Section f/16,972' To 17,006' 2 Pumps on the hole @ 91 Stks Each 420 GPM, SPP 4150 psi, Rotary Torque 16,600 Top Drive RPM 140-150
Start Time	09:30	End Time
	10:00	Comment
		Downlink to RSS.
Start Time	10:00	End Time
	12:00	Comment
		Drill 8 3/4' Lateral Section f/17,006' To 17,058' 2 Pumps on the hole @ 91 Stks Each 420 GPM, SPP 4150 psi, Rotary Torque 16,600 Top Drive RPM 140-150
Start Time	12:00	End Time
	13:00	Comment
		Drill 8 3/4' Lateral Section f/17,058' To 17,100' 2 Pumps on the hole @ 91 Stks Each 420 GPM, SPP 4150 psi, Rotary Torque 16,600 Top Drive RPM 140-150
Start Time	13:00	End Time
	13:30	Comment
		Downlink to RSS.
Start Time	13:30	End Time
	17:00	Comment
		Drill 8 3/4' Lateral Section f/17,100' To 17,223' 2 Pumps on the hole @ 91 Stks Each 420 GPM, SPP 4250 psi, Rotary Torque 14,600 Top Drive RPM 140-150
Start Time	17:00	End Time
	17:30	Comment
		Downlink to RSS.
Start Time	17:30	End Time
	18:00	Comment
		Drill 8 3/4' Lateral Section f/17,223' To 17,245' 2 Pumps on the hole @ 91 Stks Each 420 GPM, SPP 4250 psi, Rotary Torque 14,600 Top Drive RPM 140-150
Start Time	18:00	End Time
	23:30	Comment
		Drill 8 3/4' Lateral Section f/17,245' To 17,449' 2 Pumps on the hole @ 91 Stks Each 420 GPM, SPP 4250 psi, Rotary Torque 14,600 Top Drive RPM 140-150
Start Time	23:30	End Time
	00:00	Comment
		Directional Work, Survey
Report Start Date	Report End Date	24hr Activity Summary
10/22/2014	10/23/2014	Drill 8 3/4" Lateral Section F/17,245' To 17,977', TD for Lateral Section. Circulate bottoms up, Raised mud weight from 14.0 ppg to 14.3 ppg. added Lube to bring to 2% in OBM.
Start Time	00:00	End Time
	00:30	Comment
		Drill 8 3/4' Lateral Section f/17,449' To 17,478' 2 Pumps on the hole @ 91 Stks Each 420 GPM, SPP 4250 psi, Rotary Torque 14,600 Top Drive RPM 140-150
Start Time	00:30	End Time
	01:00	Comment
		Directional Work Survey,
Start Time	01:00	End Time
	04:00	Comment
		Drill 8 3/4' Lateral Section f/17,478' To 17,572' 2 Pumps on the hole @ 91 Stks Each 420 GPM, SPP 4250 psi, Rotary Torque 14,600 Top Drive RPM 140-150
Start Time	04:00	End Time
	04:30	Comment
		Service Rig

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

Start Time	04:30	End Time
		06:00
Comment Drill 8 3/4' Lateral Section f/17,572' To 17,667' 2 Pumps on the hole @ 91 Stks Each 420 GPM, SPP 4250 psi, Rotary Torque 14,600 Top Drive RPM 140-150		
Start Time	06:00	End Time
		13:30
Comment Drill 8 3/4' Lateral Section f/17,667' To 17,977' TD for Lateral Section. 2 Pumps on the hole @ 91 Stks Each 420 GPM, SPP 4250 psi, Rotary Torque 14,600 Top Drive RPM 140-150		
Start Time	13:30	End Time
		15:30
Comment Circulating bottoms up. Adding 2% Lube to system. Downlinking to shut off Deflection to RSS.		
Start Time	15:30	End Time
		18:00
Comment Circulating Bottoms Up, Raising Mud Weight from 14.0 ppg to 14.3 ppg.		
Start Time	18:00	End Time
		00:00
Comment Circulating Bottoms Up, Raising Mud Weight from 14.0 ppg to 14.3 ppg.		
Report Start Date	Report End Date	24hr Activity Summary
10/23/2014	10/24/2014	Performing Clean up Cycle cond. Mud weighing up mud to 14.5 ppg. Flow Check - No Flow. POH 5 Stands. Pump Dry Job. POH from 17,536'
Start Time	00:00	End Time
		01:00
Comment Circulating Bottoms Up, Raising Mud Weight from 14.0 ppg to 14.3 ppg.		
Start Time	01:00	End Time
		02:00
Comment Shut down pumps and flow check. Pull stand of pipe to see if pipe pulled free. pipe pulled free. after 45 min well flowing @ 1 bbl/hr.		
Start Time	02:00	End Time
		05:30
Comment Circulating Bottoms Up, Raising Mud Weight from 14.3 ppg to 14.5 ppg.		
Start Time	05:30	End Time
		06:00
Comment Service Rig		
Start Time	06:00	End Time
		08:30
Comment Circulating Bottoms Up, Raising Mud Weight from 14.3 ppg to 14.5 ppg.		
Start Time	08:30	End Time
		09:30
Comment Flow Check. No Flow.		
Start Time	09:30	End Time
		10:30
Comment Trip out of hole from 17,977' to 17,536' at 10 min/Stand, pulling 250-280K with spikes to 310K.		
Start Time	10:30	End Time
		11:30
Comment Mixed and pumped dry job.		
Start Time	11:30	End Time
		15:30
Comment Trip out of hole from 17,536' to 13,060'. Monitoring displacement on Trip Tank, hole taking correct amount of fluid displacement.		
Start Time	15:30	End Time
		16:00
Comment Serviced Rig and Equipment.		
Start Time	16:00	End Time
		18:00
Comment Trip out of hole from 13,060' to 10,000'. Monitoring displacement on Trip Tank, hole taking correct amount of fluid displacement.		
Start Time	18:00	End Time
		20:00
Comment Trip out of hole from 10,000 ' 7,868' Monitoring displacement on Trip Tank, hole taking correct amount of fluid displacement.		
Start Time	20:00	End Time
		20:30
Comment Flow Check While filling trip tank		
Start Time	20:30	End Time
		22:00
Comment Slip & Cut Drill Line		
Start Time	22:00	End Time
		22:30
Comment Service Rig		
Start Time	22:30	End Time
		00:00
Comment Pooh Laying down singles.		

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

--

Daily Operations

Report Start Date	Report End Date	24hr Activity Summary
10/24/2014	10/25/2014	POOH to Shoe Flow Check, Slip and Cut Drill Line, POOH Laying Down Drill Pipe & BHA. RIH and L/D Drill Pipe out of Derrick.
Start Time	End Time	Comment
00:00	06:00	POOH Laying Down 5" Pipe from 6,926' to 1,000'.
Start Time	End Time	Comment
06:00	07:00	POOH Laying Down 5" Pipe from 1,000' to 235'.
Start Time	End Time	Comment
07:00	07:30	Removed Rotating Head Rubber.
Start Time	End Time	Comment
07:30	11:00	POH L/D 1 Jt HWDP, Reamer, Float Sub, TOMAX, NDT, SAGR, and SST. Broke off Bit. L/D HEL/IDS, GWAR, and RSS.
Start Time	End Time	Comment
11:00	11:30	Serviced Rig and Equipment.
Start Time	End Time	Comment
11:30	14:00	M/U Bit and Bit Sub w/ Float. Trip in hole with 35 Stands of 5" Drill Pipe.
Start Time	End Time	Comment
14:00	18:00	POH Laying Down 5" Drill Pipe, Monitoring displacement on Trip Tank.
Start Time	End Time	Comment
18:00	19:30	POH Laying Down 5" Drill Pipe, Monitoring displacement on Trip Tank.
Start Time	End Time	Comment
19:30	22:00	Trip in hole with 35 Stands of 5" Drill Pipe.
Start Time	End Time	Comment
22:00	00:00	POH Laying Down 5" Drill Pipe, Monitoring displacement on Trip Tank.
Report Start Date	Report End Date	24hr Activity Summary
10/25/2014	10/26/2014	POOH Laying Down Drill Pipe. Pulled Wear Bushing. PJSM with Franks. R/U Casing Tongs and Equipment. Run 5-1/2" Production Casing.
Start Time	End Time	Comment
00:00	04:00	POH Laying Down 5" Drill Pipe, Monitoring displacement on Trip Tank. ST-80 Inoperable. Using Rotary Tongs and backing out Drill Pipe with Pipe Wrench.
Start Time	End Time	Comment
04:00	04:30	Serviced Rig and Equipment.
Start Time	End Time	Comment
04:30	06:00	Trip in hole with 35 Stands of 5" Drill Pipe.
Start Time	End Time	Comment
06:00	10:30	POH Laying Down 5" Drill Pipe, Monitoring displacement on Trip Tank. ST-80 Inoperable. Using Rotary Tongs and backing out Drill Pipe with Pipe Wrench.
Start Time	End Time	Comment
10:30	11:30	M/U Bushing Puller and pulled Wear Bushing.
Start Time	End Time	Comment
11:30	13:30	Held PJSM wit Franks, Tennaris Rep, Halliburton Serviceman. R/U CRT, Bale Extensions, Elevators, Casing Tongs and Equipment.
Start Time	End Time	Comment
13:30	18:00	Make Up Shoe Track, Reaming Shoe, 1 Jt csg, Float Collar, 1 Jt csg, Landing Collar, 2 Jts csg, RSI Sleeve. Test Floats. Run 5.5", 20# P-110 XP BTC casing. Make Up casing @ 15 RPM'S Per Deep Well thread rep. Run casing F/ surface to 2663'.
Start Time	End Time	Comment
18:00	18:30	PJSM with rig crew and casing crew
Start Time	End Time	Comment
18:30	00:00	Run 5.5", 20# P-110 XP BTC casing. Make Up casing @ 15 RPM'S Per Deep Well thread rep. Run casing F/ surface to 7544' Fill every 50 Joints

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

--

Daily Operations

Report Start Date	Report End Date	24hr Activity Summary
10/26/2014	10/27/2014	Run 5.5" Production Casing.
Start Time	End Time	Comment
00:00	04:30	Run 5.5", 20# P-110 XP BTC casing. Make Up casing @ 15 RPM'S Per Deep Well thread rep. Run casing F/ 7,544'to 10,600' Fill every 50 Joints
Start Time	End Time	Comment
04:30	05:00	Fill Casing and Install Rotating Head Rubber
Start Time	End Time	Comment
05:00	05:30	Run 5.5", 20# P-110 XP BTC casing. Make Up casing @ 15 RPM'S Per Deep Well thread rep. Run casing F/ 10,600 'to 11,313' Fill every 50 Joints
Start Time	End Time	Comment
05:30	06:00	Service Rig
Start Time	End Time	Comment
06:00	13:30	Run 5.5", 20# P-110 XP BTC casing. Make Up casing @ 15 RPM'S Per Deep Well thread rep. Run casing F/ 11,313 'to 17,816'. Fill every 50 Joints
Start Time	End Time	Comment
13:30	14:00	Removed Rotating Head Rubber.
Start Time	End Time	Comment
14:00	15:00	Run 5.5", 20# P-110 XP BTC casing. Make Up casing @ 15 RPM'S Per Deep Well thread rep. Run casing F/ 17,816 'to 17,932'. M/U Casing Hanger/Landing Joint.
Start Time	End Time	Comment
15:00	15:30	Filled Casing, Circulated down with Landing Joint, Landed Casing Hanger in wellhead.
Start Time	End Time	Comment
15:30	16:30	R/D Casing Elevators, Bale Extensions, and TAWG Tool.
Start Time	End Time	Comment
16:30	17:00	M/U Franks Cementing Head.
Start Time	End Time	Comment
17:00	17:30	Serviced Rig and Equipment.
Start Time	End Time	Comment
17:30	20:00	Circulating at 5.0 BPM, Rotating 10 RPM.
Start Time	End Time	Comment
20:00	00:00	Wait on Cement Delivery
Report Start Date	Report End Date	24hr Activity Summary
10/27/2014	10/28/2014	Ran and Cemented 5.5" Production Casing. R/D Cement Lines & Cement Head.
Start Time	End Time	Comment
00:00	01:00	Wait on Cement to be delivered
Start Time	End Time	Comment
01:00	01:30	PJSM With rig crew and cementers
Start Time	End Time	Comment
01:30	07:30	Fill Lines, Pressure test to 9000 psi. Pump 40 BBLS Tuned Spacer at 14.8 ppg. Pump 326 BBLS 15.2 ppg (1265 SX) Tergovis. Pump 577 BBLS of 15.7 ppg (2090 SX) Primary Cement, Drop Plug, Displace Cement with 395 BBLS 8.33 ppg Water. Bumped Plug with 6,470 psi. Floats Holding.
Start Time	End Time	Comment
07:30	08:30	R/D Halliburton Lines and Equipment.
Start Time	End Time	Comment
08:30	09:30	R/D Franks Cementing Head.
Start Time	End Time	Comment
09:30	12:00	Backed out and Laid Down Landing Joint.
Start Time	End Time	Comment
12:00	14:30	Made multiple attempts to remove Rotating Head Rubber. Removed Rotating Head Rubber.

NEWFIELD**Summary Rig Activity****Well Name: Powvitch 15-13-12-3-2WB**

--

Start Time	14:30	End Time	16:30	Comment
				M/U Pack-Off Running Tool. Seat Packoff and run in Anchor Ram Bolts.
Start Time	16:30	End Time	17:00	Comment
				Serviced Rig and Equipment.
Start Time	17:00	End Time	18:00	Comment
				M/U Rods, Installed Back Pressure Valve. Break down rods.
Start Time	18:00	End Time	00:00	Comment
				Nipple Down Choke Line BOP & Kill Line Clean Mud Tanks. (Release Rig @ Midnight 00:00 10-28-14)